

# Effects of uncertainty in soil properties on simulated hydrological state and fluxes at different spatio-temporal scales

Gabriele Baroni<sup>1,2</sup>, Matthias Zink<sup>1</sup>, Rohini Kumar<sup>1</sup>, Luis Samaniego<sup>1</sup>, Sabine Attinger<sup>1,2</sup>

<sup>1</sup> Helmholtz Centre for Environmental Research - UFZ, Department Computational Hydrosystems, Permoserstrasse 15, 04318 Leipzig, Germany

<sup>2</sup> Institute of Earth and Environmental Sciences, University of Potsdam, Karl-Liebknecht-Str. 24-25, 14476 Potsdam, Germany

*Correspondence to:* Gabriele Baroni (gabriele.baroni@ufz.de)

**Abstract.** Soil properties show high heterogeneity at different spatial scales and their correct characterization remains a crucial challenge over large areas. The aim of the study is to quantify the impact of different types of uncertainties that arise from the unresolved soil spatial variability on simulated hydrological states and fluxes. Three perturbation methods are presented for the characterization of uncertainties in soil properties. The methods are applied on the soil map of the upper Neckar catchment (Germany), as example. The uncertainties are propagated through the distributed hydrological model mHM to assess the impact of the simulated state and fluxes. The model outputs are analysed by aggregating the results at different spatial and temporal scales. These results show that the impact of the different uncertainties introduced in the original soil map is equivalent when the simulated model outputs are analysed at the model grid resolution (i.e., 500 m). However, several differences are identified by aggregating state and fluxes at different spatial scales (by subcatchments of different sizes or coarsening the grid resolution). Streamflow is only sensitive to the perturbation of long spatial structures while distributed state and fluxes (e.g., soil moisture and groundwater recharge) are only sensitive to the local noise introduced to the original soil properties. A clear identification of the temporal and spatial scale for which finer resolution soil information is (or is not) relevant is unlikely to be universal. However, the comparison of the impacts on the different hydrological components can be used to prioritize the model improvements in specific applications, either by collecting new measurements or by calibration and data assimilation approaches. In conclusion, the study underlines the importance of a correct characterization of uncertainty in soil properties. With that, soil maps with additional information regarding the unresolved soil spatial variability would provide a strong support to hydrological modelling applications.

## 1 Introduction

The prediction of mathematical environmental models is affected by uncertainty which arises from inadequate conceptual and mathematical representations of the processes (uncertainty in model structure), inadequate and insufficient knowledge and characterization of system forcing (uncertainty in boundary conditions) and limitations in the measurements or identification of model parameters (parameter uncertainty) (Beven, 2007, 2001; Refsgaard et al., 2007; Tartakovsky et al.,

2012). The need to quantify the predictive uncertainty has led to the development of probabilistic (stochastic) frameworks in many disciplines of environmental sciences and engineering (Altarejos-García et al., 2012; Di Baldassarre et al., 2010; Dubois and Guyonnet, 2011; Savage et al., 2016; Seiller and Anctil, 2014). Nowadays rigorous quantification of uncertainty is an integral part of science-based predictions and decision support systems (Beven, 2007; Farmer and Vogel, 2016; Liu and Gupta, 2007; Montanari and Koutsoyiannis, 2012).

In hydrological studies, several sources of uncertainty have been studied ranging from atmospheric forcing (Aguilar et al., 2010; Raleigh et al., 2015; Samain and Pauwels, 2013; Vázquez and Feyen, 2003; Zhu et al., 2013) to geology structures (Comunian et al., 2015; Hansen et al., 2014; He et al., 2015; Zech et al., 2015). Among these, the uncertainty related to the soil properties has been widely analysed. Soil properties show in fact high heterogeneity at different spatial scales with a hierarchy of spatial structures (Burrough, 1983; Heuvelink and Webster, 2001; Vogel and Roth, 2003) and complex interactions with environmental conditions (Lin, 2010). Despite international initiatives exist to improve the current status of soil characterization (Chaney et al., 2016; Heuvelink et al., 2016; Pelletier et al., 2016; Shangguan et al., 2014), detailed information of the spatial heterogeneity of the soil properties over large areas remains a crucial challenge. For this reason, an increasing number of hydrological modelling studies aim to integrate the uncertainty in soil properties that arise from the unresolved spatial heterogeneity for a proper quantification of the uncertainty of the model results. Since soil properties play a crucial role in the entire water cycle, this topic crosses research fields from lower atmosphere (De Lannoy et al., 2014; Garrigues et al., 2015; Guillod et al., 2013; Osborne et al., 2004; Yu et al., 2014) and surface water (Anderson et al., 2006; Geza and McCray, 2008; Li et al., 2013; Livneh et al., 2015; Salazar et al., 2008) to water and solute transport to groundwater systems (Besson et al., 2011; Hennings, 2002; Yu et al., 2014).

Despite its relevance, however, relative simple assumptions are adopted to characterize the uncertainty in soil properties and to understand its effect on the hydrological response. In several studies the uncertainty is characterized based on relatively small number of scenarios (Baroni et al., 2010; Christiaens and Feyen, 2001; Guber et al., 2009; Herbst et al., 2006; Hohenbrink and Lischeid, 2015; Islam et al., 2006; Mirus, 2015; Moeys et al., 2012) or by a simple random noise (i.e., variance) added to the original soil properties (Arnone et al., 2016; Chaney et al., 2015; Deng et al., 2009; Garrigues et al., 2015; Han et al., 2014; Loosvelt et al., 2011). Other studies explicitly integrate the complex heterogeneity of the subsurface and the uncertainty in the soil properties is characterized based on spatial correlated random fields i.e., specifying variance and correlation length (Binley et al., 1989; Fan et al., 2016; Fiori and Russo, 2007; Merz and Plate, 1997; Meyerhoff and Maxwell, 2011). Moreover, many of above-mentioned studies focused on the effect of the uncertainty in soil properties on a selected hydrologic variable at specific temporal and spatial scale e.g., rainfall-runoff events (e.g., Arnone et al., 2016; Fan et al., 2016), simulated evapotranspiration (e.g., Garrigues et al., 2015), soil moisture distributions (e.g., Liao et al., 2014) or groundwater recharge (e.g., Moeys et al., 2012). Simultaneous assessments of different hydrological components of the water balance at different spatial and temporal scales are rare. In addition, due to the different settings used in the studies, it is not possible to draw general conclusions about the role of the uncertainty in soil properties. In some cases the refined spatial information of soil properties does not contribute to a more accurate prediction (e.g., Li et al., 2013). In other studies

the results showed to be very sensitive to the soil properties (e.g., Livneh et al., 2015). These controversial results foster the debate on the need (or not) of finer resolution soil maps in the different modelling applications (Baveye, 2002; Baveye and Laba, 2015; Heuvelink and Webster, 2001).

In the present study, we investigate impacts of uncertainty of soil properties on hydrological states and fluxes. Uncertainty in soil properties is characterized by three different methods that are consistent in the added noise (i.e., variance), but they differ in the perturbation of the soil spatial structure i.e., correlation length. The first two methods were previously used in other studies (e.g., Fan et al., 2016; Han et al., 2014). The third method is developed in the present study to introduce small scale soil variability while preserving the original spatial patterns. By that, we hypothesize that local responses of a hydrological system, like evapotranspiration and soil moisture, will be strongly impacted by the uncertainty introduced at small spatial scale. However, integrated responses like the streamflow aggregate local responses over large areas. We hypothesize that this integrated response will be less impacted by soil properties uncertainty. The extent of the impact is expected to decrease with increasing the aggregation area and to disappear at a specific domain size. In such a condition, the system is stated to be spatially ergodic as the model output is not any more sensitive to the perturbation i.e., we have the equivalence between spatial and ensemble statistics (Dagan, 1989; Rubin, 2003).

The paper is structured as follow. First, the perturbation methods used for the characterization of the uncertainty of the soil properties are presented. The specific case study is described presenting the catchment, the data used and the specific settings of the perturbation methods. The hydrological model is then introduced together with the uncertainty analysis conducted for the assessment of the effect of the uncertainty in soil properties on the simulated state and fluxes. The results are discussed in section 3 focusing on the effect of the differences detected at different spatial and temporal scales. Final remarks are presented in the conclusions section.

## 2 Methods

### 2.1 Soil perturbation methods

In this section, the three statistical methods to characterize the uncertainty in soil properties are presented. A sketch for describing the methods is provided in Figure 1, where one hypothetical horizontal transect through a soil map with three soil units characterized by different percentages of sand is shown as example.

The first method (hereafter denoted as Random Error method - RE) is based on the assumption that the nominal value in each soil unit is the only source of uncertainty while the spatial patterns (i.e., soil units) are considered to be correct. To fulfil this assumption, a simple Gaussian random noise is defined with zero mean and given variance (Figure 1, step R1). Random values are sampled from the distribution and added to the nominal value of soil properties of each soil unit (Figure 1, step R2). This approach was commonly used in several studies with the focus of understanding the effect of the soil properties in forward uncertainty analysis of model response (e.g., Deng et al., 2009) or for creating the forward ensemble in data assimilation tests (e.g., Han et al., 2014).

In the second method (hereafter denoted as Spatially Correlated method - SC), a similar assumption of additive random values is considered. However, it is also assumed that the uncertainty arises from the presence of smaller soil units that have not been detected in the original soil map (Hennings, 2002). To fulfil this assumption, a spatial structure (i.e., variance and correlation length - CL) is defined (Figure 1, step S1). Based on that, a spatially correlated random field with zero mean is created (Figure 1, step S2) and added to the original soil map (Figure 1, step S3). Random fields are used in this approach to create variability as discussed by Goovaerts (2001) with which simulated short-range components well represent the complexity of the small-scale spatial structure. Readers interested in the details of the generation of random fields are referred to Deutsch and Journel (1998), Goovaerts (1997) and Isaaks and Srivastava (1989).

Finally, in the third approach (hereafter denoted as Conditional Points method - CP), it is assumed that the nominal value of the original soil units represents some point locations within this unit but their positions are unknown. The uncertainty arises from the spatial variability within these point locations that is not resolved in the original soil map. To fulfil this assumption, points are randomly distributed over the soil map and the soil properties are associated to each position (Figure 1, step S1). These values are used to calculate the spatial structure i.e., the empirical variogram (Figure 1, step S2). A variogram model is fitted and a conditional random field is created using the sampled locations as conditional points (Figure 1, step S3). It has to be noted that the CP method has some similarity with the pilot points approach used for the calibration of hydrogeological models (Carrera et al., 2005). The main difference is the use in this method of new points at each iteration i.e., the points are located in different positions for each created conditional random field.

It is noteworthy that additional statistical methods for the analysis of soil map are presented in literature (Goovaerts, 2011; Heuvelink et al., 2016; Kempen et al., 2009; Minasny and McBratney, 2016; Odgers et al., 2014). However, the aim of these methods is to downscale/disaggregate the information available in the original soil map and not to characterize its uncertainty. For this reason, these statistical methods are based on environmental covariates (i.e., environmental variables that co-vary with soil variability) known at higher resolution (i.e., digital elevation model or land use) and they require relative well knowledge of the soil formation and the specific settings to adopt (Kerry et al., 2012; Nauman and Thompson, 2014; Subburayalu et al., 2014; Du et al., 2015). On the contrary, the three methods selected and developed in the present study represent relative simple approaches only based on the information available in the original soil map. They can be applied for the characterization of any type of soil properties (e.g., texture, saturated hydraulic conductivity, soil depth etc.) and they reflect different assumptions regarding the uncertainties in the soil properties. For this reason, they can be tuned to characterize uncertainty for soil maps of any scales and they can be easily used to any modelling studies (e.g., sensitivity analysis or data assimilation). Combinations of the methods can also be considered when needed i.e., soil map affected by different types of uncertainties.

## 2.2 Study area

The numerical experiments are conducted in the upper Neckar catchment (Figure 2) that was extensively investigated in previous hydrological studies (Kumar et al., 2010; Samaniego et al., 2010a, 2010b; Wöhling et al., 2013b). This catchment is

located in the central uplands of Germany and comprises a catchment area of approximately 4000 km<sup>2</sup>. The catchment has a gradient in elevation from 250 m to 1015 m a.s.l. with a mean elevation of 550 m. The catchment is prevalently characterized by cropped fields and forest but with a remarkable high degree of urbanization (11%). The long-term mean annual precipitation is around 920 mm a<sup>-1</sup>.

5 Observed meteorological data, i.e., precipitation as well as minimum, maximum and average daily temperature, were provided by the German Meteorological Service (DWD; [www.dwd.de/](http://www.dwd.de/)). These observations have been interpolated to a 4 x 4 km forcing dataset for the hydrological model using external drift kriging. The potential evapotranspiration is estimated using the Hargreaves-Samani method (Hargreaves and Samani, 1985). Data characterizing the land surface are a digital elevation model (Federal Agency for Cartography and Geodesy), a soil map at the scale 1:1000000 (Federal Institute for  
10 Geosciences and Natural Resources - BGR), a hydrogeological map (Federal Institute for Geosciences and Natural Resources - BGR), and land cover information (CORINE, European Environmental Agency - EEA, 2009). The soil map used in the present study (BGR 1:1000000) contains soil texture (percentage of sand, clay and silt) and bulk density [g cm<sup>-3</sup>] for each soil unit (i.e., polygon of the soil map) and for each soil horizon. For this study, these vertical discretization is not accounted for and the soil properties of each soil horizon are averaged to the total soil depth of 2 m (Figure 3). The soil  
15 within the catchment is prevalently clay loam but with a relatively high spatial variability represented by 29 soil units (polygons) of different size within the catchment. All these data are discretized to a spatial resolution of 100 x 100 m<sup>2</sup>. Readers interested in more details on data-set and the processing may refer to Kumar et al. (2010), Samaniego et al. (2010b) and Zink et al. (2016). The spatial distributions of cumulative rain, potential evapotranspiration, land use and the mean annual leaf area index are shown in the supplementary material (see Figure S1).

## 20 2.3 Settings of the soil perturbation methods

In this section, the specific settings of each statistical perturbation method used for the characterization of the soil properties are described. The three methods are used independently to generate three different ensembles to identify the impact of the different uncertainties introduced in the original soil map on simulated state and fluxes.

Considering the random error method (see Figure 1), a Gaussian random additive noise is used with standard deviation 7 [%]  
25 and 0.07 [g cm<sup>-3</sup>] for soil texture (sand and clay) and bulk density, respectively (Table 1). A correlated sampling design is used to preserve the correlation between the original soil properties (e.g., negative correlation between sand and clay). These noises are selected to perturb the soil properties within the original soil class i.e., it is assumed that the exact values of the soil properties are unknown but the soil class (e.g., clay loam) is correct. Similar ranges were also applied in other studies (Han et al., 2014; Hennings, 2002).

30 For the spatially correlated method (see Figure 1), the parameters for the variogram and co-variogram models are selected to be consistent with the perturbation introduced in the random error method (Table 1). In particular, exponential variogram models are prescribed with the same effective noises used in the random error method (i.e., standard deviation 7 [%] and 0.07 [g cm<sup>-3</sup>] for texture and bulk density, respectively) and preserving the correlation between the original soil properties.

The correlation length of 3 km is selected to represent relative small spatial patterns that were not captured by the original soil map i.e., patterns smaller than most of the soil units (Figure 3). The variogram and co-variograms models selected are shown as supplementary material (see Figure S2).

Finally, considering the conditional points method (see Figure 1), tests are conducted to identify the density of the conditional points within the soil map. One sample at every  $3 \times 3 \text{ km}^2$  is found to introduce the same noise prescribed by the other two methods (Table 1). A stratified spatial random sample is used to distribute the points within each soil units. Based on these, two nested exponential variogram and co-variogram models are fitted to the experimental variograms based on ordinary least-squares residuals (Pebesma, 2004). These variogram models are used to create the conditional random fields. The experimental variograms and the fitted models for one realization (i.e., one random field) are shown, exemplarily, in the supplementary material (Figure S3).

In each method, the perturbed values are forced to a realistic range i.e., texture values between 0% and 100% and the sum of textural fractions equal 100%. By that, it has to be noted that these constrains (i) could modify the Gaussian noise introduced and (ii) could lower the uncertainty in areas of the basin where the actual values are close to the bounds. These constrains did not affect the spatial patterns of the generated soil maps of the present study due to the relative small perturbation introduced and the presence of limited areas with extreme texture conditions. However, attention has to be paid in cases where these features are more relevant.

For each method, an ensemble of 100 realizations is created to characterize the uncertainty in soil properties. The analysis is conducted with the statistical software R 3.2.x (R Core Team, 2013) using add-on packages (Pebesma, 2004). The multi-variate conditional random fields were generated with GCOSIM3D code (Gómez-Hernández and Journel, 1993).

## 2.4 The hydrological model mHM

The effect of the uncertainty in soil properties as characterized by the three perturbation methods on hydrological states and fluxes is analysed using the hydrological model mHM. The mesoscale Hydrological Model mHM (Kumar et al., 2013; Samaniego et al., 2010b) is an open source, spatially distributed hydrologic model ([www.ufz.de/mhm](http://www.ufz.de/mhm)). It considers interception, snow accumulation and melting, soil water retention, evapotranspiration, percolation, and runoff generation as main hydrologic processes. The Multiscale Parameter Regionalization (MPR) embedded in mHM allows for the application of the model at various locations and scales (Kumar et al., 2013; Rakovec et al., 2016). MPR accounts for sub-grid variabilities by estimating model parameters at the scale of the morphological input, e.g.  $100 \times 100 \text{ m}^2$ . Subsequently, these parameters are upscaled to the model resolution based on different average rules (e.g., harmonic mean, arithmetic mean etc.). For a detailed model description and the MPR scheme interested readers may refer to Samaniego et al. (2010b) and Kumar et al. (2013). For this study, the soil within mHM is discretized into 3 layers, the first layer is 5 cm, the second layer is 25 cm and the third has a variable thickness. The depth of latter is based on the information provided by the soil map (2 m). Based on the soil textural properties, mHM estimates effective parameters for porosity, hydraulic conductivity, field capacity and

permanent wilting point using a set of pedotransfer functions (Cosby et al., 1984; Twarakavi et al., 2009; van Genuchten, 1980; Zacharias and Wessolek, 2007). The list of the functions is reported in Table S1 in the supplementary material.

The model was calibrated and validated in previous studies showing very good capability to match streamflow measurements at catchment of different sizes (Kumar et al., 2010, 2013; Samaniego et al., 2010b; Wöhling et al., 2013b).

- 5 The same parameterization is used for the present study. We establish the mHM over the Upper Neckar catchment at 500 m spatial resolution resulting in 16432 grid cells. The model run is conducted at an hourly time scale. All simulations are conducted with a five year model spin up time (1985 - 1989) to minimize the effect of inappropriate initial conditions. The implications of uncertain soil properties are evaluated showing the uncertainty in simulated routed streamflow ( $SF$ ), generated runoff at every grid cell ( $Q$ ), actual evapotranspiration ( $AET$ ), volumetric soil moisture ( $SM$ ) in the upper 30 cm and groundwater recharge ( $GWR$ ). For each perturbation method 100 simulations were performed which yield a total of 300 simulations. The results obtained during one year of forward simulation (1990) are shown, as example. This year is selected to represent average climate condition of the area (i.e., two rain seasons concentrated in spring and fall and a relatively dry summer season) but with a relatively high variability within the catchment (see Figure S1 in supplementary material).

## 2.5 Uncertainty analysis at different spatio-temporal scales

- 15 The uncertainty in simulated states and fluxes is quantified based on the coefficient of variation ( $CV$  [%]) to allow comparability between the results obtained in the different model outputs. Assuming a generic variable  $v$  representing simulated state or fluxes,  $CV$  is calculated as follow:

$$CV_{i,t}^m = \frac{\sigma_{i,t}^m}{\mu_{i,t}^m} 100 \quad (1)$$

20

where  $\sigma$  is the standard deviation of the variable  $v$  at each cell  $i$  and time  $t$  calculated based on each perturbation method  $m$  (i.e., random error method, spatially correlated method or conditional points method) as follow:

$$\sigma_{i,t}^m = \sqrt{\frac{1}{N_{ens}} \sum_{j=1}^{N_{ens}} (v_{i,t}^{m,j} - \mu_{i,t}^m)^2} \quad (2)$$

25

with  $N_{ens}$  the number of ensemble members (i.e., 100),  $j$  one single ensemble member and  $\mu$  representing the mean of the ensemble at each cell  $i$  and time  $t$  calculated as follow:

$$\mu_{i,t}^m = \frac{1}{N_{ens}} \sum_{j=1}^{N_{ens}} v_{i,t}^{m,j} \quad (3)$$

30

The values obtained with the three perturbation methods are compared by aggregating the simulated states and fluxes at different spatial and temporal resolutions. In particular, four analyses are conducted (Table 2).

In analysis #1, the spatial variability of the uncertainty of the simulated state and fluxes is presented i.e., depending on the geographical location within the catchment. In this case the average  $CV$  calculated for the entire simulation period (i.e., one year) in each grid cell is quantified as follow:

$$\overline{CV}_i^m = \frac{1}{T} \sum_{t=1}^T CV_{i,t}^m \quad (4)$$

where  $T$  is the number of simulations time steps (i.e., 365 days). This value is used to represent and discuss the average uncertainty obtained in the specific cell  $i$  and its spatial variability within the catchment.

In analysis #2 (Table 2), the daily temporal dynamic of the uncertainty obtained at each grid cell is discussed. For this reason the  $CV_{i,t}^m$  calculated at the daily time step (Eq. 1) is directly compared for two representative grid cells selected within the catchment (see Figure 2, point A and B).

The uncertainty on simulated states and fluxes is further compared by aggregating the model outputs at different resolution to identify the effect of the spatial scale on the performance of the model as discussed by Refsgaard et al. (2016). In particular, for use in analysis #3 (Table 2), subcatchments of different sizes are defined based on 36 gauging stations located within the catchment (see Figure 2). The effect of the uncertainty in soil properties to the streamflow routed to the outlet (SF) of each subcatchment is then compared. For the other simulated model outputs (i.e., evapotranspiration, soil moisture and groundwater recharge), the values of each grid cell within the subcatchment are aggregated calculating the average of simulated model output  $v$  obtained at the finer resolution as follow:

$$\bar{v}_{sc,t}^{m,j} = \frac{1}{N_{sc}} \sum_{i=1}^{N_{sc}} v_{i,t}^{m,j} \quad (5)$$

where  $N_{sc}$  is the number of grid cells within the subcatchment  $sc$ . The value  $\bar{v}_{sc,t}^{m,j}$  is used in Eq. (1 - 4) to calculate and compare the coefficient of variation of the mean simulated state and fluxes for the subcatchments of different sizes.

Finally, in analysis #4 (Table 2), the effect of the aggregation of states and fluxes at different resolutions is further analysed based on the approach shown by Hansen et al. (2014) and Rasmussen et al. (2012). In this case, the generic model output  $v$  is averaged coarsening the model grid at different resolutions  $r_d$  (i.e.,  $r_2 = 2$  km,  $r_4 = 4$  km,  $r_8 = 8$  km,  $r_{16} = 16$  km,  $r_{32} = 32$  km). These values are substituted in Eq. (1 - 3) to calculate the coefficient of variation in each new coarsened grid cell  $i$ . In this analysis the average of the  $CV$  across the entire domain and over the entire simulation period (i.e., 365 days) is calculated as a summary statistic as follow:



$$\overline{CV^{m,r_d}} = \frac{1}{T} \sum_{t=1}^T \frac{1}{N_r} \sum_{i=1}^{N_r} CV_{i,t}^{m,r_d} \quad (6)$$

with  $N_r$  representing the number of cell  $i$  within the coarsened domain  $r_d$ .

- In addition to the spatial dimension, in this study, the same procedure is also repeated for each spatial aggregation  $r_d$  considering a time aggregation  $t_d$ . In particular, all the simulated model outputs  $v$  obtained at daily time step are averaged at  $t_{10} = 10$  days,  $t_{30} = 30$  days,  $t_{60} = 60$  days,  $t_{120} = 120$  days and  $t_{180} = 180$  days, respectively. These values are substituted in Eq. (1-4) to calculate the coefficient of variation in each temporal aggregation  $t_d$  and they are considered to represent the uncertainty in the simulated state and fluxes in case the averaged values are used in the assessment of the performance of the model.
- The four analyses described above are conducted based on the results of 100 simulations obtained with the distributed hydrological model for each perturbation methods. A total of 300 simulations, analysed in 12 cases, are discussed in the results section (Table 2).

### 3. Results and discussion

#### 3.1 Perturbation of the soil properties

- Three methods are used to perturb the values of the original soil map i.e., sand [%], clay [%] and bulk density [ $\text{g cm}^{-3}$ ]. This section discusses the results obtained on clay percentage exemplarily. Similar results are obtained for the other soil properties and for the related soil hydraulic parameters (see supplementary material, Figure S4 – S6). For each method, Figure 4 (top row) shows one realization of the perturbed clay percentage. In addition (Figure 4, bottom row), one transect along the catchment is selected and the clay percentage of the original soil map, of one realization and of the ensemble spread (95% confidence interval) are shown. The longitudinal transect was selected to capture the strong variability in the soil units detected along this direction (see Figure 3).

- The random error method (RE) preserves the shapes of the soil units and perturbs just the nominal values. The results therefore show how the contrasts between the soil units are modified and in some cases are exaggerated. For this reason, it is noteworthy to observe that this method could create non-realistic spatial patterns since soil properties usually show smother changes in space. The results obtained based on the spatially correlated method (SC) show that the shapes of the soil units are still highly identifiable and the sharp changes between the units are still preserved. With this method, however, the random fields superimposed to the original soil map were selected with a correlation length of 3 km (see section 2.3). For this reason, smaller spatial structures than the original soil units are introduced and the sharp changes in the soil properties are not uniformly distributed all over the soil unit. Finally, considering the results obtained with the conditional points method (CP), the results show that the soil units are visible but the contrasts are completely smoothed eliminating the artefact of the original soil map. However, the spread (gray area) in this transition between soil units (polygons) is wider than

the spread detected within each soil unit. The effect is due to the combination of the uncertainty introduced to the nominal value of the soil property and to the exact position of the transition between the soil units.

The spread of the realizations is quantitatively evaluated based on the standard deviation of the ensemble. In particular, Figure 5a represents the probability distribution of the standard deviation of the clay percentage calculated at every grid cell within the catchment (i.e., 16432 grid cells) for each method. Results obtained based on the three methods, on average, exhibit a high consistency in representing the uncertainty over the catchment (i.e., average standard deviation is for all the methods 7%). However, some differences are detected in the distributions. The random error method (RE) shows a normal distribution with a relatively low variability (i.e., the coefficient of variation of the distribution is 6%). This is the consequence of the fact that the soil properties within the catchment are perturbed with almost the same magnitude. Similarly, the spatially correlated method (SC) shows also a normal distribution but with a slightly wider variability (i.e.,  $CV = 8\%$ ). In contrast, the results obtained with the conditional points (CP) method show a very different distribution that is skewed with a tail to high extreme values. These high spreads in the soil realizations are located in the transition between the soil units, in particular if the transition is sharp (see Figure 4).

Finally, the standard deviation of the values is calculated by aggregating the map for different subcatchments (Figure 5b) and at different grid resolution (Figure 5c) based on the analysis described in section 2.5. The spreads of the realizations obtained with the three perturbation methods are of similar magnitude considering the finer resolution (e.g., resolution  $< 1 \times 1 \text{ km}^2$ ). The differences between the perturbation methods become more relevant by aggregating to a coarser resolution. In other words, this means that the introduced uncertainty is in the same order of magnitude, but the spatial patterns are different. In the random error method (RE), the spread is relatively high at all scales and even the mean value of the soil properties of the entire catchment is perturbed (i.e., standard deviation  $> 0$  for the resolution of  $60 \times 60 \text{ km}^2$ ). The spread obtained with the spatially correlated method (SC) decreases more rapidly with increasing spatial scale. This is consistent with the correlation length prescribed to the random fields used in this method (i.e., 3 km). However, it is noteworthy to observe how the mean value of the soil properties over the entire catchment is still perturbed also with this method. This is explained by the fact that the random fields superimposed to the original soil map have zero mean over a rectangular domain, but the average can be different when masked to the catchment. The behaviour is exaggerated when a relatively long correlation length in comparison to the size of the domain is used. Finally, the results of the conditional points method (CP) show how just the small scale is perturbed and the spread of the ensemble drops already at the resolution of 5 km to disappear completely when the average over the catchment is considered. This behaviour is consistent with the density of the samples used to constrain the random fields (i.e., one sample every  $3 \times 3 \text{ km}^2$ ).

### 3.2 Spatial variability of the uncertainty of state and fluxes

In this section, the spatial variability of the uncertainty of the simulated state and fluxes is presented. In this analysis (see section 2.5, Table 2, uncertainty analysis #1), the mean coefficient of variation over time (i.e., 1 year) is calculated for each

grid cell (i.e., 16432 grid cells) and the spatial distributions obtained with the three perturbation methods are compared (Figure 6).

The uncertainties of all hydrological states and fluxes obtained with each perturbation methods provide nearly the same magnitude and the same spatial variability, with correlation coefficients calculated between the results obtained by each method higher than 0.8. For this reason, only the spatial distribution of the coefficient of variations (*CVs*) of the model outputs over the entire catchment obtained with the random error method (RE) is shown as example (Figure 6, left). The results obtained with all the three perturbation methods are shown for the transect depicted in Figure 4 to facilitate the visualization of the relatively small differences (Figure 6, right).

In general, the results obtained show that, independently from the perturbation method used, the uncertainty in the total runoff (*Q*) and groundwater recharge (*GWR*) are highest, with an average *CV* estimated across the catchment of 11% and 15%, respectively. Soil moisture (*SM*) and actual evapotranspiration (*AET*) appear to be less sensitive to the soil variability with an average *CV* of 3% and 1%, respectively (Figure 6, left). The relatively small differences detected based on the use of different perturbation methods are located in the transition between the soil units (Figure 6, right) and they are attributed to the higher uncertainty in the soil properties introduced in those areas (see Figure 5a). Overall, a strong spatial variability in the uncertainty in the model outputs is detected with some differences depending on the considered model output. The uncertainty in runoff is more pronounced in the north-west areas, actual evapotranspiration appears to be more affected in the central-north areas. High uncertainty in simulated soil moisture is distributed across the catchment and the uncertainty in simulated groundwater recharge increases close to the catchment outlet (see Figure 2).

For a further interpretation, the spatial variability of the uncertainty in the simulated model outputs is compared to different boundary conditions and input properties. In particular, the correlation coefficients between the spatial distribution of the *CVs* of each model outputs and the spatial distribution of clay [%], the mean leaf area index (*LAI* [ $\text{m}^2 \text{m}^{-2}$ ]) and the annual sum of the potential evapotranspiration (*PET* [mm]) calculated over the simulation period (i.e., one year) are calculated. These three factors are selected to represent soil, vegetation and atmospheric conditions, respectively. The spatial distributions of these factors are shown in the supplementary material (see Figure S1). Correlation coefficients for each perturbation method are calculated and average and standard deviation based on the three methods are depicted in Figure 7.

The results obtained with the three different methods are consistent between each other also in this comparison (i.e., as represented by the small error bars) showing different correlations for each model output. The uncertainty in the runoff is stronger correlated to the actual value of the soil property. This correlation can be visually identified comparing the spatial variability detected in Figure 6 (right) and the spatial variability of the soil property shown in Figure 4 for the same transect. The uncertainty in the actual evapotranspiration is strongly correlated to the atmospheric conditions and, to less extend, to the soil properties. Finally, the uncertainties of the soil moisture and groundwater recharge are correlated to the vegetation characteristics, with a relatively lower effect of soil properties.

To further evaluate the different correlations found for each simulated model output, the correlation matrix between the uncertainty (*CV*) detected in each model output is calculated (Table 3). On the one hand, the results show that the

uncertainties in the fluxes are positively correlated (correlation coefficient  $> 0.2$ ). This means that when the uncertainty in one specific flux is relatively high, also other fluxes to some degree are uncertain. On the other hand, it is interesting to note that the uncertainty in soil moisture is highly correlated to the groundwater recharge (correlation coefficient = 0.7) while the correlations to the other model outputs are negligible (correlation coefficient  $< 0.2$ ). This means that the model could have relatively low uncertainty in soil moisture but high uncertainty in evapotranspiration or runoff and vice-versa. These results are consistent among all the three perturbation methods and they support the use of both state and fluxes for a proper assessment of the performance of hydrological models as it was underlined in several other studies (Ahmadi et al., 2014; Baroni et al., 2010; Conradt et al., 2013; Delsman et al., 2016; McCabe et al., 2005; Rakovec et al., 2016; Silvestro et al., 2015; Wöhling et al., 2013a; Zink et al., 2016).

### 10 3.3 Temporal variability of the uncertainty of state and fluxes

The daily temporal variability of the uncertainty on the simulated state and fluxes obtained at the model resolution (i.e., 500 m) is presented in this section. In this analysis (see section 2.5, Table 2, analysis #2), the coefficient of variation at daily time step for each perturbation method obtained in two grid cells selected within the catchment are compared for an illustrative purpose. The two locations A and B are depicted in Figure 2. The two grid cells are characterized by (see also supplementary material, figure S1) a remarkable difference in the rain (i.e., almost  $1600 \text{ mm a}^{-1}$  and  $1000 \text{ mm a}^{-1}$ , respectively), by different land use (i.e., crop field and deciduous forest, respectively) but they have almost the same soil properties (i.e., 19% sand and 59% clay for grid cell A; 19% sand and 66% clay for grid cell B). The grid cells are selected to represent different uncertainties of the model outputs (see Figure 6). In particular, grid cell A shows relatively high uncertainty in simulated soil moisture ( $CV \sim 4\%$ ) while grid cell B show relatively low uncertainty ( $CV \sim 2\%$ ). The three perturbation methods provide nearly the same results with a correlation coefficient higher than 0.8. For this reason, only the results obtained with the random error method (RE) are shown in Figure 8. The figure also shows the actual values of simulated state and fluxes for comparison (i.e., mean value and 95% confidence interval of the ensemble simulations obtained with the random error method).

The results show how the uncertainty of the total runoff is relatively high during the entire simulation period with a tendency of increasing the uncertainty during high flow period. The behaviour is particularly evident in the grid cell B (i.e., correlation coefficient between  $CV$  and simulated runoff is 0.6). In contrast, the actual evapotranspiration is close to the potential rate for most of the simulation period and, for this reason, it is not sensitive to changes in soil properties. As expected, the uncertainty is only detected during summer time when soil moisture is relatively low and the actual evapotranspiration rate decreases in comparison to the potential evapotranspiration. This result also explains the low correlation detected between the uncertainty in soil moisture and evapotranspiration (see Table 3). The temporal variability obtained for the uncertainty in soil moisture shows a more complex behaviour depending on the grid cell considered. In grid cell A, the  $CV$  increases with the increasing of soil moisture while it decreases in grid cell B. The different behaviours are explained comparing the actual soil moisture values. In grid cell A, the soil moisture values are relatively low ( $0.25 \text{ m}^3 \text{ m}^{-3}$ ) while, in grid cell B, the

values are close to saturation ( $0.4 \text{ m}^3 \text{ m}^{-3}$ ). Finally, groundwater recharge shows also a strong temporal dynamic with a tendency of higher uncertainty with increasing groundwater recharge in grid cell A (correlation coefficient = 0.2) while the correlation is negligible in grid cell B (correlation  $\sim 0$ ).

Overall, it is noteworthy to observe how the uncertainty in soil moisture is relatively constant in time while the uncertainty in the fluxes shows much stronger temporal variability. This different behaviour can be explained considering two main characteristics. On the one hand, the presence of non-linear relations between state and fluxes generates threshold behaviour for which the uncertainty in soil moisture could be limited to ranges where the fluxes are not affected. This is for instance the case when the uncertainty in soil moisture is limited to relative wet conditions (i.e., above plant stress) and for this reason it does not affect the evapotranspiration. Similarly, the uncertainty in soil moisture could be limited in relative dry conditions and the runoff could be not affected. On the other hand, there is a tendency of compensation in the uncertainty in the model outputs for which an overestimation of the actual evapotranspiration could be related to an underestimation of the groundwater recharge (or vice-versa). In these conditions the soil moisture could be still well defined without providing any indication of the degradation of the model performance. As a result, the low uncertainty in soil moisture does not represent the overall uncertainty in the model. Overall, this analysis underlines the role of the different hydrological conditions (e.g., dry or wet) for understanding the effect of the uncertainty in soil properties on the model response. Similar conclusions are supported by the use of temporal sensitivity and identifiability analysis to better capture the role of the different uncertainties in the parameters analysed (Ghasemizade et al., 2017; Guse et al., 2015; Pianosi and Wagener, 2016; Wagener et al., 2003).

### 3.4 Spatial uncertainty of state and fluxes at subcatchments

The uncertainties (CV) of simulated state and fluxes are also compared by aggregating the results over subcatchments of different sizes (see section 2.5, Table 2, analysis #3). The results obtained with the three perturbation methods are shown against the catchment size in Figure 9.

As presented by Refsgaard et al. (2016), the uncertainty in all the model output reduces with increasing catchment area. Assuming an arbitrary threshold (i.e., CV) acceptable for a specific model application, this analysis identifies, on the one hand, the spatial limit of model predictive capability for the specific application. On the other hand, it identifies the resolution below which it might become important to have a better understanding of the soil spatial variability. This resolution is referred to as the Representative Elementary Scale (RES) by Refsgaard et al. (2014) and it provides a clear and simple framework for the assessment of the performance of distributed models. However, it is interesting to note that the three perturbation methods generated very different results and, assuming the same arbitrary threshold for each method, different RESs are identified. The random error method (RE) creates higher uncertainty in all the subcatchments and even the mean of states and fluxes over the entire catchment is uncertain (i.e.,  $60 \times 60 \text{ km}^2$ ). The spatial correlated method (SC) shows a similar pattern but the uncertainty is lower in all the subcatchments. Finally, the uncertainty based on the condition points method (CP) decreases already at small catchment sizes of e.g.,  $2 \times 2 \text{ km}^2$ .

The different results in the uncertainty in the model outputs obtained by the use of the different perturbation methods are consistent with the different uncertainties introduced in the soil properties (Figure 5b). This result supports the conclusion that the different RESs identified are related to the underlying correlation length scale (CL) used in each perturbation method (Refsgaard et al., 2016). The random error method perturbs the value of the entire soil units and it does not generate spatially ergodic soil parameters fields i.e., aggregated hydrological responses still show a non-vanishing uncertainty at large catchment. The spatial correlated method introduced correlation length of 3 km and the effect on the uncertainty in the aggregated model output reached a remarkable reduction (e.g., > 90% of the uncertainty in all the simulated state and fluxes is reduced) when the entire catchment is considered. Finally, the conditional points method introduces uncertainty only at small spatial scales while the longer spatial patterns are preserved. For this reason the domain is ergodic already at relatively low catchment size (i.e., 20 x 20 km<sup>2</sup>).

These characteristic lengths (Representative Elementary Scale RES vs. correlation length CL) identified by the use of the three different soil perturbation methods are in agreement with previous studies conducted in surface hydrology (Binley et al., 1989; Fan et al., 2016; Herbst et al., 2006; Merz and Plate, 1997) and in stochastic subsurface hydrology (Dagan, 1989; Fiori and Russo, 2007; Rubin, 2003), where a suitable value for defining ergodic system was found to be  $\sim \text{RES/CL} > 20$ .

For this reason, it is notable the equivalence of the ergodic concept introduced in subsurface hydrology (Dagan, 1989; Rubin, 2003) and the RES concept in the case the arbitrary threshold (i.e., CV) is set to zero. However, two important characteristics can be further underlined. First, it is notable how catchments with similar size provide different degrees of uncertainties in the model output. This behaviour is in agreement with the results discussed in section 3.2 showing different sensitivity on the soil perturbation depending on the different boundary conditions and model set-up (i.e., depending on the location within the catchment). For this reason, the results support the difficulties to find a universal RES that is not affected by the uncertainty in the soil properties for the entire catchment. Despite the RES concept has some differences with the Representative Elementary Area concept (REA) introduced in past literature (see Refsgaard et al. (2016) for further discussion about the differences), it is noteworthy how this result is in agreement with the difficulties for finding a universal REA discussed also in those studies (e.g., Fan and Bras, 1995; Wood et al., 1988). Secondly, different sensitivities arise depending on the model output considered. Soil moisture is more sensitive to the perturbation of soil properties since the relative change between the three different methods is highest among the four hydrological variables under investigation. This behaviour is particularly evident when considering the results obtained with the random error method. In this case, a relatively small perturbation introduced in the mean of the entire catchment (60 x 60 km<sup>2</sup>) explains already most of the uncertainty in the simulated soil moisture. The uncertainty slightly increases with decreasing catchment size. In comparison, all the fluxes are much less affected by the small perturbations introduced for the entire catchment but they become increasingly pronounced with a decreasing catchment size. For this reason, the RES is also different depending on the model output considered.

### 3.5 Uncertainty of state and fluxes at different spatio-temporal scales

A similar scaling analysis is also conducted averaging state and fluxes by coarsening the grid resolution and by aggregating at different temporal scales (see section 2.5, Table 2, analysis #4). The results obtained with the three perturbation methods are presented in Figure 10.

- 5 The spatial aggregation of the model output, as represented in the x-axis of Figure 10, shows the same effect obtained by aggregating the model output based on catchment of different sizes (Figure 9). For this reason, the two analyses (aggregating by catchment vs. coarsening the grid resolution) can be considered equivalent in the identification of the effect of the spatial resolution on the uncertainty in the model outputs. However, the results described in the previous sections showed also a strong variability in space and in time. For this reason, the use of the mean coefficient of variation calculated over time and
- 10 across all the grid cells to represent the model performance (Eq. 6) can be misleading e.g., underestimating the actual uncertainty in the model output. Instead, the use of the maximum CV calculated over the catchment and over the simulated period could be used to better represent the model performance. In addition, the extension of the analysis to the temporal scale (y-axis in Figure 10) emphasizes the clear trade-off of the performance of the model between the spatial resolution and the temporal resolution. In particular, assuming an arbitrary threshold (i.e., CV) as a limit of model predictive capability for
- 15 the specific model application (Refsgaard et al., 2016), the spatial and temporal analysis shows how the simulated state and fluxes should be aggregated in time to maintain acceptable performance when decreasing the space resolution.

Overall, also for this spatio-temporal analysis, the results obtained with the three perturbation methods are very different and the RES (here defined as the spatial and temporal scale at which it might become important - or not - to have a better understanding of the soil spatial variability) strongly depends on the perturbation methods used. Since the three perturbation

20 methods reflect different uncertainties introduced in the original soil map, the analysis emphasises the importance to identify the correct approach to characterize the uncertainty for each model application and for further model improvements. For the specific case study presented here, it is notable how the streamflow at the catchment outlet (i.e., spatial resolution > 32 km), that was used for calibration of the model in previous studies (Kumar et al., 2013; Samaniego et al., 2010b), is sensitive only to the perturbation of long soil spatial structures introduced with the random error method. For this reason, it could be

25 assumed that the uncertainty in soil properties introduced with the RE method is well compensated by the calibration and the RE method could not represent the actual uncertainty in the specific model application. The same could be considered for the results obtained with the spatially correlated method, as soon as subcatchments of different sizes are used in the calibration. In contrast, this model output is not sensitive to the perturbations introduced at small scale (e.g., conditional points method). On the one hand, this means that small soil variabilities are not relevant when the model application focuses on the

30 streamflow prediction. On the other hand, this results underlines that it is not possible to infer (e.g., calibrate) these small spatial soil patterns based on the streamflow observations. For this reason, the conditional points method appear to be a simple and effective method to preserve the general spatial pattern of the original soil map while introducing uncertainty due to the unresolved spatial heterogeneity within the soil units. This type of uncertainty affects the streamflow only for small

subcatchments (size < 1 x 1 km<sup>2</sup>) while introducing relevant effects on the local hydrological states (i.e., soil moisture) and fluxes (e.g., groundwater recharge). This method therefore could be considered as a valuable choice to account for the uncertainty of soil properties for this type of model applications i.e., when well calibrated hydrological models based on streamflow measurements are used.

- 5 A different behaviour is noted for the distributed hydrological states and fluxes (evapotranspiration and groundwater recharge). These variables represent in fact local conditions (i.e., spatial resolution < 1 km) and they show the same degree of uncertainty independently from the perturbation method used. This means that these localized state and fluxes can be used to infer local properties but it is not possible to use this type of observations to calibrate the values for larger areas. For this reason, the use of e.g., remote sensing products as total water storage anomalies and evapotranspiration is an effective
- 10 approach for constraining and improving local model parameterization.

#### 4. Conclusions

In the present study, uncertainty in soil properties is characterized based on three statistical perturbations methods. This uncertainty is propagated applying the distributed hydrological model mHM. The uncertainty in the simulated states and fluxes are analysed at different spatial and temporal scales. The main conclusions are summarized as follow:

- 15 1. The effect of uncertainty in soil properties depends on the hydrological model output. In particular, the uncertainty in the fluxes are relatively positive correlated i.e., if the uncertainty in one of the simulated flux is high, also the other fluxes show, to some degrees, uncertainties. On the contrary, the uncertainty in the simulated soil moisture shows a more complex relation as its uncertainty does not always represent the overall uncertainty in the simulated fluxes. This behaviour is explained by the non-linear relation between state and fluxes and the occurrence of
- 20 threshold conditions in the model response. For this reason, these results support the need of multi-variable (e.g., soil moisture and streamflow) for a proper assessment of the overall performance of hydrological models (Rakovec et al., 2016; Zink et al., 2016).
- 25 2. The uncertainty in state and fluxes depends on the specific locations and on the boundary conditions. In particular, the uncertainty in the model results shows strong temporal and spatial variability over the catchment with complex interactions to local environmental conditions (i.e., atmosphere, vegetation and soil). These results highlight the role of specific model settings (i.e., parameters and boundary conditions) for a proper characterization of the model response and the difficulty to generalize the result for other applications (i.e., different study areas and weather conditions). Similar conclusions were obtained based on sensitivity analysis conducted using hydrological models in other catchments (e.g., Shin et al., 2013; van Griensven et al., 2006) and they support the use of spatial and
- 30 temporal diagnostic tools for a better understanding of the input-output space (Ghasemizade et al., 2017; Guse et al., 2015; Pianosi and Wagener, 2016; Wagener et al., 2003).



3. The uncertainty in state and fluxes depends on the spatio-temporal resolution used for the analysis. In particular, the uncertainty in all the model outputs decreases with increasing spatial and temporal resolution. Assuming an arbitrary threshold (e.g., *CV*) acceptable for a specific model application as proposed by Refsgaard et al. (2016), this scaling analysis identifies the so-called Representative Elementary Scale (RES). On the one hand, this scale represents the resolution at which the model produces acceptable limits of predictive capability. On the other hand, it identifies the resolution below which it might become important to have a better understanding of the soil spatial variability. For this reason, this analysis shows to be a simple and practical approach for the assessment of spatially distributed models. However, in the present study it was underlined the difficulties to identify a universal RES since it depends on locations, time and model output. For these reasons, the present study proposes three possible extensions of the RES approach: the use of the maximum *CV*, the temporal aggregation and the assessment of multi-variables. The first extension should better capture the model performance due to the strong spatial and temporal variability that could be present in the uncertainty within the catchment. The second extension could be used to emphasize the trade-off between temporal and spatial resolution of the model application. Finally, the third extensions should provide a better assessment of the overall performance of the model.
4. The assumptions and the methods used for the characterizations of the uncertainty in soil properties plays a crucial role. In particular, the above conclusions are supported by the results obtained with all the three soil perturbation methods used in this study. However, the absolute value of the uncertainty detected in state and fluxes at different spatial and temporal scales strongly depends on the perturbation methods. For this reason, the results underline the importance to properly characterize the specific sources of uncertainty to transform a pure numerical exercise to specific results that are able to better support the model applications. The three methods developed and used in the present study represent three relatively simple approaches that can be considered to account for different types of uncertainty in a soil map. In particular, this study proposes a new perturbation method (here called Conditional points method) able to introduce small scale soil variability while preserving the original spatial patterns. In this context, however, the availability of soil map with additional information regarding not only the actual mean value within the soil units but also information representing the unresolved variability (variance and correlation length of the subdominant soil units) would provide a strong support to hydrological modelling applications.
5. Finally, the analysis conducted in the present study identifies important information to be used for possible model improvement, either by collecting additional data regarding the soil properties or for inverse modelling and data assimilation frameworks. In particular, integrated fluxes like river discharge of large catchments are shown not to be impacted by small scales soil variabilities (i.e., standard deviation) but only by long spatial structures (i.e., long correlation lengths). For this reason, additional details in the soil map do not improve the model performance on streamflow but rather other sources of uncertainties should be considered for that (e.g., vegetation properties). For the same reason, this integrated observation cannot be used to infer local parameters (i.e., parameter of finer resolutions) but only mean characteristics of the input parameters (e.g., average soil properties over the soil units).

On the contrary, local state and fluxes show to be very sensitive to local variation in the soil properties (i.e., standard deviation). For this reason, a soil map with finer resolution data is found to be an important factor for decreasing the uncertainty in these local model outputs. For the same reason, these simulated outputs can be used to infer local soil parameters in calibration or data assimilation. Despite the transition between these two extreme conditions for which the uncertainty in soil properties is (or is not) important is quite smooth, it depends on the output considered and on the boundary conditions, this analysis provides a strong support to prioritize the model improvements in specific model applications. For this reason, similar studies can be considered for comparing statistical methods to characterize other sources of uncertainty relevant in catchment hydrology (e.g., precipitation, vegetation parameters).

*Acknowledgment.* The study was supported by the Deutsche Forschungsgemeinschaft (DFG) under CI 26/13-1 in the framework of the research unit FOR 2131 “Data Assimilation for Improved Characterization of Fluxes across Compartmental Interfaces” and by the Helmholtz Alliance - Remote Sensing and Earth System Dynamics (HGF-EDA). The comments provided by the two anonymous Reviewers were highly appreciated.

## References

- Aguilar, C., Herrero, J., Polo, M.J., 2010. Topographic effects on solar radiation distribution in mountainous watersheds and their influence on reference evapotranspiration estimates at watershed scale. *Hydrol. Earth Syst. Sci.* 14, 2479–2494. doi:10.5194/hess-14-2479-2010
- Ahmadi, M., Arabi, M., Ascough, J.C., Fontane, D.G., Engel, B.A., 2014. Toward improved calibration of watershed models: Multisite multiobjective measures of information. *Environ. Model. Softw.* 59, 135–145. doi:10.1016/j.envsoft.2014.05.012
- Altarejos-García, L., Martínez-Chenoll, M.L., Escuder-Bueno, I., Serrano-Lombillo, A., 2012. Assessing the impact of uncertainty on flood risk estimates with reliability analysis using 1-D and 2-D hydraulic models. *Hydrol. Earth Syst. Sci.* 16, 1895–1914. doi:10.5194/hess-16-1895-2012
- Anderson, R.M., Koren, V.I., Reed, S.M., 2006. Using SSURGO data to improve Sacramento Model a priori parameter estimates. *J. Hydrol.* 320, 103–116. doi:10.1016/j.jhydrol.2005.07.020
- Arnone, E., Dialynas, Y.G., Noto, L.V., Bras, R.L., 2016. Accounting for soil parameter uncertainty in a physically based and distributed approach for rainfall-triggered landslides. *Hydrol. Process.* 30, 927–944. doi:10.1002/hyp.10609
- Baroni, G., Facchi, A., Gandolfi, C., Ortuani, B., Horeschi, D., van Dam, J.C., 2010. Uncertainty in the determination of soil hydraulic parameters and its influence on the performance of two hydrological models of different complexity. *Hydrol. Earth Syst. Sci.* 14, 251–270. doi:10.5194/hess-14-251-2010
- Baveye, P., 2002. Comment on “Modeling soil variation: past, present and future” by G.B.M. Heuvelink and R. Webster. *Geoderma* 109, 289–293. doi:10.1016/S0016-7061(02)00173-8
- Baveye, P.C., Laba, M., 2015. Moving away from the geostatistical lamppost: Why, where, and how does the spatial heterogeneity of soils matter? *Ecol. Model.* 298, 24–38. doi:10.1016/j.ecolmodel.2014.03.018
- Besson, A., Javaux, M., Bièdiers, C.L., Vanclooster, M., 2011. Impact of tillage on solute transport in a loamy soil from leaching experiments. *Soil Tillage Res.* 112, 47–57. doi:10.1016/j.still.2010.11.001
- Beven, K., 2007. Towards integrated environmental models of everywhere: uncertainty, data and modelling as a learning process. *Hydrol. Earth Syst. Sci.* 11, 460–467. doi:10.5194/hess-11-460-2007

- Beven, K., 2001. How far can we go in distributed hydrological modelling? *Hydrol. Earth Syst. Sci.* 5, 1–12. doi:10.5194/hess-5-1-2001
- Binley, A., Elgy, J., Beven, K., 1989. A physically based model of heterogeneous hillslopes: 1. Runoff production. *Water Resour. Res.* 25, 1219–1226. doi:10.1029/WR025i006p01219
- 5 Burrough, P.A., 1983. Multiscale sources of spatial variation in soil. II. A non-Brownian fractal model and its application in soil survey. *J. Soil Sci.* 34, 599–620. doi:10.1111/j.1365-2389.1983.tb01058.x
- Carrera, J., Alcolea, A., Medina, A., Hidalgo, J., Slooten, L.J., 2005. Inverse problem in hydrogeology. *Hydrogeol. J.* 13, 206–222. doi:10.1007/s10040-004-0404-7
- Chaney, N.W., Herman, J.D., Reed, P.M., Wood, E.F., 2015. Flood and drought hydrologic monitoring: the role of model parameter uncertainty. *Hydrol. Earth Syst. Sci.* 19, 3239–3251. doi:10.5194/hess-19-3239-2015
- 10 Chaney, N.W., Wood, E.F., McBratney, A.B., Hempel, J.W., Nauman, T.W., Brungard, C.W., Odgers, N.P., 2016. POLARIS: A 30-meter probabilistic soil series map of the contiguous United States. *Geoderma* 274, 54–67. doi:10.1016/j.geoderma.2016.03.025
- Christiaens, K., Feyen, J., 2001. Analysis of uncertainties associated with different methods to determine soil hydraulic properties and their propagation in the distributed hydrological MIKE SHE model. *J. Hydrol.* 246, 63–81. doi:10.1016/S0022-1694(01)00345-6
- 15 Comunian, A., De Micheli, L., Lazzati, C., Felletti, F., Giacobbo, F., Giudici, M., Bersezio, R., 2015. Hierarchical simulation of aquifer heterogeneity: implications of different simulation settings on solute-transport modeling. *Hydrogeol. J.* doi:10.1007/s10040-015-1343-1
- 20 Conradt, T., Wechsung, F., Bronstert, A., 2013. Three perceptions of the evapotranspiration landscape: comparing spatial patterns from a distributed hydrological model, remotely sensed surface temperatures, and sub-basin water balances. *Hydrol. Earth Syst. Sci.* 17, 2947–2966. doi:10.5194/hess-17-2947-2013
- Cosby, B.J., Hornberger, G.M., Clapp, R.B., Ginn, T.R., 1984. A Statistical Exploration of the Relationships of Soil Moisture Characteristics to the Physical Properties of Soils. *Water Resour. Res.* 20, 682–690. doi:10.1029/WR020i006p00682
- 25 Dagan, G., 1989. Flow and transport in porous formations. New York: Springer-Verlag.
- De Lannoy, G.J.M., Koster, R.D., Reichle, R.H., Mahanama, S.P.P., Liu, Q., 2014. An updated treatment of soil texture and associated hydraulic properties in a global land modeling system. *J. Adv. Model. Earth Syst.* 6, 957–979. doi:10.1002/2014MS000330
- 30 Delsman, J.R., Winters, P., Vandenbohede, A., Oude Essink, G.H.P., Lebbe, L., 2016. Global sampling to assess the value of diverse observations in conditioning a real-world groundwater flow and transport model. *Water Resour. Res.* n/a–n/a. doi:10.1002/2014WR016476
- Deng, H., Ye, M., Schaap, M.G., Khaleel, R., 2009. Quantification of uncertainty in pedotransfer function-based parameter estimation for unsaturated flow modeling. *Water Resour. Res.* 45, n/a–n/a. doi:10.1029/2008WR007477
- 35 Deutsch, C.V., Journel, A.G., 1998. GSLIB: Geostatistical Software Library and User's Guide. Oxford University Press.
- Di Baldassarre, G., Schumann, G., Bates, P.D., Freer, J.E., Beven, K.J., 2010. Flood-plain mapping: a critical discussion of deterministic and probabilistic approaches. *Hydrol. Sci. J.* 55, 364–376. doi:10.1080/02626661003683389
- Du, F., Zhu, A.-X., Band, L., Liu, J., 2015. Soil property variation mapping through data mining of soil category maps: SOIL PROPERTY MAPPING THROUGH DATA MINING OF SOIL CATEGORY MAPS. *Hydrol. Process.* 29, 2491–2503. doi:10.1002/hyp.10383
- 40 Dubois, D., Guyonnet, D., 2011. Risk-informed decision-making in the presence of epistemic uncertainty. *Int. J. Gen. Syst.* 40, 145–167. doi:10.1080/03081079.2010.506179
- Fan, L., Lehmann, P., Or, D., 2016. Effects of soil spatial variability at the hillslope and catchment scales on characteristics of rainfall-induced landslides. *Water Resour. Res.* 52, 1781–1799. doi:10.1002/2015WR017758
- 45 Fan, Y., Bras, R.L., 1995. On the concept of a representative elementary area in catchment runoff. *Hydrol. Process.* 9, 821–832. doi:10.1002/hyp.3360090708
- Farmer, W.H., Vogel, R.M., 2016. On the deterministic and stochastic use of hydrologic models. *Water Resour. Res.* doi:10.1002/2016WR019129
- Fiori, A., Russo, D., 2007. Numerical analyses of subsurface flow in a steep hillslope under rainfall: The role of the spatial heterogeneity of the formation hydraulic properties. *Water Resour. Res.* 43, n/a–n/a. doi:10.1029/2006WR005365
- 50


- Garrigues, S., Olivos, A., Calvet, J.C., Martin, E., Lafont, S., Moulin, S., Chanzy, A., Marloie, O., Buis, S., Desfonds, V., Bertrand, N., Renard, D., 2015. Evaluation of land surface model simulations of evapotranspiration over a 12-year crop succession: impact of soil hydraulic and vegetation properties. *Hydrol. Earth Syst. Sci.* 19, 3109–3131. doi:10.5194/hess-19-3109-2015
- 5 Geza, M., McCray, J.E., 2008. Effects of soil data resolution on SWAT model stream flow and water quality predictions. *J. Environ. Manage.* 88, 393–406. doi:10.1016/j.jenvman.2007.03.016
- Ghasemizade, M., Baroni, G., Abbaspour, K., Schirmer, M., 2017. Combined analysis of time-varying sensitivity and identifiability indices to diagnose the response of a complex environmental model. *Environ. Model. Softw.* 88, 22–34. doi:10.1016/j.envsoft.2016.10.011
- 10 Gómez-Hernández, J.J., Journel, A.G., 1993. Joint Sequential Simulation of MultiGaussian Fields, in: Soares, A. (Ed.), *Geostatistics Tróia '92, Quantitative Geology and Geostatistics*. Springer Netherlands, pp. 85–94. doi:10.1007/978-94-011-1739-5\_8
- Goovaerts, P., 2011. A coherent geostatistical approach for combining choropleth map and field data in the spatial interpolation of soil properties. *Eur. J. Soil Sci.* 62, 371–380. doi:10.1111/j.1365-2389.2011.01368.x
- 15 Goovaerts, P., 2001. Geostatistical modelling of uncertainty in soil science. *Geoderma, Estimating uncertainty in soil models* 103, 3–26. doi:10.1016/S0016-7061(01)00067-2
- Goovaerts, P., 1997. *Geostatistics for Natural Resources Evaluation*. Oxford University Press.
- Guber, A.K., Pachepsky, Y.A., van Genuchten, M.T., Simunek, J., Jacques, D., Nemes, A., Nicholson, T.J., Cady, R.E., 2009. Multimodel Simulation of Water Flow in a Field Soil Using Pedotransfer Functions. *Vadose Zone J.* 8, 1. doi:10.2136/vzj2007.0144
- 20 Guillo, B.P., Davin, E.L., Kündig, C., Smiatek, G., Seneviratne, S.I., 2013. Impact of soil map specifications for European climate simulations. *Clim. Dyn.* 40, 123–141. doi:10.1007/s00382-012-1395-z
- Guse, B., Pfannerstill, M., Strauch, M., Reusser, D.E., Lüttke, S., Volk, M., Gupta, H., Fohrer, N., 2015. On characterizing the temporal dominance patterns of model parameters and processes: Characterizing temporal dominance patterns of parameters and processes. *Hydrol. Process.* n/a-n/a. doi:10.1002/hyp.10764
- 25 Han, X., Hendricks Franssen, H.-J., Montzka, C., Vereecken, H., 2014. Soil moisture and soil properties estimation in the Community Land Model with synthetic brightness temperature observations. *Water Resour. Res.* n/a-n/a. doi:10.1002/2013WR014586
- Hansen, A.L., Gunderman, D., He, X., Refsgaard, J.C., 2014. Uncertainty assessment of spatially distributed nitrate reduction potential in groundwater using multiple geological realizations. *J. Hydrol.* 519, 225–237. doi:10.1016/j.jhydrol.2014.07.013
- 30 Hargreaves, G.H., Samani, Z.A., 1985. Reference crop evapotranspiration from temperature. *Appl Eng Agric* 1, 96–99.
- He, X., Højberg, A.L., Jørgensen, F., Refsgaard, J.C., 2015. Assessing hydrological model predictive uncertainty using stochastically generated geological models. *Hydrol. Process.* n/a-n/a. doi:10.1002/hyp.10488
- 35 Hennings, V., 2002. Accuracy of coarse-scale land quality maps as a function of the upscaling procedure used for soil data. *Geoderma* 107, 177–196. doi:10.1016/S0016-7061(01)00148-3
- Herbst, M., Dieckrüger, B., Vanderborght, J., 2006. Numerical experiments on the sensitivity of runoff generation to the spatial variation of soil hydraulic properties. *J. Hydrol.* 326, 43–58. doi:10.1016/j.jhydrol.2005.10.036
- Heuvelink, G.B.M., Kros, J., Reinds, G.J., De Vries, W., 2016. Geostatistical prediction and simulation of European soil property maps. *Geoderma Reg.* 7, 201–215. doi:10.1016/j.geodrs.2016.04.002
- 40 Heuvelink, G.B.M., Webster, R., 2001. Modelling soil variation: past, present, and future. *Geoderma, Developments and Trends in Soil Science* 100, 269–301. doi:10.1016/S0016-7061(01)00025-8
- Hohenbrink, T.L., Lischeid, G., 2015. Does textural heterogeneity matter? Quantifying transformation of hydrological signals in soils. *J. Hydrol.* 523, 725–738. doi:10.1016/j.jhydrol.2015.02.009
- 45 Isaaks, E.H., Srivastava, R.M., 1989. *An Introduction to Applied Geostatistics*. Oxford University Press.
- Islam, N., Wallender, W.W., Mitchell, J.P., Wicks, S., Howitt, R.E., 2006. Performance evaluation of methods for the estimation of soil hydraulic parameters and their suitability in a hydrologic model. *Geoderma* 134, 135–151. doi:10.1016/j.geoderma.2005.09.004
- Kempen, B., Brus, D.J., Heuvelink, G.B.M., Stoorvogel, J.J., 2009. Updating the 1:50,000 Dutch soil map using legacy soil data: A multinomial logistic regression approach. *Geoderma* 151, 311–326. doi:10.1016/j.geoderma.2009.04.023
- 50

- Kerry, R., Goovaerts, P., Rawlins, B.G., Marchant, B.P., 2012. Disaggregation of legacy soil data using area to point kriging for mapping soil organic carbon at the regional scale. *Geoderma* 170, 347–358. doi:10.1016/j.geoderma.2011.10.007
- 5 Kumar, R., Samaniego, L., Attinger, S., 2013. Implications of distributed hydrologic model parameterization on water fluxes at multiple scales and locations. *Water Resour. Res.* 49, 360–379. doi:10.1029/2012WR012195
- Kumar, R., Samaniego, L., Attinger, S., 2010. The effects of spatial discretization and model parameterization on the prediction of extreme runoff characteristics. *J. Hydrol.* 392, 54–69. doi:10.1016/j.jhydrol.2010.07.047
- Li, X., Zhang, Q., Ye, X., 2013. Effects of spatial information of soil physical properties on hydrological modeling based on a distributed hydrological model. *Chin. Geogr. Sci.* 23, 182–193. doi:10.1007/s11769-013-0599-4
- 10 Liao, K., Xua, F., Zheng, J., Zhu, Q., Yang, G., 2014. Using different multimodel ensemble approaches to simulate soil moisture in a forest site with six traditional pedotransfer functions. *Environ. Model. Softw.* 57, 27–32. doi:10.1016/j.envsoft.2014.03.016
- Lin, H., 2010. Earth's Critical Zone and hydropedology: concepts, characteristics, and advances. *Hydrol. Earth Syst. Sci.* 14, 25–45. doi:10.5194/hess-14-25-2010
- 15 Liu, Y., Gupta, H.V., 2007. Uncertainty in hydrologic modeling: Toward an integrated data assimilation framework. *Water Resour. Res.* 43. doi:10.1029/2006WR005756
- Livneh, B., Kumar, R., Samaniego, L., 2015. Influence of soil textural properties on hydrologic fluxes in the Mississippi river basin: Influence of Soil Textural Properties on Hydrologic Fluxes. *Hydrol. Process.* 29, 4638–4655. doi:10.1002/hyp.10601
- 20 Loosvelt, L., Pauwels, V.R.N., Cornelis, W.M., De Lannoy, G.J.M., Verhoest, N.E.C., 2011. Impact of soil hydraulic parameter uncertainty on soil moisture modeling. *Water Resour Res* 47, W03505.
- McCabe, M.F., Franks, S.W., Kalma, J.D., 2005. Calibration of a land surface model using multiple data sets. *J. Hydrol.* 302, 209–222. doi:10.1016/j.jhydrol.2004.07.002
- Merz, B., Plate, E.J., 1997. An analysis of the effects of spatial variability of soil and soil moisture on runoff. *Water Resour Res* 33, 2909–2922.
- 25 Meyerhoff, S.B., Maxwell, R.M., 2011. Quantifying the effects of subsurface heterogeneity on hillslope runoff using a stochastic approach. *Hydrogeol. J.* 19, 1515–1530. doi:10.1007/s10040-011-0753-y
- Minasny, B., McBratney, A.B., 2016. Digital soil mapping: A brief history and some lessons. *Geoderma* 264, 301–311. doi:10.1016/j.geoderma.2015.07.017
- 30 Mirus, B.B., 2015. Evaluating the importance of characterizing soil structure and horizons in parameterizing a hydrologic process model: Integrating Soil Characterization and Hydrologic Modelling. *Hydrol. Process.* 29, 4611–4623. doi:10.1002/hyp.10592
- Moeys, J., Larsbo, M., Bergström, L., Brown, C.D., Coquet, Y., Jarvis, N.J., 2012. Functional test of pedotransfer functions to predict water flow and solute transport with the dual-permeability model MACRO. *Hydrol. Earth Syst. Sci.* 16, 2069–2083. doi:10.5194/hess-16-2069-2012
- 35 Montanari, A., Koutsoyiannis, D., 2012. A blueprint for process-based modeling of uncertain hydrological systems. *Water Resour. Res.* 48. doi:10.1029/2011WR011412
- Nauman, T.W., Thompson, J.A., 2014. Semi-automated disaggregation of conventional soil maps using knowledge driven data mining and classification trees. *Geoderma* 213, 385–399. doi:10.1016/j.geoderma.2013.08.024
- 40 Odgers, N.P., Sun, W., McBratney, A.B., Minasny, B., Clifford, D., 2014. Disaggregating and harmonising soil map units through resampled classification trees. *Geoderma* 214–215, 91–100. doi:10.1016/j.geoderma.2013.09.024
- Osborne, T.M., Lawrence, D.M., Slingo, J.M., Challinor, A.J., Wheeler, T.R., 2004. Influence of vegetation on the local climate and hydrology in the tropics: sensitivity to soil parameters. *Clim. Dyn.* 23. doi:10.1007/s00382-004-0421-1
- Pebesma, E.J., 2004. Multivariable geostatistics in S: the gstat package. *Comput. Geosci.* 30, 683–691. doi:10.1016/j.cageo.2004.03.012
- 45 Pelletier, J.D., Broxton, P.D., Hazenberg, P., Zeng, X., Troch, P.A., Niu, G.-Y., Williams, Z., Brunke, M.A., Gochis, D., 2016. A gridded global data set of soil, intact regolith, and sedimentary deposit thicknesses for regional and global land surface modeling. *J. Adv. Model. Earth Syst.* n/a-n/a. doi:10.1002/2015MS000526
- Pianosi, F., Wagener, T., 2016. Understanding the time-varying importance of different uncertainty sources in hydrological modelling using global sensitivity analysis. *Hydrol. Process.* doi:10.1002/hyp.10968
- 50

- R Core Team, 2013. R: A language and environment for statistical computing. R Foundation for Statistical Computing.
- Rakovec, O., Kumar, R., Mai, J., Cuntz, M., Thober, S., Zink, M., Attinger, S., Schäfer, D., Schrön, M., Samaniego, L., 2016. Multiscale and Multivariate Evaluation of Water Fluxes and States over European River Basins. *J. Hydrometeorol.* 17, 287–307. doi:10.1175/JHM-D-15-0054.1
- 5 Raleigh, M.S., Lundquist, J.D., Clark, M.P., 2015. Exploring the impact of forcing error characteristics on physically based snow simulations within a global sensitivity analysis framework. *Hydrol. Earth Syst. Sci.* 19, 3153–3179. doi:10.5194/hess-19-3153-2015
- Rasmussen, S.H., Christensen, J.H., Drews, M., Gochis, D.J., Refsgaard, J.C., 2012. Spatial-Scale Characteristics of Precipitation Simulated by Regional Climate Models and the Implications for Hydrological Modeling. *J. Hydrometeorol.* 13, 1817–1835. doi:10.1175/JHM-D-12-07.1
- 10 Refsgaard, J.C., Højberg, A.L., He, X., Hansen, A.L., Rasmussen, S.H., Stisen, S., 2016. Where are the limits of model predictive capabilities?: Representative Elementary Scale - RES. *Hydrol. Process.* doi:10.1002/hyp.11029
- Refsgaard, J.C., van der Sluijs, J.P., Højberg, A.L., Vanrolleghem, P.A., 2007. Uncertainty in the environmental modelling process – A framework and guidance. *Environ. Model. Softw.* 22, 1543–1556. doi:10.1016/j.envsoft.2007.02.004
- 15 Rubin, Y., 2003. Applied stochastic hydrogeology. Oxford University Press.
- Salazar, O., Wesström, I., Joel, A., 2008. Evaluation of DRAINMOD using saturated hydraulic conductivity estimated by a pedotransfer function model. *Agric. Water Manag.* 95, 1135–1143. doi:10.1016/j.agwat.2008.04.011
- Samain, B., Pauwels, V.R.N., 2013. Impact of potential and (scintillometer-based) actual evapotranspiration estimates on the performance of a lumped rainfall–runoff model. *Hydrol. Earth Syst. Sci.* 17, 4525–4540. doi:10.5194/hess-17-4525-2013
- 20 Samaniego, L., Bárdossy, A., Kumar, R., 2010a. Streamflow prediction in ungauged catchments using copula-based dissimilarity measures. *Water Resour. Res.* 46, n/a-n/a. doi:10.1029/2008WR007695
- Samaniego, L., Kumar, R., Attinger, S., 2010b. Multiscale parameter regionalization of a grid-based hydrologic model at the mesoscale. *Water Resour. Res.* 46. doi:10.1029/2008WR007327
- 25 Savage, J.T.S., Bates, P., Freer, J., Neal, J., Aronica, G., 2016. When does spatial resolution become spurious in probabilistic flood inundation predictions?: When Spatial Resolution Becomes Spurious in Probabilistic Flood Maps. *Hydrol. Process.* 30, 2014–2032. doi:10.1002/hyp.10749
- Schalge, B., Rihani, J., Baroni, G., Erdal, D., Geppert, G., Haefliger, V., Haese, B., Saavedra, P., Neuweiler, I., Hendricks Franssen, H.-J., Ament, F., Attinger, S., Cirpka, O.A., Kollet, S., Kunstmann, H., Vereecken, H., Simmer, C., 2016. High-Resolution Virtual Catchment Simulations of the Subsurface-Land Surface-Atmosphere System. *Hydrol. Earth Syst. Sci. Discuss.* 1–44. doi:10.5194/hess-2016-557
- 30 Seiller, G., Anctil, F., 2014. Climate change impacts on the hydrologic regime of a Canadian river: comparing uncertainties arising from climate natural variability and lumped hydrological model structures. *Hydrol. Earth Syst. Sci.* 18, 2033–2047. doi:10.5194/hess-18-2033-2014
- 35 Shanguan, W., Dai, Y., Duan, Q., Liu, B., Yuan, H., 2014. A global soil data set for earth system modeling. *J. Adv. Model. Earth Syst.* 6, 249–263. doi:10.1002/2013MS000293
- Shin, M.-J., Guillaume, J.H.A., Croke, B.F.W., Jakeman, A.J., 2013. Addressing ten questions about conceptual rainfall-runoff models with global sensitivity analyses in R. *J. Hydrol.* doi:10.1016/j.jhydrol.2013.08.047
- Silvestro, F., Gabellani, S., Rudari, R., Delogu, F., Laiolo, P., Boni, G., 2015. Uncertainty reduction and parameter estimation of a distributed hydrological model with ground and remote-sensing data. *Hydrol Earth Syst Sci* 19, 1727–1751. doi:10.5194/hess-19-1727-2015
- 40 Subburayalu, S.K., Jenhani, I., Slater, B.K., 2014. Disaggregation of component soil series on an Ohio County soil survey map using possibilistic decision trees. *Geoderma* 213, 334–345. doi:10.1016/j.geoderma.2013.08.018
- Tartakovsky, D.M., Nowak, W., Bolster, D., 2012. Introduction to the special issue on uncertainty quantification and risk assessment. *Adv. Water Resour.* 36, 1–2. doi:10.1016/j.advwatres.2011.12.010
- 45 Twarakavi, N.K.C., Sakai, M., Šimůnek, J., 2009. An objective analysis of the dynamic nature of field capacity. *Water Resour. Res.* 45, n/a-n/a. doi:10.1029/2009WR007944
- van Genuchten, M.T., 1980. A Closed-form Equation for Predicting the Hydraulic Conductivity of Unsaturated Soils1. *Soil Sci. Soc. Am. J.* 44, 892. doi:10.2136/sssaj1980.03615995004400050002x

- van Griensven, A., Meixner, T., Grunwald, S., Bishop, T., Diluzio, M., Srinivasan, R., 2006. A global sensitivity analysis tool for the parameters of multi-variable catchment models. *J. Hydrol.* 324, 10–23. doi:10.1016/j.jhydrol.2005.09.008
- 5 Vázquez, R.F., Feyen, J., 2003. Effect of potential evapotranspiration estimates on effective parameters and performance of the MIKE SHE-code applied to a medium-size catchment. *J. Hydrol.* 270, 309–327. doi:10.1016/S0022-1694(02)00308-6
- Vogel, H.-J., Roth, K., 2003. Moving through scales of flow and transport in soil. *J. Hydrol.* 272, 95–106. doi:10.1016/S0022-1694(02)00257-3
- 10 Wagener, T., McIntyre, N., Lees, M.J., Wheater, H.S., Gupta, H.V., 2003. Towards reduced uncertainty in conceptual rainfall-runoff modelling: dynamic identifiability analysis. *Hydrol. Process.* 17, 455–476. doi:10.1002/hyp.1135
- Wöhling, T., Gayler, S., Priesack, E., Ingwersen, J., Wizemann, H.-D., Högy, P., Cuntz, M., Attinger, S., Wulfmeyer, V., Streck, T., 2013a. Multiresponse, multiobjective calibration as a diagnostic tool to compare accuracy and structural limitations of five coupled soil-plant models and CLM3.5. *Water Resour. Res.* n/a-n/a. doi:10.1002/2013WR014536
- 15 Wöhling, T., Samaniego, L., Kumar, R., 2013b. Evaluating multiple performance criteria to calibrate the distributed hydrological model of the upper Neckar catchment. *Environ. Earth Sci.* 69, 453–468. doi:10.1007/s12665-013-2306-2
- Wood, E.F., Sivapalan, M., Beven, K., Band, L., 1988. Effects of spatial variability and scale with implications to hydrologic modeling. *J. Hydrol.* 102, 29–47. doi:10.1016/0022-1694(88)90090-X
- 20 Yu, X., Duffy, C., Baldwin, D.C., Lin, H., 2014. The role of macropores and multi-resolution soil survey datasets for distributed surface–subsurface flow modeling. *J. Hydrol.* 516, 97–106. doi:10.1016/j.jhydrol.2014.02.055
- Zacharias, S., Wessolek, G., 2007. Excluding Organic Matter Content from Pedotransfer Predictors of Soil Water Retention. *Soil Sci. Soc. Am. J.* 71, 43. doi:10.2136/sssaj2006.0098
- Zech, A., Zehner, B., Kolditz, O., Attinger, S., 2015. Impact of Heterogeneous Permeability Distribution on the Groundwater Flow Systems of a Small Sedimentary Basin. *J. Hydrol.* doi:10.1016/j.jhydrol.2015.11.030
- 25 Zhu, D., Peng, D.Z., Cluckie, I.D., 2013. Statistical analysis of error propagation from radar rainfall to hydrological models. *Hydrol. Earth Syst. Sci.* 17, 1445–1453. doi:10.5194/hess-17-1445-2013
- Zink, M., Kumar, R., Cuntz, M., Samaniego, L., 2016. A High-Resolution Dataset of Water Fluxes and States for Germany Accounting for Parametric Uncertainty. *Hydrol. Earth Syst. Sci. Discuss.* 1–29. doi:10.5194/hess-2016-443


30




**Figure 1.** Soil perturbation methods (Random Error Method RE, Spatially Correlated method SC and Conditional Points methods CP).

- 5 The panel on the left shows the fraction of sand of a hypothetical horizontal transect through the original soil map as orange line. Within the transect three different soil units are observed, which leads to three different sand contents. Each row of the right panels depicts the steps for setting the perturbation methods. The blue line depicts one realization of the respective perturbation method. The detailed description of these methods can be found in section 2.1. Abbreviations: var – variance, CL – correlation length.







**Figure 2.** Location of the upper Neckar catchment within Germany. The positions of the 36 gauging stations (red points) used for defining the subcatchments, the transect (dashed black line) and the two grid cells analysed (green points A and B) are depicted on the map.




**Figure 3.** Soil maps of sand [%], clay [%] and bulk density [g cm<sup>-3</sup>] and area [km<sup>2</sup>] of the soil units within the catchment.




**Figure 4.** Soil realizations obtained for the percentage of clay based on the Random Error method (RE, left column), Spatially Correlated method (SC, middle) and Conditional Points method (CP, right column). The top row shows one realization for each method and the transect (dashed black line). The bottom row depicts the spread of the 100 realizations by using the 5th and 95th percentile for the selected transect (gray area). The red line depicts one realization, whereas the black line shows the percentage of clay by the original soil map.




**Figure 5.** (a) Probability distribution of the standard deviation of the clay percentage based on 100 realizations of the soil map calculated for all grid cells and each method (RE = Random Error method; SC = Spatially Correlated method; CP = Conditional Points method). The mean and coefficient of variation of the distribution are indicated in parenthesis. (b) Standard deviation calculated by aggregating the clay percentage at subcatchments with different size. (c) Standard deviation calculated by aggregating the clay percentage at different grid resolutions.




**Figure 6.** Spatial variability of the uncertainty (CV) in the simulated model outputs ( $Q$  = generated runoff;  $AET$  = evapotranspiration;  $SM$  = soil moisture;  $GWR$  = groundwater recharge). On the left column, the results obtained based on the Random Error method (RE) over the entire catchment are depicted together with the position of the transect (dashed black line) and the two grid cells (blue points). On the right column, the CVs along the transect within the catchment based on the three perturbation methods (Random Error RE; Spatially Correlated SC; Conditional Points CP) are plotted. Vertical dashed gray lines indicate the position of the grid cells A and B within the transect. Please note that all the plots have individual limits for the y-axis.



**Figure 7.** Correlation coefficient calculated between the spatial distributions of the uncertainty (*CV*) of the simulated model outputs (*Q* = runoff; *AET* = actual evapotranspiration; *SM* = soil moisture; *GWR* = groundwater recharge) and local environmental conditions (the clay [%] is used to represent the soil; annual mean leaf area index *LAI* [ $\text{m}^2 \text{m}^{-2}$ ] is used to represent the vegetation; cumulative potential evapotranspiration *PET* [ $\text{mm a}^{-1}$ ] is used to represent the atmospheric water demand). The bars represent the mean of the correlation coefficients obtained with the three perturbation methods and the error bars the standard deviation.




**Figure 8.** Daily temporal variability of the uncertainty in state and fluxes ( $Q$  = runoff,  $AET$  = evapotranspiration,  $SM$  = soil moisture,  $GWR$  = groundwater recharge) obtained in two grid cells within the catchment obtained based on the random error method (RE). The mean (black) and the 95% confidence interval (gray) of the ensemble is depicted together with the coefficient of variation (CV) calculated at daily time step (red). Note the log y-axis for  $Q$  and  $GWR$ . Location of grid cell A and B is shown in Figure 2 and Figure 6.



**Figure 9.** Uncertainty, i.e., coefficient of variation (CV), of hydrological state and fluxes at catchments with different sizes (*SF* = streamflow, *AET* = evapotranspiration, *SM* = soil moisture, *GWR* = groundwater recharge). Exponential curves are fitted to the data. Please note that all figures have individual limits for the y-axis.





**Figure 10.** Spatio-temporal uncertainty analysis by aggregating the model results at different spatial and temporal resolutions. The three columns refer to the results obtained by (left) Random Error Method - RE, (middle) Spatially Correlated method - SC and (right) Conditional Points method - CP. The rows refers to the different model outputs (i.e.,  $Q$  = runoff, AET = actual evapotranspiration, SM = soil moisture; GWR = groundwater recharge). Note that a smooth approximation is depicted to facilitate the visualization of the actual CVs values.

**Table 1.** Parameter settings for each perturbation method (Random Error, Spatially Correlated and Conditional Points). Variogram models used for the Spatially Correlated and Conditional Points methods are showed in the supplementary material (Figure S2 and Figure S3, respectively).

<b>Perturbation method</b>	<b>Parameters</b>	<b>Specific settings</b>
Random Error	Standard deviation	7 [%] and 0.07 [g cm <sup>-3</sup> ] for texture and bulk density, respectively
Spatially correlated	Variograms and co-variograms models	Exponential models (see supplementary material, Figure S2)
	Effective variance	50 [% <sup>2</sup> ] and 0.05 [g <sup>2</sup> cm <sup>-6</sup> ] for texture and bulk density, respectively. These values are equivalent to the noise (i.e., standard deviation) introduced with the random error method.
	Correlation length	3 km
Conditional Points	Density of samples	1 sample every 3 x 3 km <sup>2</sup>
	Variograms and co-variograms models	Two nested exponential models fitted to the empirical variograms and co-variograms (see supplementary material, Figure S3)

**Table 2.** Overview of the uncertainty analysis presented and discussed.

		Perturbation methods		
n.	Uncertainty analysis	1. Random Error	2. Spatially Correlated	3. Conditional Points
1.	<p>Local uncertainty: long term temporal mean of CV at every grid point</p> $\mu_{i,t}^m = \frac{1}{N_{ens}} \sum_{j=1}^{N_{ens}} v_{i,t}^{m,j}$ $\sigma_{i,t}^m = \sqrt{\frac{1}{N_{ens}} \sum_{j=1}^{N_{ens}} (v_{i,t}^{m,j} - \mu_{i,t}^m)^2}$ $CV_{i,t}^m = \frac{\sigma_{i,t}^m}{\mu_{i,t}^m}$ $\overline{CV}_i^m = \frac{1}{T} \sum_{t=1}^T CV_{i,t}^m$	<p>Section 3.2 Figure 6 (left &amp; right black line)</p>	<p>Section 3.2 Figure 6 (right, red line)</p>	<p>Section 3.2 Figure 6 (right, green line)</p>
2.	<p>Local uncertainty: CV at every grid point</p> $CV_{i,t}^m$	<p>Section 3.3 Figure 8</p>	<p>Section 3.3</p>	<p>Section 3.3</p>
3.	<p>Uncertainty by aggregating model output at catchment of different sizes</p> $\bar{v}_{sc,t}^{m,j} = \frac{1}{N_{sc}} \sum_{i=1}^{N_{sc}} v_{i,t}^{m,j}$ $\sigma_{sc,t}^m = \sqrt{\frac{1}{N_{ens}} \sum_{j=1}^{N_{ens}} (v_{sc,t}^{m,j} - \mu_{sc,t}^m)^2}$ $CV_{sc,t}^m = \frac{\sigma_{sc,t}^m}{\mu_{sc,t}^m}$	<p>Section 3.4 Figure 9 (black line)</p>	<p>Section 3.4 Figure 9 (red line)</p>	<p>Section 3.4 Figure 9 (green line)</p>
4.	<p>Uncertainty by aggregating model output at different spatial (<math>r_d</math>) and temporal (<math>t_d</math>) resolutions</p> $\overline{CV}^{m,r_d,t_d} = \frac{1}{T} \sum_{t=1}^T \frac{1}{N_r} \sum_{i=1}^{N_r} CV_{i,t}^{m,r_d,t_d}$	<p>Section 3.5 Figure 10 (left)</p>	<p>Section 3.5 Figure 10 (middle)</p>	<p>Section 3.5 Figure 10 (right)</p>

**Table 3.** Correlation matrix of the uncertainty (*CV*) of the model outputs (*Q* = generated runoff; *AET* = actual evapotranspiration; *SM* = soil moisture; *GWR* = groundwater recharge) obtained with the three perturbation methods (Random Error, Spatially Correlated and Conditional Points).

		<i>Q</i>	<i>AET</i>	<i>SM</i>
<i>AET</i>	Random Error	0.3		
	Spatially Correlated	0.4		
	Conditional Points	0.3		
<i>SM</i>	Random Error	-0.1	0.0	
	Spatially Correlated	-0.1	-0.1	
	Conditional Points	-0.0	0.1	
<i>GWR</i>	Random Error	0.2	0.2	0.7
	Spatially Correlated	0.2	0.1	0.7
	Conditional Points	0.3	0.3	0.7