

Review on "Hydrogeological controls on spatial patterns of groundwater discharge in peatlands" by Danielle Hare, David Boutt, William Clement, Christine Hatch, Glorianna Davenport and Alex Hackmann.

This is a very innovative and well-structured paper. The methodology is faceted across many different measuring techniques, each of them enriching the overall understanding on the hydro-geological controls on groundwater discharge in a reclaimed peatland.

The paper is well-argued. The results are very interesting allowing the identification of water sources and local flow paths and providing new information on upwelling of groundwater.

Thank you for your review, we are glad you found the results relevant and interesting.

However, a simple 3-D conceptual model of the sand/peat interface might be useful for explaining the geomorphological situation and flow directions.

While a 3-D conceptual model would be helpful in explaining the full scale processes, it would be a very complex and busy image. I believe the updated 2D Figure 9 image provides the useful information for flow directions required for data discussion with combination of the Figure 2 interpolation image required to understand the peatland basin shape and the processes .

A more in-depth discussion of how hydrology and seasonality and day and night differences influence or are susceptible to influence your results would be helpful. It would be important to point out how the given window of observation is related to the longterm hydrology and particular season and how the results would differ if they were taken at a different time period. Sometimes information on the measuring dates are missing altogether.

Hare et al 2015 provides an in depth analysis of the TIR method including data collection, specifically analyzing the TIR imagery data presented in this manuscript. An additional reference has been provided to describe that how day and night differences may or may not impact temperature results. Text has also been added to the site description section as well as the results section to discuss how due to the location of this site in the aquifer the observations made during the 2-year study are representative of the present day conditions.

Dates have been added to locations where the authors determined they were missing (GPR and stream gauging).

p. 4 The site description could benefit from some background information on the geology, climatology, hydrology, vegetation and landuse and gradient. Some more detail on the flashboards and the role of the dam would be useful.

Information has been added to the background to include basic vegetation, land gradient, and climatology of the site, as well as additional geology. It is felt that the hydrology and land use information has be described with

enough detail to support the results and discussion. As the flashboard/dam was removed in 2010 there is no immediate impact to the results of this study.

p. 6 What type of GPR instrument did you use? When were they carried out? How did they relate to the hydrological situation and season? How would you expect your results to be different if carried out in a different season?

Details including the GPR make and model, as well as the date of the data collected have been included within the manuscript. We do not expect the GPR results we present in this manuscript to change seasonally nor on decadal timescales, as we are only evaluating the GPR results for depth of peat, not depth to the watertable.

p. 10 Results. A subsection on Hydrology at the beginning would be important so that the reader can obtain a better idea of the overall hydrology as well as how representative the measuring periods are. A conceptual 3-D model of the underlying topography (gravel/peat interface) would be helpful. Describe the location and recording period of the discharge stations and show some results.

A subsection of hydrology in the Section 1 has been added to focus on the hydrology of the site. Text has been added to further discuss the reasons that the observations made during this study are relevant to the current hydrologic condition in this area. A 3D model has not been added, as the authors feel Figure 2 is adequate for this purpose. Text has also been added in Section 3 to indicate the locations of the stream gauging stations as well as the recording period, as there was only one discharge measurement round recorded, the authors feel these results in text are adequate for the purposes of this study.

p. 11 It would be useful to have some air temperatures here to correlate with the groundwater temperatures in the ditches and channel (Fig. 3).

Discuss the limits of the methodology if the pictures (Fig. 4) were only taken at night.

How would the results differ if taken by day? Mention this in the methods section.

We explored adding the air temperature to Figure 3 for reference; however, the noise of the signal caused by changes in solar radiation throughout the day is found to be distracting and the scale shifts taking the focus away from the seepage dynamics. In addition, as the seepage was recorded within the drainage ditch the drainage ditch temperature is the upper boundary condition not the air. For these reasons we authors feel that this edits is not necessary.

Hare et al (2015) provides an in depth analysis of the TIR method including data collection, specifically analyzing the TIR imagery data presented in this manuscript. An additional reference has been provided to describe that how day and night differences may or may not impact temperature results.

p. 13 Why were the rates so high for temperature profiler 2? To which extend is this dependent on seasonality?

It is thought that this is an area of a preferential flow path. The rate is greater than 3 m/d, which was confirmed by the seepage meter method. This high discharge area was observed in all seasons, thus it is not thought to be dependent on seasonality.

p. 15 The explanation of "PEP" and "matrix" should come much earlier since it is

difficult to understand these without the definitions.

While this would be useful for defining the methods, the terms PFP and matrix seepage are terminology designed through the interpretation of the results, thus it would not make sense to include them earlier than section 3.2, as they presently are. Additional text has been added to clear up the beginning of section 4.1, which I hope it useful to satisfy this comment.

p. 16 Would it not be better to introduce the conceptual model at the beginning to help guide the reader throughout the text and provide a simple, conceptual 3-D model extended from Fig. 9 for the whole study area?

Introducing the conceptual model earlier in the manuscript, while helpful to walking through the methods would not make sense to the readers until the definitions of matrix and PFPs have been explored in relation to the GPR results, which occurs in the discussion section. Reference to figure 9 has been included in the early paragraphs of section 4.2 to help introduce the conceptual model as early as possible, as the data interpretation of Figure 7 must be discussed prior to the conceptual model. It is the aim of the study to use Figure 2 as the basis for the 3D conceptual site model in combination with the updated figure 9.

I recommend publishing once the comments have been addressed.

Hydrogeological controls on spatial patterns of groundwater discharge in peatlands

Danielle K. Hare^{1,2}, David F. Boutt², William P. Clement², Christine E. Hatch²,

5 Glorianna Davenport³, Alex Hackman⁴

¹AECOM Technical Services, Rocky Hill, CT 06067

²Department of Geosciences, University of Massachusetts Amherst, 611 N. Pleasant St., Amherst, MA, 01003, USA

10 ³Living Observatory at Tidmarsh Farms, 139 Bartlett Road, Plymouth, MA, 02360, USA

⁴Massachusetts Division of Ecological Restoration, 251 Causeway St., Suite 400, Boston, MA 02114

Correspondence to: Danielle K. Hare (hare.danielle@gmail.com)

15 **Abstract.** Peatland environments provide important ecosystem services including water and carbon storage, nutrient processing and retention, and wildlife habitat. However, these systems and the services they provide have been degraded through historical anthropogenic agricultural conversion and dewatering practices. Effective wetland restoration requires incorporating site hydrology and understanding groundwater discharge spatial patterns. Groundwater discharge maintains wetland ecosystems by providing
20 relatively stable hydrologic conditions, nutrient inputs, and thermal buffering important for ecological structure and function; however, a comprehensive site-specific evaluation is rarely feasible for such resource-constrained projects. An improved process-based understanding of groundwater discharge in peatlands may help guide ecological restoration design without the need for invasive methodologies and detailed site-specific investigation.

25

Here we examine a kettle-pond peatland in southeast Massachusetts historically modified for commercial cranberry farming. During the time of our investigation, a large process-based ecological restoration project was in the assessment and design phases. To gain insight into the drivers of site hydrology, we evaluated
30 the spatial patterning of groundwater discharge and the subsurface structure of the peatland complex using heat-tracing methods and ground penetrating radar. Our results illustrate that two groundwater discharge processes contribute to the peatland hydrologic system: diffuse lower-flux marginal matrix seepage; and, discrete higher-flux preferential-flow-path seepage. Both types of groundwater discharge develop through interactions with subsurface peatland basin structure, often where the basin slope is at a high angle to the regional groundwater gradient. These field observations indicate strong correlation between subsurface structures and surficial groundwater discharge. Understanding these general patterns may allow resource managers to more efficiently predict and locate groundwater seepage, confirm these using remote sensing technologies, and incorporate this information into restoration design for these critical ecosystems.
35

40 1 Introduction

Peatlands develop in response to physical, biological, and chemical processes and feedbacks. Groundwater discharge to surface water is one of the most important physical controls on peatlands stability (Siegel et al., 1995; Watters and Stanley, 2007); yet the underlying physical hydrogeologic framework governing the development of surface seepage distribution in these systems is not well understood. Preferential flow paths, hydraulic conductivity (K) anisotropy, and geologic heterogeneities likely influence the surface expression of discharge zones (Chason and Siegel, 1986; Drexler et al., 1999; Smart et al., 2012). However, these variables have been difficult to constrain due to the spatial resolution of traditional localized groundwater wetland methods (wells, boreholes, surface point measurements, etc.), and their impact on fragile flow paths. The underlying hydrologic engine of these wetlands have shown to be difficult to discern on large scale systems.

Thermal dynamics of ground and surface waters also govern critical wetland functions and can be assessed in multiple ways. Surface water thermal stability, for example, is a popular research focus in ecohydrology, as this process is important for aquatic species that rely on the low variance of groundwater temperature to buffer themselves from heat extremes and regulate their metabolism (Caissie, 2006; Deitchman and Loheide II, 2012). Temperature also controls chemical processes in ecosystem respiration, which in turn controls carbon processing and nutrient retention (Boulton et al., 1998; Davidson and Janssens, 2006; Demars et al., 2011; Lafleur et al., 2005), biodiversity (Parish et al., 2008), and overall species health (Verberk et al., 2011). Upwelling zones are linked to increased biogeochemical cycling (Sebestyen and Schneider, 2001), and also maintain species richness through the ‘edge effect’- overlap between the thermally and chemically stable groundwater ecotone and the higher oxygen environment within the main stream channel (Brunke and Gonser, 1997; Cirkel et al., 2010). An increase in wetland temperature has been shown to stimulate methane production (McKenzie et al., 2007) as well. The underlying drivers of the thermal regime of a wetland system can be caused through varying driving processes, and are important to the ecosystem services provided in the peatland.

Widespread drainage of peatlands has caused wetland degradation and loss of ecosystem services. Anthropogenic modifications such as ditching and filling create discontinuity between surface water and groundwater systems with impacts to wetland function (van Loon et al., 2009). In some parts of the world, wetland restoration is attempting to address these historical impacts. Within the United Kingdom, for

example, efforts to return natural water table levels by filling drainage ditches in peat mining areas have led to disagreements as to the cost-benefits of these specific restoration designs (Grand-Clement et al., 2013). In New England (United States), where thousands of acres of historical peatlands were converted to commercial cranberry farming in the late 1800s (Garrison and Fitzgerald, 2005), wetland restoration is 75 similarly attempting to regain natural water table levels (Price et al., 2003). An incomplete understanding of underlying hydrology and thermal regime can limit the effectiveness of such efforts.

In this research, we explore the spatial distribution of groundwater seepage through a kettle-hole peatland from the analysis of basin structure and hydraulic properties of the peatland matrix. To ~~help~~ assist in wetland restoration design at ~~the~~^{our} study site, we focus on understanding the natural processes that promote the hydrologic inputs for aquatic habitat formation and maintenance. The goals of this study are to: 80 (1) identify groundwater discharge locations and their hydrogeologic controls, (2) determine temperature dynamics of the groundwater discharge locations, and (3) evaluate the development of these seepage patterns. Through this work, insight is gained into the hydrologic driving mechanisms of peat-based wetlands ~~to help~~ support restoration of sustainable ecosystems (e.g. process-based design) (Beechie et al., 85 2010; Dahl et al., 2007).

1.1 Site Description

The site ‘Tidmarsh Farms’ is ~~consolidated~~ 3 cranberry farms, and the two largest farms (~~Tidmarsh East and Tidmarsh West~~) are separated by Beaver Dam Road ~~-(Fig. 1)~~. ~~The area surrounding this peatland site is characterized by outwash, kame deltas and ground moraines that show evidence of collapse features/deformation (Larson, 1982; Stone et al., 2011). These ice collapse features are typical of environments proximal of ice contact zones and can result in the formation of kettle holes, which there is extensive evidence of throughout the surrounding region. All three of the site’s cranberry farms were built on kettle hole peatlands between the late 1800’s and early 1900’s. In 2010, ~~+The~~ The cranberry peatlands on Tidmarsh East were taken out of production ~~in 2010; and another peatland on Tidmarsh West ther~~ ~~was~~^{were} taken out of production in 2015. ~~The This current paper study~~ concerns work on Tidmarsh East (the ~~S~~ite), which is 2.5 km² ~~(Fig. 1B)~~.~~

~~Both farms drain into the small 5 km² surficial Beaver Dam Brook Watershed, but are also a discharge location of the 360 km² Plymouth Carver Kingston Duxbury (PCKD) groundwater aquifer, thus the groundwater flowpaths contribute from a much larger hydrologic system than the surficial watershed (Fig. 1A). The PCKD aquifer surrounding the site is characterized by glacial outwash sands (Masterson et al.,~~

2009), which includes the aquifer underlying the peat. Surface water enters the site from four surface water bodies south of the site (Fresh Pond, Little Island Pond, the Arm Wetland, and Beaver Dam Pond headwaters), and drains northward into Beaver Dam Brook, an approximately 2 kilometer reach, before discharging in Bartlett Pond and then directly into Plymouth Bay (Fig. 1B).

Cranberry farming practices had applied 0.3-1.5 meters m of locally mined sand overlays native surficial soils, which was laid down as a part of a normal cranberry farming practices as of until the site retirement in 2010. This practice maintained a very low gradient across the site with a slight decline to the north, with minimal micro-topography.

During this research, which was conducted underin collaboration between Living Observatory and University of Massachusetts, a restoration project involving the private landowners, governmental agencies, and non-governmental organizations was in assessment and design phases. Project planners were specifically interested in the location of groundwater discharge across the site to help design the placement of reconstructed stream channels. In addition, the restoration design team sought to better understand the location of subsurface peat deposits, underlying site hydrology, and potential future thermal regime when considering potential restoration activities. As of 2017, the site has undergone both passive and active restoration to encourage an accelerated ecological recovery based on the conclusions of this work. In the following sections, we document our methods and findings specific to the spatial distribution of the groundwater discharge at Tidmarsh East and the implications for restoration design.

1.2 Site Hydrology

The farm is a part of the small 5 km² surficial Beaver Dam Brook Watershed, but are also a discharge location of the 360 km² Plymouth-Carver-Kingston-Duxbury (PCKD) aquifer, thus the groundwater flowpaths contribute from a much larger hydrologic system than the surficial watershed (Fig. 1A). The PCKD aquifer below the site is characterized by glacial outwash sands (Masterson et al., 2009). Surface water enters the site from four surface water bodies south of the site (Fresh Pond, Little Island Pond, the Arm Wetland, and Beaver Dam Pond headwaters), and drains northward into Beaver Dam Brook, an approximately two km reach, before discharging in Bartlett Pond and then directly into Plymouth Bay (Fig. 1B).

To facilitate drainage and irrigation, lateral and perimeter drainage ditches exist throughout farmed areas.

135 Parallel drainage ditches are located approximately every 18-35 m_{eters} throughout the entire site, and are approximately 1 meter-m wide and 0.5 meterm deep. The western agricultural cells have drainage ditches oriented east-west (Cell 3 and 4), and in the eastern cells (Cell 6 and 7) most drainage ditches are oriented north-south). When the study was conducted, the site was still predominately covered in low-lying cranberry vegetation, as well as a variety of sedges and cattails mostly adjacent to the central stream bank and marginal drainage ditches.

140

Flashboards in the dam creating the Beaver Dam Pond impoundment were permanently removed by the landowners in the fall of 2010, and since thenafter which the southern side of the farm has beenwas allowed to drain and return to a natural wetland state (Fig.1B). Data collection conducted for this research spanned 145 2012-2014, beginning two years after farming ceased, and prior to any active wetland restoration activity.

150 While the study was conducted over only a 2 year period, tThe site is located within the discharge zone of the large PCKD aquifer, and thus, short-term, drastic temporal shifts are not expected toin the hydrogeology for the processes described herein. and We expect that our observations from the study conducted over this 2-year period tareo be representative of the present-day conditions. However, tThe primary source of recharge to the PCKD aquifer is through precipitation, and which rapidly infiltrationes is rapid as the recharge deposits are outwash plains deposits (Wareham and Carver Pitted Plains) (Masterson, 2009), thus changes in the water table elevation can be expected. and tTopographic changes to base level due to isostatic rebound and sea level rise couldmay also atcontribute to the water table elevation changes (Oakley and Boothroyd, 2012). Therefore, tThe regional aquifer ismay be sensitive to long term climatic changes (Shuman et al., 2001; Newby et al., 2009); however, this question is outside the scope of this study.

160 During this research, which was conducted under collaboration between Living Observatory and University of Massachusetts, a restoration project involving the private landowners, governmental agencies, and non-governmental organizations was in assessment and design phases. Project planners were specifically interested in the location of spring emergence across the site to help guide placement of reconstructed stream channels. In addition, the restoration design team sought to better understand the location of subsurface peat deposits, underlying site hydrology, and potential future thermal regime when considering potential restoration activities. As of 2017, the site has undergone both passive and active restoration to encourage an accelerated ecological recovery based on the conclusions of this work. In the following

~~sections, we document our methods and findings specific to the spatial distribution of the groundwater discharge at Tidmarsh East and the implications for restoration design.~~

2 Methods

170 Seepage patterns within peatlands have been difficult to constrain due to large site areas and complex, dynamic substrates. At Tidmarsh Farms, we use multiple remote-sensing and direct-contact methods in this environment to connect data from different scales into a process-based understanding of peatland groundwater seepage. Ground penetrating radar (GPR) is used to evaluate the subsurface structure of the peatland basin(s), and multiple thermal methods are used to locate and analyze surficial groundwater 175 seepage patterns. Stable water isotopes are used to describe dominant water sources supplying the seepage.

Traditional hydrogeologic methods were also implemented including well transects, seepage meters and differential discharge gauging along Beaver Dam Brook. Figure 1BA illustrates the location of field measurements. Differential discharge gauging of surface water flow was performed at the site with a Marsh 180 McBirney Flo-Mate 2000. ~~A seepage meter measurements were performed using low-profile seepage meters was used to quantify groundwater discharge designed for use in flowing water (in accordance with the technique described by Rosenberry, 2008).~~

185 2.1 Resolving Subsurface Structure

GPR has been successfully used to characterize peatlands' physical structure and stratigraphy due to the strong contrast between peat and the underlying aquifer geophysical properties (e.g. water content) (e.g. Comas et al., 2005; Holden, 2004; Kettridge et al., 2008; Lowry et al., 2009; Slater and Reeve, 2002). The GPR method relies on the transmission of electromagnetic (EM) waves through the subsurface then records 190 the time and amplitude of the returning signal (reflection) to image changes in the ~~electromagnetic EM~~ properties between subsurface materials (Knight, 2001; Lowry et al., 2009). ~~In August 2012 We used collected common-offset reflection data using- Malå ProEx common offset reflection profiling to acquire GPR data with both 100 MHz and 50 MHz antennas with a transmitter-receiver separation of 1 mmeter and 2 mmeters respectively.; however, wHere, we only use of the 100 MHz data to generate interpolated maps of peat thickness, as that those data provided better resolution of the peat-sand interface given. This was due to the EMelectromagnetic (EM) properties of the peat matrix and the depth of the structure of interest.~~

which was 0-15m for this study site. Nineteen GPR line surveys were completed; all surveys used 0.3-meter-trace spacing and ranged from 100 meters to 1000 meters in total length (Fig. 1B2). The vertical resolution of the survey was 0.9 meters, based on the theory that layers can only be resolved if their thickness is greater than a quarter-wavelength.

We applied a 150 MHz high-cut filter to remove the high frequency noise, and then a 100 nano-second ns automatic gain control to compensate for signal loss with depth and distinguish deeper reflections by averaging over the time window applied and adjusting the central signal strength with respect to that result. No topographic adjustments were made, as there is-a negligible topographic variation both along the surveys and between the surveys. The peat thickness sand interface was determined in each of the radargrams. Three characteristic radargrams are shown in Figure 2.

We constrain the EM signal velocity through the peat for the GPR data analysis, and describe the peat's structure with depth by collecting nine sediment cores (Fig. 1B) with . These cores were collected and analyzed from the ground surface to the underlying sand using both a vibracorer (3) and hand corers (6). The Analysis of the cores demonstrated that the layered reflections observed in the radargrams were due to as variations in the degrees of humification. We determined an average EM velocity of 0.036 m/ns (range = 0.030-0.040 m/ns) through the peat for the five full length cores that extended to the peat-sand interface. The range of these five calculated velocities was 0.030–0.040 m/ns. This velocity range and average which are is consistent with other GPR peatland GPR research studies (0.033-0.040 m/ns) (Parsekian et al., 2012). Using these data, a 3D interpolation of the peat-sand interface was created using kriging to estimate the subsurface peat basin structure (Fig. 2). The second derivative of the maximum slope (profile curvature) was calculated from the interpolated surface to identify changes in basal peat-slope change of the peat-sand interface, and is shown in Figure 2.

2.2. Identifying locations of groundwater discharge to surface water using temperature

Heat can be used as a tracer to identify upwelling groundwater, as- air temperature oscillations on diurnal and annual timescales strongly influence surface waters, while deep (e.g. greater than approximately 10 m) groundwater temperatures remain relatively constant through time (Anderson et al., 2005; Constantz, 2008~~1998~~). Local, shallow flow-paths can be more sensitive to climatic and seasonal changes in evaporation and precipitation (Fraser et al., 2001; Kurylyk et al., 2014b; Menberg et al., 2014; Reeve et al., 2006), and may not contribute to the thermal stability of aquatic systems to the same extent as deep

(>10m), regional aquifers. This noted, during the thermal study periods, groundwater temperatures range from 10-11 °C in onsite wells below the peat.

230 **2.2.1. Fiber-Optic Distributed Temperature Sensing**

Raman spectra fiber-optic distributed temperature sensing (FO-DTS) is used for spatially extensive heat tracing in aquatic systems. Tyler et al., 2009 provides a thorough review of the details of the technology and calibration. DTS temperature data were collected with Sensor Tran Gemini HT control unit in dual-ended mode ~~on-using~~ AFL telecommunications umbilical fiber-optic cable. This FO-DTS unit allows for 235 1-m~~eter~~ spatial accuracy at 0.1°C precision over ~15 min integration times. Each FO-DTS deployment was operated for a minimum of 5 days to ensure multiple sufficiently strong diurnal signals-oscillations were captured. ~~Fifty~~50-m-long ~~eter~~ calibration coils were maintained at a constant temperature with an ice-water slush bath and/or ambient bath and were compared to an independent Onset HOBO Water Temperature Pro v2 Data Logger (U22-001) (± 0.2 °C accuracy).

240

In July and August of 2013 four FO-DTS deployments were installed, one within the drainage ditches of eastern peatland cells, and three within the western cells. We capitalize on the modified structure of the agricultural peatland surface, particularly the relatively evenly spaced drainage ditches, to thermally sample surface water in a distributed way which is not possible in more natural systems (e.g. Lowry et al., 2007).

245

The deployment sites were chosen based on previous infrared surveys (November 27st, 2012, discussed in Sect. 2.2.2), interviews with the ~~previous~~ farmer, and feasibility of installation. Each deployment ranged from 1000_m ~~to~~ -2500_m in length. Macrophyte growth was cleared during installation and continuously monitored through each deployment.

250

~~The arithmetic FO-DTS data analysis consisted of mean and standard deviation were calculated the on the for each ~5five-day time series of FO-DTS data. These data were calculated for every 1-mmeter along the fiber-optic cable to identify locations of groundwater seepage. These results and can indicate the groundwater discharge's site location and relative magnitude and permanence of groundwater discharge, which is not possible for with other methods, such as TIR or temperature probes "snapshot" in time methods~~ (Briggs et al., 2012; Hare et al., 2015; Sebok et al., 2013; Selker et al., 2006).

255 **2.2.2. Infrared Surveys**

Thermal infrared (TIR) cameras sense and quantify surface infrared (heat) radiation, and are increasingly being used to evaluate aquatic systems efficiently at large scales (Chen et al., 2009; Deitchman and

Loheide, 2009; Dugdale et al., 2016; Handcock et al., 2012; Hare et al., 2015), particularly at large sites, or
260 sites where in-situ measurements are not possible. The hand-held TIR survey was conducted to both expand the thermal survey and to compare this method to the FO-DTS data. We used a high-resolution forward-looking infrared camera (T640BX model FLIR, FLIR Systems, Inc.) with GPS and compass capabilities. The TIR method allowed for efficient spatial coverage, and allowed us to obtain thermal data unreachable with FO-DTS (Hare et al., 2015).

265

At Tidmarsh Farms East three TIR surveys were completed: July 30-31st, 2013; March 21, 2014; and one reconnaissance survey on November 27th, 2012. The July survey was used to make comparisons to the FO-DTS data as it was taken during the same time period; the March survey was used to compare seasonal variability in seepage patterns. Surveys were conducted in the morning and evening to minimize reflection interference, and all temperature collection practices and considerations for this site are described in detail in (Hare et al., (2015)). To create a spatial site map comprised of all TIR images, a single temperature (color-contoured pixel) from an aquatic point of interest was selected, and used to color an icon on the map. This allowed for georeferenced TIR data to be used quantitatively to evaluate seepage patterns by location. The relative magnitude of seepage rate is estimated based on how similar the observed temperature is to the regional groundwater temperature.s.

270

275

2.2.3. One-Dimensional Vertical Temperature Profiles

The depth to which the surface diurnal temperature signal penetrates saturated near-surface sediments depends on the period of the signal, the fluid flow velocity and direction, and the physical properties of the fluid-saturated sediment (Goto et al., 2005; Hatch et al., 2006; Irvine et al., 2016; Stallman, 1965). With
280 depth, the diurnal heat signal variation decreases in amplitude and its shifts forward in time. Much of the heat transport not explained by pure conduction is attributable to advective fluxes, which can be solved for from thermal time-series at multiple depths using simple analytical solutions to the one dimensional heat transport equation with specified boundary conditions (Hatch et al., 2006; Rau et al., 2014; Schmidt et al., 2007; Silliman et al., 1995; Stallman, 1965).

285

We analyzed four 1D vertical temperature profiles to understand the vertical subsurface fluid flux patterns at the site. Maxim iButtons temperature loggers (0.0625 °C resolution; 1°C accuracy ~~model #~~) were attached to cavities drilled into a wooden dowel, and placed into the ground such that the logger# locations were located at -2.5, -5.0, -10.0, -25.0 cm depth below the ground surface and one at +2.5 cm above the
290 surface. We coated each iButton with silicon sealant to prevent leaking/sensor damage; however, a 25%

sensor failure rate was still experienced. A 10-minute sampling interval was used for a minimum of 7 days during July and August of 2013 for each temperature time series.

Installation locations chosen represented the two types of seepage observed with the FO-DTS, and 1D vertical temperature data were collected synchronously with DTS deployments. Two additional control deployments of 1D temperature profiles were installed within/below drainage ditches. We assume that under low surficial flow conditions the system is at quasi-steady-state, allowing us to estimate (upward) seepage flux from measured surface water, groundwater, and intermediate-depth temperatures using the analytical solution to the heat transport equation derived by Turcotte and Schubert (1982) and modified by

Schmidt et al. (2007). A flux value was calculated for each collected data time step, and was averaged for each profile for the final reported flux value. Flux values were calculated four times for each profile using the range of peat porosity and range of thermal conductivity values. The thermal parameters utilized for the 1D heat transport equation are shown on Table 2.

2.3 Assessment of environmental isotopes to infer groundwater flow paths

To trace the source of the groundwater flow paths contributing to discharge, we use $\delta^{18}\text{O}$ and $\delta^2\text{H}$ to distinguish between local recharge (short flow paths) and regional recharge (long flow paths). The isotopic composition ($\delta^2\text{H-H}_2\text{O}$, $\delta^{18}\text{O-H}_2\text{O}$) of hydrogen and oxygen of the water molecule was analyzed for water samples collected from surface water (monthly), shallow ground water (seasonally), deep groundwater (seasonally), groundwater seepage (August 2013) and pore waters (October 2013). Upper 1-meter peat The four pore water samples were acquired through a manual press of samples from Russian peat cores 0-1 meter below the ground surface, and subsequently filtered for analysis.

$\delta^2\text{H-H}_2\text{O}$ and $\delta^{18}\text{O-H}_2\text{O}$ was measured by wavelength scanned cavity ring-down spectrometry on unacidified samples with a Picarro L-1102i WS-CRDS analyzer (Picarro, Sunnyvale, CA). Samples were vaporized at 110°C. International reference standards (IAEA, Vienna, Austria) were used to calibrate the instrument to the VSMOW-VSLAP scale and working standards were used with each analytical run. Three standards that isotopically bracket the sample values are run alternately with the samples. Secondary laboratory reference waters (from Boulder, Colorado; Tallahassee, Florida; and Amherst, Massachusetts) were calibrated with Greenland Ice Sheet Precipitation (GISP), Standard Light Antarctic Precipitation (SLAP) and Vienna Standard Mean Ocean Water (VSMOW) from the IAEA. The isotopic composition results are calculated based on use a rolling calibration, which calculates so that each samples error is determined by the three standards run closest in time to that of the sample. Long-term averages of internal

laboratory standard analytical results yield an instrumental precision of 0.51 ‰ for $\delta^2\text{H}-\text{H}_2\text{O}$ and 0.08 ‰ for $\delta^{18}\text{O}-\text{H}_2\text{O}$.

325

The USGS wells were sampled for groundwater isotopic compositions within the PCKD aquifer, providing regional groundwater values for the aquifer and defining the expected annual range of isotopic values for local precipitation (Table 1). The regional groundwater trend line was generated by fitting a linear regression through the USGS well isotope data from the regional PCKD aquifer.

330

34 Results

As an initial evaluation of the groundwater contribution to the site, we conducted differential discharge gauging measurements on September 15th, 2013. The location of these measurements are indicated by the purple circles on Figure 1B. The stream gained 6 L s⁻¹ discharge through Cell 7 from the Arm Pond input to the confluence with Beaver Dam Brook (1.5 km), equal to an average of 0.004 L s⁻¹ per meter of river length (Fig. 1B). Cell 3 and 4 gained 113-L s⁻¹ from the Beaver Dam Pond input to the confluence with the East side river (1 km), equal to an average of 0.113 L s⁻¹ per meter of river length. At other wetland sites seepage flux magnitudes and directions have shown to be temporally transient (Fraser et al., 2001; Sebestyen and Schneider, 2001); however due to the consistent high hydraulic gradient in the regional aquifer and the small watershed, we assume that temporal dynamics are insignificant within our data set and sufficiently static to describe the present day conditions. This assumption is supported by the two seasonally distinct infrared surveys resulting with similar seepage distribution results.

34.1 Resolving Peatland Basin Structure

The interpolation of the basal surface, or the peat-sand contact beneath the peat from GPR data, indicates four isolated peat depressions at the site, two depressions in Cell 6 and Cell 7 and two Cell 3 and Cell 4.

345 The Cells 6 and 7 have a maximum peat thickness of ~7 meters and a gradual curvature of the peat-sand interface contact than the western cells, Cell 3 and Cell 4 (Fig. 2). The western cells show a maximum peat thickness of ~10 meters, and relatively high curvature values. The basin structure of the western cells is also more complex than Cell 6 and 7, as Cell 3 and Cell 4 have pronounced undulations in the basal peat-sand contact surface, creating dramatic changes in basin shape. Particularly, there is a notably high curvature of the basal peat-sand contact interface along the western edge approximately 30 meters from the margin. The GPR profiles illustrate multiple series of normal faults beneath the peat body that are

consistent with ice melt-out and/or collapse features (Fig. 2C) typical of kettle pond origin (Kruger et al., 2009).

43.2 Thermal evaluation of groundwater seepage

355 Surface water temperatures in the main channel and ambient drainage ditch environments generally show high standard deviation, indicative of a coupling between these surface waters and air temperatures, and mean water temperatures closely tied to the seasonal surface temperature average, also indicative of surface water dominance. TIR and FO-DTS surveys were designed to detect low standard deviation and consistent mean temperature anomalies from these background conditions, which would beis indicative of groundwater inflows. ~~An alternative explanation for this low variance could be coverage via mobile sediment (Sebek et al., 2015); however, within this peatland environment this process is not expected, nor was observed.~~ The temperature results of both these surveys are presented in Hare et al. (2015). Results from both TIR and FO-DTS identified two categories of thermal anomalies: type 1 anomalies manifest as temperatures with relatively low standard deviation through time, and an anomalous heat signature that is 360 ~~approximately seasonally warmer or cooler than~~ regional groundwater temperature ~~by approximately~~ $\pm 3\text{-}5$ °C; and type 2 thermal anomalies also have a low standard deviation, but temperatures more closely resemble regional groundwater temperatures (10-11 °C). Figure 3 shows time series data collected with the FO-DTS and illustrates each of the major thermal signatures shown on site: temperatures of groundwater, the main channel, a drainage ditch, and the two thermal anomalies. We interpret these two anomalies to 365 correspond to two modes of seepage, type 1 thermal anomalies correspond to matrix seepage, and type 2 thermal anomalies correspond to preferential flow path (PFP) seepage. The two seepage types are clearly differentiated through thermal signatures, and can be isolated using the average and standard deviation of temperatures with time. The TIR surveys ~~supported and reinforced also evidenced revealed~~ these two distinct types of seepage, which were present in both the summer and winter surveys (Fig. 4).

375 TIR surveys and FO-DTS data indicate that most groundwater ~~input likely influenced temperature~~ occurs along the western edge of the Cell 3 and Cell 4, where peat is thinner or where there is strong sand/peat contact curvature in peat basin shape (Fig. 5). ~~Isolated locations of~~ ~~C~~onsistent temperatures similar to groundwater temperatures and anomalously low standard deviations exist along the linear location of 380 highest peat/sand contact curvature near the western edge of the cells, ~~as well as along edge areas with the thinnest peat~~ ~~temperature analysis yields a number of isolated locations~~. These isolated, unique locations of ~~type 2 PFP~~ seepage ~~that occurring~~ within the deeper peat represent a distinct seepage process from ~~type 1 matrix~~ seepage and PFP seeps along the edge of the peat.

385 During the March infrared survey, a high density of ~1-5 cm diameter flowing macropores within the peat
was discovered ~~on the interior of the~~ in Cell 3. The water discharging from these macropores exhibited
~~typical type 2 groundwater~~ seepage temperatures (Fig. 6), and led us to term this mode of PFP seepage. This
observation is similar to the peat macropores or ‘peat pipes’ described in previous peatland research (e.g.
Briggs et al., 2016; Cunliffe et al., 2013; Holden, 2004; Smart et al., 2012; Vandenbohede et al., 2014), but
390 the concentration of macropores in this singular location makes the northwest cell macropores observation
unique. ~~Due to We measured the high 3.0 L min⁻¹ high-flux observed from PFP seeps with a seepage meter.~~
~~Despite , even though the very few number of locations quantity is small few, theseof PFPs, their high~~
~~fluxes~~ have the potential to contribute significantly to the groundwater gain ~~across the site t sites~~ (Poulsen
et al., 2015). The peat thickness map (Fig. 5) indicates that the zone of high macropore density is an area of
395 peat thinning reaching a minimum peat thickness of 3 m, and also a location of high curvature (center of
cell 3). Rossi et al. (2012) describes similar correlation to peat thinning at ~~their-a~~ site in Finland.

34.3 1D vertical temperature profiles

400 The two seepage types and two ambient drainage ditch locations were monitored with 1D vertical
temperature profiles for seven to ten days. We expected to observe significant upwelling at this site, which
we could easily identify by a rapid attenuation of the diurnal signal with depth coupled with a characteristic
convex upward shape of mean temperature with depth (e.g. Schmidt et al., 2007). Temperatures from all
four 1D vertical temperature profiles are distinct from one another; however, all the temperature profiles,
including the “ambient” drainage ditches, ~~indicate are consistent with~~ upwelling of groundwater (convex
upward shape of mean temperature with depth in Fig.7). The surface temperature of the ambient drainage
405 ditches (temperature profiles 3 and 4) is similar to the diurnal temperature cycles measured with FO-DTS,
~~and were used as background data for the heat signature of the site. As water was shallow in most ditches~~
~~(<0.5m) with no thermally significant influx of groundwater, water in and below the ditch was expected to~~
~~have temperatures similar to, or warmer than air temperature. However, the subsurface profiler results show~~
~~a characteristic upwelling thermal envelope (convex shape); except the entire temperature envelope is 7-10~~
410 ~~°C warmer than average groundwater. In addition, the mean temperature at depth this time of year is 13-15~~
~~°C at 25 cm, significantly warmer than the groundwater temperature. Using these~~~~The 1D fluid flux~~
~~calculations of the~~ temperature time series ~~of the two drainage ditch locations to solve for 1D upward fluid~~
~~flux yielded a range of -0.028 to -0.031 m d⁻¹ and -0.067 and to -0.074 0.11 and -0.20 m d⁻¹ for these~~
~~drainage ditches. These flux values are similar to the seepage observed at temperature profiler 1. Despite~~

415

~~our intention to use these locations as control points for pure conduction temperature depth profiles, upwelling was observed beneath the ditches as well.~~

420

Temperature profiler 1 was installed at a location with a surficial temperature of 13-14 °C in August 2013. The total peat thickness at this location is 50 cm, and consistent with groundwater upwelling, minimal diurnal signal propagates to depth, and surface water exhibits relatively low variance in temperatures over time. Thermal time series estimates of flux show a modest ~~-0.23~~-~~0.146~~ to ~~-0.163~~ m d⁻¹ upwelling through the peat at this seepage location.

430

Finally, temperature profiler 2 was installed in a location with a surficial temperature consistent with groundwater temperatures of 10-11 °C in August 2013, and temperatures with depth exhibit a groundwater thermal signal throughout the entire profile. Even close to the bed interface, the streambed thermistor (2.5 cm) shows slight thermal shifts ($\sigma = 0.096$ °C), which are near to the resolution of the instrument (0.0625 °C). This unique temperature profile is indicative of high upward flux rates, as the diurnal signal cannot be resolved and there is essentially no downward conduction from above; therefore, we were unable to use the steady state analytical solution to estimate a flux rate. However, in July 2015, we deployed a seepage meter at this location and measured fluxes in excess of 3 m d⁻¹, rates which exceed the limits for analytical flux calculations.

34.4 Groundwater Discharge Source Areas

435

Groundwater discharge to the wetland complex is a mixture of shallow and deep regional flow paths. Isotopic analyses of waters from wells in the up-gradient portion of the PCKD aquifer (blue circles in Figure 8) fall along a regional groundwater trend line. We interpret this regional trend line to be characteristic of the annual isotopic composition of recharge water to the region as well as local groundwater recharge in the topographic watershed of Tidmarsh. ~~This~~these upgradient groundwater water isotopic values plot left of the global meteoric water line (GWML)(Craig, 1961), which reflects local and regional vapor recycling and a characteristic mixture of vapor sources (Koster et al., 1993). The one exception to this line is the USGS well MA-PWW 494 in Plymouth, MA which is similar to Tidmarsh in that it is downgradient of the recharge area of the PCKD aquifer. This water falls to the right of the regional groundwater trend line. Discharging and shallow groundwaters at the wetland site plot close to but off of the regional groundwater trend line. The blue diamonds (Fig. 8) represent a monthly sampling of wetland surface waters that depict a significant clustering to the right of the regional groundwater trend and evolve along a line tangent to this intersecting the deep TM groundwater. Uncharacteristically, the deepest

sampled groundwater at the site (>15 m) falls ~~even~~ to the right of the GMWL ([orange circle](#)), suggesting this water has experienced a significant enrichment in the heavy isotopes due to evaporation processes. Repeated sampling of this water reveals a consistent isotopic composition that suggests the deep groundwater beneath Tidmarsh is isotopically enriched due to evaporation from open water bodies in upgradient kettle ponds. ~~The H headwater seepage area and a repeatedly the strong discharge seepagesampled area of strong discharge~~ (large pink and red triangles in Figure 8) in the interior of the wetland complex fall along a line that represents either a mixture of this evaporated water and the regional groundwater trend (finely dashed line) or itself is simply an evaporatively evolved water. Both interpretations suggest that the source of water to the shallow groundwater wells and the large volume springs in the interior of the wetland complex are distinct. This indicates that the local flow path from the southwest to the northeast is the large-scale hydraulic gradient that dominates the observed seepage patterns. The orientation of peatland basin slope break and the regional groundwater gradient also intercept the southwest corner of the peatland where numerous high-flux groundwater seeps are located.

460 [**45 Discussion**](#)

[**45.1 Groundwater discharge types**](#)

Two types of groundwater discharge (or seepage) were identified using thermal methods, [as detailed in Section 3.2](#). [PFPFirst](#), discharge areas that have regional groundwater temperature (e.g. 10-11 °C). [Second, Matrix](#) seepage locations [are groundwater discharge](#) with temperatures that are offset ($\pm 3\text{-}5^\circ\text{C}$) from [regional](#) groundwater temperature, but have very low variance [compared to expected diurnal variations](#) and are also significantly distinct from local surface water temperatures. Both seepage types appear to strongly buffer stream temperatures, illustrated by low variance when examined through time (FO-DTS data). [A low variance could have also been caused mobile sediment \(Sebok et al., 2015\); however, within this peatland environment this process is not expected, nor was observed.](#) The identification of these two distinct seepage types using multiple methods and during distinct seasons indicates different mechanisms for generation of each of these seepage patterns. Figure 5 combines [these two types of both matrix and PFP](#) seepage observed with either FO-DTS or TIR to evaluate spatial patterning and consistencies, and shows how the two types are related to one another as well as to patterns of high basal curvature.

475 | Consistent (low standard deviation) and groundwater-like temperatures (10-11°C) of the [PFPtype 2](#) seepage indicate very high flux ($>3 \text{ m d}^{-1}$ was confirmed with seepage meter measurements). Given the low vertical K of peat matrices, sustaining such high fluxes would require seemingly implausible hydraulic gradients,

certainly far above the vertical hydraulic gradients observed on site. Therefore, it is highly likely that this seepage does not occur as flow through the peat ~~media/matrix-itself~~, but instead focused, high discharge,

480 conduit flow, consistent with “short-circuit discharges” described by Conant Jr. (2004). Focused flow in conduits through the peat was observed in the field at Tidmarsh Farms (Fig. 6), and by Briggs et al. (2016), and has been documented through visual descriptions of peat pipes, or macropores at other locations (Baird, 1997; Beckwith et al., 2003; Cunliffe et al., 2013; Holden, 2004; Smart et al., 2012; Wallage and Holden, 2011). However, the spatial extent of these preferential flow zones has not been previously demonstrated.

485 Due to their high flux, physical isolation, and focused nature, we refer to this type of seepage as ~~preferential flow path (PFP)~~ seeps ~~in the following discussion.~~

Data represented by ~~type 4matrix~~ seepage show that surface water diurnal temperatures are also buffered in these zones and are distinct from most ambient surface temperatures. This observation could indicate

490 shallow aquifer groundwater discharge, which is more influenced by atmospheric temperatures than deeper regional flow (Kurylyk et al., 2014a; Menberg et al., 2014). However, consistent temperatures in the site’s shallow groundwater wells and 1D temperature profiles indicate that these seepage temperatures are controlled by a lower flux rather than distinct atmospheric-influenced shallow flow paths. These ~~type 4matrix~~

495 seeps indicate that while vertical upwelling fluxes are present, they are much smaller than PFP discharge zones, and must be controlled by a different mechanism. Thermal profilers yielded vertical flux rates consistent with a low to moderate upwelling through porous media according to Conant Jr. (2004);

which would be typical of the hydraulic properties associated with peat, and thus, ~~which is the reason~~ we refer to locations with this signature as “matrix” seeps. The two seepage types, PFP and Matrix seepage, are similar to the “point” and “diffuse” peat seepage categories defined by Rossi et al. (2012), but rather than focusing on the area of influence, instead highlight the physical structure that governs the process which ultimately generates seepage in these peatland seepage zones.

505 ~~Within the drainage ditches that have no thermal indication of groundwater discharge, a vertical flux was nevertheless present at a magnitude similar to matrix seep flux. This was observed in both temperature profiles 3 and 4 (Fig. 7). A longer flow path within the peat’s catotelm may explain the similar vertical flux rates to matrix seepage, but with a warmer surface expression. This indicates upwelling throughout the entire site; though these locations do not appear to contribute to the thermal buffering of the surface waters.~~

45.2 Subsurface Structural Control on the Spatial Distribution of Seepage Types

Matrix seeps were plentiful within approximately 30 m of the peatland edge (Fig. 5), consistent with margin seepage observed in lake environments (Rosenberry et al., 2010; Sebestyen and Schneider, 2004;

510 Sebek et al., 2013; Winter, 2001) and other wetlands (Freeze, 1988; Labaugh et al., 1998). The peat is 0.1-
3.0 meters thick along the margin where matrix seepage occurs (Fig. 3), which is generally significantly
thinner than locations of observed interior PFP seepage. Matrix seeps generally occur in the thinnest peat
zones, and typically decrease rapidly with distance from the peatland edge toward the interior slope change,
after which no thermally distinct groundwater discharge points are observed (Fig. 5). While evidence for

515 PFP seepage does occur as well in these shallow areas, matrix seepage is more consistent within this
shallow peat environment. This is shown as a conceptual model in Figure 9, based on temperature data
collected proximal to GPR line 7.1 (radargram shown in Fig.2C). Similar landscape-scale observations
have been made within lakes and wetlands (e.g. Cherkauer and Zager, 1989; Sebek et al., 2013), and as
kettle hole peatlands typically form from initially open water bodies, there are logical similarities in basic
520 processes between the two environments.

Discrete seepage zones may reflect zones of higher effective K than the surrounding peat matrix, which
could be explained by littoral-zone migration in the lake to wetland evolution as the water table fluctuates
and migrates. In lake environments, diffuse matrix seepage occurs because of an increase in K at the edge
of the lake caused by “erosional deposition,” whereby focused wave and current action disrupt and erode
525 sediments, particularly mobilizing the finest sediments elsewhere, and concentrating larger particles,
indicative of these higher-energy environments in these locations. Preferentially stronger flow paths are
thus concentrated at the break in land surface slope (Blume et al., 2013; Casson et al., 2010; Cherkauer and
McKereghan, 1991; McBride and Pfannkuch, 1975; Rosenberry et al., 2010; Winter, 1981). Previous work

530 proposes that seepage flux decreases exponentially with distance from shore of a lake (Cherkauer and
Zager, 1989; McBride and Pfannkuch, 1975), which is qualitatively confirmed by our data. Paleoclimate
reconstructions have demonstrated that the regional water table around Tidmarsh has been increasing in
elevation since the Laurentide ice sheet retreated ~10 ka ago, with 2-3 significant low stands (Newby et al.,
2000, 2009). Therefore, we hypothesize that the extent of the matrix seepage observed along the western
edge of the peatland is a result of this lake transgression and coincident decrease in deposition of organic
535 material. Here the lower K of the peat matrix intersects with shallow groundwater flowpaths, strongly
affecting lateral hydraulic gradients and driving upward flux; a process which likely generates much of the
observed matrix seepage (Fig.9). Figure 9 provides a conceptual model of this process, and isThis
observation is supported by similar seepage processes observed in riverine systems (Sophocleous, 2002),

wetland (Larsen et al., 2007), lake (Bakker and Anderson, 2002; Winter, 1981) and hillslope environments

540 (Shaw et al., 2017; Winter et al., 1998).

In contrast to the matrix seepage, PFP seepage was less common and spatially disconnected from similar flux seeps (Fig. 5). Similar to matrix seepage, PFP seepage exhibits low standard deviation of temperature (Fig. 3), but PFP seep temperatures were much closer to average regional groundwater temperature. This indicates that PFP seepage waters have very short residence times within peatland sediments, which may

545 have important implications for nutrient transformations within them. ~~At~~ ~~At some~~ PFP seeps ~~the~~ peat is generally thicker and located more toward the interior of the peatland rather than along the margin where

matrix seepage zones are found in addition to being found between the peatland edge and the area with high basal curvature values(Fig. 5 and Fig.9). Typical interior PFP flow path lengths from the sandy

aquifer below the peat to the surface should be much greater than for matrix seeps;~~–h~~ However, the thermal

550 signature seems to contradict this;~~–h~~ therefore, PFP seepage zones must ~~therefore~~ be generated through a unique hydraulic process from matrix seeps. Since PFP seeps at Tidmarsh Farms correlate with significant

slope changes, or locations of high curvature, these isolated seepage zones must be generated by an abrupt change in horizontal K, and the PFP seep locations closer to the edge may be a result of zones of inherent

matrix weaknesses such as varying degrees of humification caused by vegetative difference and water level, or other disruptions in the peat matrix including plant rooting and desiccation ‘cracks’ as proposed by

(Smart et al., 2012) (Fig.9).

An abrupt change from high to low K has long been known to promote the transition from horizontal to vertical flow (Freeze and Witherspoon, 1967). Lowry et al., (2009) hypothesized this process to explain developed seepage within the interior of a peatland through using 3D numerical groundwater flow models.

560 As horizontally flowing regional groundwater encounters a low-conductivity peatland, it is forced to go through or around it, causing pressure to increase where the abrupt change in the K from the sand to catotelm peat matrix occurs (Fig.9). PFP seeps~~s~~ develop as a fast-pathway to the surface, a pressure-relief valve, where these localized increases in aquifer pressure at the base of the peat matrix translate into strong, sustained discharge of unaltered regional groundwater to the surface.

565 Rosenberry et al. (2010) notes that in lake bottoms, a significant upward seepage velocity can maintain a locally high K as the upward force may suspend smaller particles within the water column. Particulate organic matter and lacustrine sediment have a very low settling velocity, therefore if the upward force that groundwater seepage induces is greater than the settling velocity, only organic matter with a high mass will be able to accumulate over these lake seepage locations. This would cause the peat matrix to have a

570 relatively high porosity and a high permeability compared to its surrounding very low permeability matrix. These locations will continue to be zones of weakness through the formation of the peatland. Thus, we hypothesize that high-flux PFP seepage zones persist through the transition from lake to peatland environment due to the inability of fine sediments and organic matter to accumulate over these high flux locations. Still, these locations of consistently high hydraulic gradient will also continually take advantage
575 of inherent matrix weaknesses,~~such as varying degrees of humification caused by vegetative difference and water level, or other disruptions in the peat matrix including plant rooting and desiccation ‘cracks’ as proposed by (Smart et al., 2012)~~. However, the underlying mechanics of PFP seepage in the interior/deeper peat are caused by the interception of the regional groundwater gradient and high curvature peat subsurface structure (Fig.9).

580 The orientation of peatland basin slope break (high basin profile curvature) and the southwest to northeast regional groundwater gradient dictates the observed pattern of strong seepage along the western boundary, which is supported by isotopic analysis. PFP and matrix seep waters both exhibit isotopic signatures consistent with a mixture of local groundwater and regional recharge signature (Fig. 8). This observation is further reinforced by the increase in net groundwater gain through the western cells, as well as a large
585 number of PFP seeps in the southwestern portion of the site (Fig. 5).

56 Conclusion

Subsurface basin shape exhibits significant control on the spatial distribution of groundwater discharge within peatland environments. As horizontal groundwater flow intercepts the peat matrix, two types of seepage develop: matrix and preferential flow path seepage. Matrix seepage is defined by a low standard deviation in temperature and surface temperature similar to groundwater $\pm 3\text{--}5^\circ\text{C}$, consistent with relatively 590 low-flux seepage. Low fluxes are produced where the regional groundwater flow paths intercept the low-K peat at the basin ‘shoreline’, inducing upward flow through relatively thin (0.1-3.0 meters) peat. The second type of observed discharge, PFP seepage, has a surface temperatures~~s~~ essentially indistinguishable from deep regional groundwater temperature. This indicates very strong upwelling fluxes at these locations
595 and little time for conductive heat losses/gains. Locations of PFP seeps appear along the periphery of the peatland, but more notably also correlate with high rates of basal peat slope change (curvature) of the peat basin (Fig.9). These seeps develop where the regional groundwater flow path intercepts a secondary slope change and where there is a stark change in K between the high-K sand aquifer material and the low-K peat. Together, these physical features generate large pressures, induce localized zones of high vertical
600 hydraulic gradient and drive large seepage fluxes upward. Because PFP seeps occur typically in locations

with thicker peat and yet maintain close to groundwater temperatures, they must have a much higher vertical hydraulic gradient and/or higher effective K than the matrix seeps. Through multiple lines of evidence, we conclude that the development and spatial distribution of mineralogical peatland seepage is strongly controlled by the interaction between the subsurface basin structure, physical process within the peat structure and hydraulic gradient.

Through our results, we establish a predictable pattern of seepage, consistent across the coastal site that is explained by knowledge of basin shape and regional hydraulic gradient. This information provides valuable insight for water resource managers to better understand the natural forces driving groundwater seepage. This knowledge, in turn, may be used in the restoration design of degraded peatland systems.

Knowing where seepage is expected to occur naturally across a site allows for the development of more sustainable restoration designs that work with the land, and not against it. In retired cranberry farms, for example, channels may be relocated to intercept springs to maintain cooler water temperatures. This knowledge can also guide the location of targeted intensive grading. For example, as was done at Tidmarsh Farms, the dense cranberry mat can be broken up mechanically to encourage groundwater expression on former dry farm surfaces and access native seed banks below. Incorporating this data into a restoration design will greatly aid the ability to predict and achieve desired ecosystem outcomes, making restoration projects more efficient, both ecologically and monetarily.

This research provides a process-based investigation of the subsurface hydrodynamics within a peatland. While a peat matrix exhibit strongly heterogeneous and anisotropic tendencies, large-scale patterns occur and can be predicted. These patterns are dependent on basin shape, peat accumulation history, and underlying aquifer flow paths. The importance of groundwater flow paths surrounding the peatland and resulting seepage patterns emphasizes that peatlands are not isolated entities from the groundwater system and cannot be treated as such. Observed large-scale seepage patterning provides insight that may help explain vegetation patterning, macropore development, and other localized peat dynamics that have been unidentified in the past, and greatly aid peatland management and restoration to establish more naturally sustainable, efficient practices.

Disclaimer

The views and opinions expressed in this article are those of the authors and do not necessarily reflect the official policy or position of AECOM Technical Services.

Acknowledgments

This research would like to acknowledge the support of Evan Shulman for site access, field support and good humor, Henry Eshbaugh, Eric Van Dam, Steve Hurley and the many volunteers who support the data collection efforts site co-ordination. Much gratitude is given to John Lane and Martin Briggs of the U.S. Geological Survey, Branch of Hydrogeophysics for equipment rental and technical support. Also, we thank
635 | Jon Woodruff of the University of Massachusetts, Amherst for use of his laboratory² equipment, data processing software, student support and technical guidance.

References

- 640 Anderson, J. K., Wondzell, S. M., Gooseff, M. N. and Haggerty, R.: Patterns in stream longitudinal profiles and implications for hyporheic exchange flow at the H.J. Andrews Experimental Forest, Oregon, USA, *Hydrological Processes*, 19(15), 2931–2949, 2005.
- Baird, A. J.: Field estimation of macropore functioning and surface hydraulic conductivity in a fen peat, *Hydrological Processes*, 11, 287–295, 1997.
- 645 Bakker, M. and Anderson, E. I.: Comment on “Numerical investigation of lake bed seepage patterns: effects of porous medium and lake properties” by Genereux, D., and Bandopadhyay, I., 2001. *Journal of Hydrology* 241, 286–303, *Journal of Hydrology*, 258(1–4), 260–264, doi:10.1016/S0022-1694(01)00570-4, 2002.
- Beckwith, C. W., Baird, A. J. and Heathwaite, A. L.: Anisotropy and depth-related heterogeneity of 650 hydraulic conductivity in a bog peat. II: modelling the effects on groundwater flow, *Hydrological Processes*, 17(1), 89–101, doi:10.1002/hyp.1116, 2003.
- Beechie, T. J., Sear, D. A., Olden, J. D., Pess, G. R., Buffington, J. M., Moir, H., Roni, P. and Pollock, M. M.: Process-based principles for restoring river ecosystems, *BioScience*, 60(3), 209–222, doi:10.1525/bio.2010.60.3.7, 2010.
- 655 Blume, T., Krause, S., Meinikmann, K. and Lewandowski, J.: Upscaling lacustrine groundwater discharge rates by fiber-optic distributed temperature sensing, *Water Resources Research*, 49, 7929–7944, doi:10.1002/2012WR013215, 2013.
- Boulton, A. J., Findlay, S., Marmonier, P., Stanley, E. H. and Valett, H. M.: The functional significance of the hyporheic zone in streams and rivers, *Annual Review of Ecology and Systematics*, 29, 59–81, 1998.
- 660 Briggs, M. A., Lautz, L. K., McKenzie, J. M., Gordon, R. P. and Hare, D. K.: Using high-resolution distributed temperature sensing to quantify spatial and temporal variability in vertical hyporheic flux, *Water Resources Research*, 48(2), 1–17, doi:10.1029/2011WR011227, 2012.
- Briggs, M. A., Hare, D. K., Boutt, D. F., Davenport, G. and Lane, J. W.: Thermal infrared video details

- multiscale groundwater discharge to surface water through macropores and peat pipes, *Hydrological Processes*, 30(14), 2510–2511, doi:10.1002/hyp.10722, 2016.
- 665 Brunke, M. and Gonser, T.: The ecological significance of exchange processes between rivers and groundwater, *Freshwater Biology*, 37(1), 1–33, 1997.
- Brunke, M. and Gonser, T.: The ecological significance of exchange processes between rivers and groundwater, *Freshwater Biology*, 37(1), 1–33, 1997.
- Caissie, D.: The thermal regime of rivers: a review, *Freshwater Biology*, 51(8), 1389–1406, doi:10.1111/j.1365-2427.2006.01597.x, 2006.
- 670 Casson, N. J., Eimers, M. C. and Buttle, J. M.: The contribution of rain-on-snow events to nitrate export in the forested landscape of south-central Ontario, Canada, *Hydrological Processes*, 24(14), 1985–1993, doi:Doi 10.1002/Hyp.7692, 2010.
- Chason, D. B. and Siegel, D. I.: Hydraulic conductivity and related physical properties of peat, Lost River peatland, northern Minnesota, *Soil Science*, 142(2), 91–101, 1986.
- 675 Chen, X. H., Song, J. X., Cheng, C., Wang, D. M. and Lackey, S. O.: A new method for mapping variability in vertical seepage flux in streambeds, *Hydrogeology Journal*, 17(3), 519–525, doi:Doi 10.1007/S10040-008-0384-0, 2009.
- Cherkauer, D. S. and McKereghan, P. F.: Ground-water discharge to lakes: focusing in embayments, *Ground Water*, 29(1), 72–80, 1991.
- 680 Cherkauer, D. S. and Zager, J. P.: Groundwater interaction with a kettle-hole lake: relation of observations to digital simulations, *Journal of Hydrology*, 109(1–2), 167–184, doi:10.1016/0022-1694(89)90013-9, 1989.
- Cirkel, D. G., Witte, J. M. and van der Zee, S. E. A. T. M.: Estimating seepage intensities from groundwater level time series by inverse modelling: A sensitivity analysis on wet meadow scenarios,
- 685 Journal of Hydrology, 385(1–4), 132–142, doi:10.1016/j.jhydrol.2010.02.009, 2010.
- Comas, X., Slater, L. and Reeve, A.: Stratigraphic controls on pool formation in a domed bog inferred from ground penetrating radar (GPR), *Journal of Hydrology*, 315(1–4), 40–51, doi:10.1016/j.jhydrol.2005.04.020, 2005.
- Conant Jr, B.: Delineating and Quantifying Ground Water Discharge Zones Using Streambed Temperatures, *Ground Water*, 42(2), 243–257, 2004.
- 690 Constantz, J. : Heat as a tracer to determine streambed water exchanges, *Water Resources Research*, 44, doi:10.1029/2008WR006996, 2008. Constantz, J.: Interaction between stream temperature, streamflow, and groundwater exchanges in Alpine streams, *Water Resources Research*, 34(7), 1609–1615, 1998.
- Craig, H.: Isotopic Variations in Meteoric Waters, *Science*, 133(3465), 1702–1703, doi:10.1126/science.133.3465.1702, 1961.
- 695 Cunliffe, A. M., Baird, A. J. and Holden, J.: Hydrological hotspots in blanket peatlands: Spatial variation in peat permeability around a natural soil pipe, *Water Resources Research*, 49(9), 5342–5354,

- doi:10.1002/wrcr.20435, 2013.
- Dahl, M., Nilsson, B., Langhoff, J. H. and Refsgaard, J. C.: Review of classification systems and new
700 multi-scale typology of groundwater – surface water interaction, *Journal of Hydrology*, 344, 1–16,
doi:10.1016/j.jhydrol.2007.06.027, 2007.
- Davidson, E. A. and Janssens, I. A.: Temperature sensitivity of soil carbon decomposition and feedbacks to
climate change., *Nature*, 440(7081), 165–73, doi:10.1038/nature04514, 2006.
- Deitchman, R. and Loheide II, S. P.: Sensitivity of Thermal Habitat of a Trout Stream to Potential Climate
705 Change, Wisconsin, United States, *Journal of American Water Resources Association*, 48(6), 1091–1103,
doi:10.1111/j.1752-1688.2012.00673.x, 2012.
- Deitchman, R. S. and Loheide, S. P.: Ground-based thermal imaging of groundwater flow processes at the
seepage face, *Geophysical Research Letters*, 36(14), L14401, doi:10.1029/2009GL038103, 2009.
- Demars, B. O. L., Russell Manson, J., Ólafsson, J. S., Gíslason, G. M., Gudmundsdóttir, R., Woodward, G.,
710 Reiss, J., Pichler, D. E., Rasmussen, J. J. and Friberg, N.: Temperature and the metabolic balance of
streams, *Freshwater Biology*, 56(6), 1106–1121, doi:10.1111/j.1365-2427.2010.02554.x, 2011.
- Drexler, J. Z., Bedford, B. L., Scognamiglio, R. and Siegel, D. I.: Fine-scale characteristics of groundwater
flow in a peatland, *Hydrological Processes*, 13, 1341–1359, 1999.
- Dugdale, S. J., Bergeron, N. E. and St-Hilaire, A.: Spatial distribution of thermal refuges analysed in
715 relation to riverscape hydromorphology using airborne thermal infrared imagery, *Remote Sensing of
Environment*, doi:10.1016/j.rse.2014.12.021, 2016.
- Fraser, C. J. D., Roulet, N. T. and Lafleur, M.: Groundwater flow patterns in a large peatland, *Journal of
Hydrology*, 246(1–4), 142–154, doi:10.1016/S0022-1694(01)00362-6, 2001.
- Freeze, A. R.: A conceptual framework for assessing cumulative impacts on the hydrology of nontidal
720 wetlands, *Environmental Management*, 12(5), 605–620, 1988.
- Freeze, R. A. and Witherspoon, P. A.: Theoretical analysis of regional groundwater flow- 2. Effect of
water-table configuration and subsurface permeability variation, *Water Resources Research*, 3(2), 623–634,
1967.
- Garrison, P. J. and Fitzgerald, S. A.: The role of shoreland development and commercial cranberry farming
725 in a lake in Wisconsin , USA, *Journal of Paleolimnology*, 33(2), 169–188, 2005.
- Goto, S., Yamano, M. and Kinoshita, M.: Thermal response of sediment with vertical fluid flow to periodic
temperature variation at the surface, *Journal of Geophysical Research B: Solid Earth*, 110(1), B01106,
doi:10.1029/2004JB003419, 2005.
- Grand-Clement, E., Anderson, K., Smith, D., Luscombe, D., Gatis, N., Ross, M. and Brazier, R. E.:
730 Evaluating ecosystem goods and services after restoration of marginal upland peatlands in South-West
England, edited by S. Wan, *Journal of Applied Ecology*, 50(2), 324–334, doi:10.1111/1365-2664.12039,

2013.

Handcock, R. N., Torgersen, C. E., Cherkauer, K. A., Gillespie, A. R., Tockner, K., Faux, R. N. and Tan, J.: Thermal infrared remote sensing of water temperature in riverine landscapes, in *Fluvial Remote Sensing for Science and Management*, pp. 85–113, John Wiley & Sons Inc., 2012.

Hare, D. K., Briggs, M. A., Rosenberry, D. O., Boutt, D. F. and Lane, J. W.: A comparison of thermal infrared to fiber-optic distributed temperature sensing for evaluation of groundwater discharge to surface water, *Journal of Hydrology*, 530, 153–166, doi:10.1016/j.jhydrol.2015.09.059, 2015.

Hatch, C. E., Fisher, A. T., Revenaugh, J. S., Constantz, J. and Ruehl, C.: Quantifying surface water-groundwater interactions using time series analysis of streambed thermal records: method development,

Water Resources Research, 42(10), n/a-n/a [online] Available from:

<http://doi.wiley.com/10.1029/2005WR004787> (Accessed 17 July 2014a), 2006.

Hatch, C. E., Fisher, A. T., Revenaugh, J. S., Constantz, J. and Ruehl, C.: Quantifying surface water-groundwater interactions using time series analysis of streambed thermal records: method development,

Water Resources Research, 42(10), 2006b.

Holden, J.: Hydrological connectivity of soil pipes determined by ground-penetrating radar tracer detection, *Earth Surface Processes and Landforms*, 29(4), 437–442, doi:10.1002/esp.1039, 2004.

Irvine, D. J., Briggs, M. A., Lautz, L. K., Gordon, R. P., McKenzie, J. M. and Cartwright, I.: Using Diurnal Temperature Signals to Infer Vertical Groundwater-Surface Water Exchange., *Ground water*,

doi:10.1111/gwat.12459, 2016.

Kettridge, N., Comas, X., Baird, A., Slater, L., Strack, M., Thompson, D., Jol, H. and Binley, A.: Ecohydrologically important subsurface structures in peatlands revealed by ground-penetrating radar and complex conductivity surveys, *Journal of Geophysical Research*, 113, 1–15, doi:10.1029/2008JG000787, 2008.

Knight, R.: Ground penetrating radar for environmental applications, *Annual Review of Earth and Planetary Sciences*, 29, 229–255, 2001.

Koster, R. D., de Valpine, D. P. and Jouzel, J.: Continental water recycling and H_2^{18}O concentrations, *Geophysical Research Letters*, 20(20), 2215–2218, doi:10.1029/93GL01781, 1993.

Kruger, J., Kjaer, K. H. and Schomacker, A.: 7 dead-ice environments: a landsystems model for a debris-charged, stagnant lowland glacier margin, Kötlujökull, *Developments in Quaternary Science*, 13, 105–126, 2009.

Kurylyk, B. L., MacQuarrie, K. T. B. and Voss, C. I.: Climate change impacts on the temperature and magnitude of groundwater discharge from shallow, unconfined aquifers, *Water Resources Research*, 50(4), 3253–3274, doi:10.1002/2013WR014588, 2014a.

Kurylyk, B. L., MacQuarrie, K. T. B., Linnansaari, T., Cunjak, R. a. and Curry, R. A.: Preserving,

augmenting, and creating cold-water thermal refugia in rivers: concepts derived from research on the Miramichi River, New Brunswick (Canada), *Ecohydrology*, 8(6), 1095–1108, doi:10.1002/eco.1566, 2014b.

770 Labaugh, J. W., Winter, T. C. and Rosenberry, D. O.: Hydrologic functions of prairie wetlands, *Great Plains Research*, 8, 17–37, 1998.

Lafleur, P. M., Moore, T. R., Roulet, N. T. and Frolking, S.: Ecosystem respiration in a cool Temperate bog depends on peat temperature but not water table, *Ecosystems*, 8(6), 619–629, doi:10.1007/s10021-003-0131-2, 2005.

775 Larsen, L. G., Harvey, J. W. and Crimaldi, J. P.: A delicate balance: ecohydrological feedbacks governing landscape morphology in a lotic peatland, *Ecological Monographs*, 77(4), 591–614, 2007.

Letts, M. G., Roulet, N. T., Comer, N. T., Hall, B., Sherbrooke, O., Ha, Q., Skarupa, M. R. and Verseghe, D. L.: Parametrization of Peatland Hydraulic Properties for the Canadian Land Surface Scheme, *Atmosphere-Ocean*, 38(1), 141–160, 2000.

van Loon, A. H., Schot, P. P., Griffioen, J., Bierkens, M. F. P., Batelaan, O. and Wassen, M. J.:

780 Throughflow as a determining factor for habitat contiguity in a near-natural fen, *Journal of Hydrology*, 379(1–2), 30–40, doi:10.1016/j.jhydrol.2009.09.041, 2009.

Lowry, C. S., Walker, J. F., Hunt, R. J. and Anderson, M. P.: Identifying spatial variability of groundwater discharge in a wetland stream using a distributed temperature sensor, *Water Resources Research*, 43(10), 1–9, doi:10.1029/2007WR006145, 2007.

785 Lowry, C. S., Fratta, D. and Anderson, M. P.: Ground penetrating radar and spring formation in a groundwater dominated peat wetland, *Journal of Hydrology*, 373(1–2), 68–79, doi:10.1016/j.jhydrol.2009.04.023, 2009.

Masterson, J. P., Carlson, C. S. and Walter, D. A.: Hydrogeology and simulation of groundwater flow in the Plymouth-Carver-Kingston-Duxbury aquifer system , southeastern Massachusetts, *Scientific Investigations Report 2009–5063*, 110p, 2009.

McBride, M. S. and Pfannkuch, H. O.: Distribution of seepage within lakebeds, *US Geological Survey Journal of Research*, 3(5), 505–512, 1975.

McKenzie, J. M., Siegel, D. I., Rosenberry, D. O., Glaser, P. H. and Voss, C. I.: Heat transport in the Red Lake Bog , Glacial Lake Agassiz Peatlands, *Hydrological Processes*, 21, 369–378, doi:10.1002/hyp, 2007.

795 Menberg, K., Blum, P., Kurylyk, B. L. and Bayer, P.: Observed groundwater temperature response to recent climate change, *Hydrology and Earth System Sciences*, 18(11), 4453–4466, doi:10.5194/hess-18-4453-2014, 2014.

Newby, P. E., Killoran, P., Waldorf, M. R., Shuman, B. N., Webb, R. S. and Webb, T.: 14,000 years of sediment, vegetation, and water-level changes at the Makepeace Cedar swamp, southeastern Massachusetts,

- 800 Quaternary Research, 53(3), 352–368, doi:10.1006/qres.1999.2120, 2000.
- Newby, P. E., Donnelly, J. P., Shuman, B. N. and MacDonald, D.: Evidence of centennial-scale drought from southeastern Massachusetts during the Pleistocene/Holocene transition, Quaternary Science Reviews, 28(17–18), 1675–1692, doi:10.1016/j.quascirev.2009.02.020, 2009.
- Parish, F., Sirin, A., Charman, D., Joosten, H., Minayeva, T. and Silvius, M.: Assessment on peatlands, 805 biodiversity and climate change: main report., edited by L. Stringer, Global Environment Centre, Kuala Lumpur and Wetlands International. Wageningen., 2008.
- Parsekian, A. D., Slater, L., Ntarlagiannis, D., Nolan, J., Sebesteyen, S. D., Kolka, R. K. and Hanson, P. J.: Uncertainty in Peat Volume and Soil Carbon Estimated Using Ground-Penetrating Radar and Probing, Soil Science Society of America Journal, 76(5), 1911, doi:10.2136/sssaj2012.0040, 2012.
- 810 Poulsen, J. R., Sebok, E., Duque, C., Tetzlaff, D. and Engesgaard, P. K.: Detecting groundwater discharge dynamics from point-to-catchment scale in a lowland stream: combining hydraulic and tracer methods, Hydrology and Earth System Sciences, 19(4), 1871–1886, doi:10.5194/hess-19-1871-2015, 2015.
- Price, J. S., Heathwaite, A. L. and Baird, A. J.: Hydrological processes in abandoned and restored peatlands : An overview of management approaches, Wetlands Ecology and Management, 11, 65–83, 2003.
- 815 Rau, G. C., Andersen, M. S., McCallum, A. M., Roshan, H. and Acworth, R. I.: Heat as a tracer to quantify water flow in near-surface sediments, Earth-Science Reviews, 129, 40–58, doi:10.1016/j.earscirev.2013.10.015, 2014.
- Reeve, A. S., Evensen, R., Glaser, P. H., Siegel, D. I. and Rosenberry, D.: Flow path oscillations in transient ground-water simulations of large peatland systems, Journal of Hydrology, 316(1–4), 313–324, 820 doi:10.1016/j.jhydrol.2005.05.005, 2006.
- Rezanezhad, F., J. S. Price, W. L. Quinton, B. Lennartz, T. Milojevic, and P. Van Cappellen, Structure of peat soils and implications for water storage, flow and solute transport: A review update for geochemists, Chemical Geology, 429, 75-84, doi: 10.1016/j.chemgeo.2016.03.010, 2016.
- Rosenberry, D. O.: A seepage meter designed for use in flowing water, Journal of Hydrology, 359(1–2), 825 118–130, 2008.
- Rosenberry, D. O., Toran, L. and Nyquist, J. E.: Effect of surficial disturbance on exchange between groundwater and surface water in nearshore margins, Water Resources Research, 46(6), n/a-n/a, doi:10.1029/2009WR008755, 2010.
- Rossi, P. M., Ala-aho, P., Ronkanen, A. and Kløve, B.: Groundwater–surface water interaction between an 830 esker aquifer and a drained fen, Journal of Hydrology, 432–433, 52–60, doi:10.1016/j.jhydrol.2012.02.026, 2012.
- Schmidt, C., Conant Jr., B., Bayer-Raich, M. and Schirmer, M.: Evaluation and field scale application of an analytical method to quantify groundwater discharge using mapped streambed temperatures, Journal of

- Hydrology, 347, 292–307, 2007.
- 835 Sebestyen, S. D. and Schneider, R. L.: Dynamic temporal patterns of nearshore seepage flux in a headwater Adirondack lake, *Journal of Hydrology*, 247, 137–150, 2001.
- Sebestyen, S. D. and Schneider, R. L.: Seepage patterns, pore water, and aquatic plants: hydrological and biogeochemical relationships in lakes, *Biogeochemistry*, 68(3), 383–409, 2004.
- 840 Sebok, E., Duque, C., Kazmierczak, J., Engesgaard, P., Nilsson, B., Karan, S. and Frandsen, M.: High-resolution distributed temperature sensing to detect seasonal groundwater discharge into Lake Vaeng, Denmark, *Water Resources Research*, 49(9), 5355–5368, doi:10.1002/wrcr.20436, 2013.
- Sebok, E., Duque, C., Engesgaard, P. and Boegh, E.: Application of Distributed Temperature Sensing for coupled mapping of sedimentation processes and spatio-temporal variability of groundwater discharge in soft-bedded streams, *Hydrological Processes*, 29(15), 3408–3422, doi:10.1002/hyp.10455, 2015.
- 845 Selker, J. S., Thevenaz, L., Huwald, H., Mallet, A., Luxemburg, W., de Giesen, N. V., Stejskal, M., Zeman, J., Westhoff, M., Parlange, M. B., Thévenaz, L. and Van De Giesen, N.: Distributed fiber-optic temperature sensing for hydrologic systems, *Water Resources Research*, 42(12), doi:doi:10.1029/2006WR005326, 2006.
- Shaw, S. B., Bonville, D. B. and Chandler, D. G.: Combining observations of channel network contraction and spatial discharge variation to inform spatial controls on baseflow in Birch Creek, Catskill Mountains, USA, *Journal of Hydrology: Regional Studies*, 12(June 2016), 1–12, doi:10.1016/j.ejrh.2017.03.003, 2017.
- 850 Siegel, D. I., Reeve, A. S., Glaser, P. H. and Romanowicz, E. A.: Climate-driven flushing of pore water in peatlands, *Nature*, 374, 531–533, 1995.
- Silliman, S. E., Ramirez, J. and McCabe, R. L.: Quantifying Downflow through Creek Sediments Using Temperature Time-Series - One-Dimensional Solution Incorporating Measured Surface-Temperature, *Journal of Hydrology*, 167(1–4), 99–119, 1995.
- Slater, L. D. and Reeve, A.: Case history investigating peatland stratigraphy and hydrogeology using integrated electrical geophysics, *Geophysics*, 67(2), 365–378, 2002.
- 860 Smart, R. P., Holden, J., Dinsmore, K. J., Baird, A. J., Billett, M. F., Chapman, P. J. and Grayson, R.: The dynamics of natural pipe hydrological behaviour in blanket peat, , doi:10.1002/hyp, 2012.
- Sophocleous, M.: Interactions between groundwater and surface water: the state of the science, *Hydrogeology Journal*, 10(1), 52–67, 2002.
- Stallman, R. W.: Steady one-dimensional fluid flow in a semi-infinite porous medium with sinusoidal surface temperature, *Journal of Geophysical Research*, 70(12), 2821–2827, doi:Cited By (since 1996) 106 Export Date 4 April 2012, 1965.
- 865 Stone, B.D., Stone, J.R., DiGiacomo-Cohen, M.L., and Kincare, K. A. : Surficial geologic map of the Norton-Manomet-Westport-Sconticut Neck 23-quadrangle area in southeast Massachusetts: U.S.

| [Geological Survey Open-File Report 2006-1260-F, 21 sheets, scale 1:24,000, 22-p. text, 2011.](#)

- Turcotte, D. L. and Schubert, G.: Geodynamics: applications of continuum physics to geological problems,
870 John Wiley & Sons, New York, 1982.
- Tyler, S. W., Selker, J. S., Hausner, M. B., Hatch, C. E., Torgersen, T., Thodal, C. E. and Schladow, S. G.: Environmental temperature sensing using Raman spectra DTS fiber-optic methods, *Water Resources Research*, 45, doi:doi:10.1029/2008WR007052, 2009.
- Vandenbohede, a., de Louw, P. G. B. and Doornenbal, P. J.: Characterizing preferential groundwater discharge through boils using temperature, *Journal of Hydrology*, 510, 372–384, doi:10.1016/j.jhydrol.2014.01.006, 2014.
- Verberk, W. C. E. P., Bilton, D. T., Calosi, P. and Spicer, J. I.: Oxygen supply in aquatic ectotherms: Partial pressure and solubility together explain biodiversity and size patterns, *Ecology*, 92(8), 1565–1572, 2011.
- 880 Wallage, Z. E. and Holden, J.: Near-surface macropore flow and saturated hydraulic conductivity in drained and restored blanket peatlands, *Soil Use and Management*, 27(2), 247–254, doi:10.1111/j.1475-2743.2011.00336.x, 2011.
- Watters, J. R. and Stanley, E. H.: Stream channels in peatlands: The role of biological processes in controlling channel form, *Geomorphology*, 89(1–2), 97–110, doi:10.1016/j.geomorph.2006.07.015, 2007.
- 885 Winter, T. C.: Effects of water-table configuration on seepage through lake beds, *Limnology and Oceanography*, 26(5), 925–934, doi:10.4319/lo.1981.26.5.0925, 1981.
- Winter, T. C.: The concept of hydrologic landscapes, *Journal of American Water Resources Association*, 37(2), 335–349, 2001.
- Winter, T. C., Harvey, J. W., Franke, O. L. and Alley, W. M.: Ground water and surface water; a single
890 resource, U. S. Geological Survey Circular, , 79, 1998.

USGS Well ID	$\delta^{18}\text{O}$	$\delta^2\text{H}$	Latitude (WGS 84)	Longitude (WGS 84)
MA-PWW 494, Plymouth	-6.15	-37.38	41.8713889	-70.6586111
MA-EBW 30, East Bridgewater	-8.07	-46.33	42.0155556	-70.9658333
MA-WFW 51 Wareham	-6.83	-37.45	41.7550000	-70.7325000
MA-D4W 80 Duxbury	-8.13	-47.42	42.0547222	-70.7247222
MA-XGW 2, Weymouth	-8.55	-50.33	42.1650000	-70.9458333
MA-NGW 116, New Bedford	-7.55	-43.42	41.6736111	-70.9577778
MA-F3W 23, Freetown	-7.86	-44.02	41.7847222	-71.0813889

895 **Table 1: USGS groundwater wells $\delta^2\text{H-H}_2\text{O}$, $\delta^{18}\text{O-H}_2\text{O}$ isotopic data used to establish the regional groundwater trend.**

K_s [$J s^{-1} m^{-1} K^{-1}$]	<u>0.4^a-0.6^b</u>
K_f [$J s^{-1} m^{-1} K^{-1}$]	<u>0.6^c</u>
n	<u>0.5^a-0.8^d</u>
ρ_f at 10°C [$kg m^{-3}$]	<u>999.7</u>
c_f at 10°C [$kJ kg^{-1} K^{-1}$]	<u>4193</u>

^a *McKenzie et al., 2007*; ^b *Letts et al., 2000*; ^c *Schmidt et al., 2007*

^d *Rezanezhad et al. 2016*

900

905

Table 2: Parameters within the 1D heat transport equation derived by Turcotte and Schubert (1982) and modified by Schmidt et al. (2007). K_s is the thermal conductivity of the solid, K_f is the thermal conductivity of the fluid, and n is the porosity of the matrix. The density of the fluid and heat capacity of the fluid multiplied together are the volumetric heat capacity of the fluid ($\rho_f c_f$, $J m^{-3} K^{-1}$).






Figure 1: a) Site map of the Tidmarsh Farms regional peatland showing the study area and watershed boundary; Plymouth County, Massachusetts, and PCKD USGS wells used for regional groundwater isotopic data (Table 1). b) Detail of the Tidmarsh Farms study site showing the major waterways and flow direction in blue, site groundwater wells, isotopic sample locations, and GPR transects. Beaver Dam Brook flows north into Plymouth Bay.

910




915 Figure 2: a) Map of total peat thickness beneath Tidmarsh Farms based on GPR data. GPR data collected along linear transects shown here (black lines; pink lines on Figure 1B) were interpolated and contoured to show peat thickness (colors) on the 2D surface map. Zones of medium and high curvature (the 2nd derivative of the thickness) of the peat-sand interface are shown as grey and black pixels, respectively. b) and c) Three example cross sectional profiles, or radargrams, illustrate a distinct reflector at the basal peat-sand contact. Peat is shaded red, and sediment cores samples used to constrain the GPR velocity data are also shown as yellow lines (hand cores) and orange lines (vibracore) were used to constrain the GPR velocity data. High curvature is highlighted in green boxes.

920



925 | Figure 3: Fiber-optic Distributed Temperature Sensing (FO-DTS) temperature time series from four 1-meter segments of cable to illustrate the characteristic thermal signatures at Tidmarsh Farms. The greatest amplitude and variability occurs in the drainage ditches with little flow and significant solar heating (red), followed by the main channel of Beaver Dam Brook (green). Two seepage types are also plotted over 2.5 days; matrix (type 1) seepage, with very low variability (low standard deviation) over time and a mean temperature a few degrees higher than groundwater (light blue) and preferential flow path (type 2) seepage with a mean temperature nearly equal to groundwater (dark blue) are also plotted over 2.5 days.

930 |



935

Figure 4: Thermal infrared (TIR) images recorded in July 30-31, 2013 (Summer) and March 21, 2014 (Winter) at Tidmarsh Farms. Visible light images are shown in the bottom left of March images, but not July, as these surveys were conducted at night to limit issues associated with reflectance. TIR images illustrate the two types of seepage in both seasons: type 1 preferential flow path seepage that is characterized by discrete discharge points very close to groundwater temperature with high-flux, and type 2 matrix seeps that are diffuse, 3-5 °C warmer or cooler than groundwater and lower flux.





Figure 5: Map of seepage at Tidmarsh Farms determined with fiber-optic distributed temperature sensing (FO-DTS, squares) and thermal infrared (TIR) surveys (circles). Background shaded region(s) match the bounded area from Figure 1B, and darker background shading delineates zones of high curvature (the 2nd derivative of the thickness) of the peat-sand interface (Fig. 2). For both methods, light purple to pink symbols indicate matrix (type 1) seepage, and dark blue indicates locations of PFP (type 2) seepage. From FO-DTS data, a location was tagged as seepage if the standard deviation was less than 1.5 and the temperature was less than 15 °C for matrix and less than or equal to 11 °C for PFP seepage. From TIR surveys, seepage was distinguished by temperatures of 9-11 °C for interior seepage, and 11-15 °C for matrix seepage. [The location of GPR line 7.1 is shown on this figure to reference data for the conceptual model in Figure 9.](#)



955
Figure 6: Thermal infrared (TIR) image from March 21, 2014 at Tidmarsh Farms illustrating PFP (type 2) seepage. Many macropores are observed in both the infrared (slightly smaller) and the visual image. These seeps are located in the middle of cell 3 (Fig. 1B), where peat is ~3m thick and dramatically thinning.



960 **Figure 7:** Temperature profiles vs. depth at Tidmarsh Farms recorded in July 30-31, 2013. For each profile, the range of air temperatures and groundwater (GW) temperatures are shown as **bands of pink (air)** and dark blue (**groundwater(GW)-bands**). At **locations 1 and 2**, (profiles 1 and 2) show the influence of upwelling groundwater; expressed as type 1 preferential flow path (PFP) seepage (profile 2) and type 2 matrix seepage (profile 1). The **concaveconvex upward** shape of temperature-depth profiles—3 and 4 is also **indicative ofconsistent with** upwelling seepage.

965





Figure 8: Plot of the stable isotopes $\delta^2\text{H-H}_2\text{O}$ and $\delta^{18}\text{O-H}_2\text{O}$ from the Tidmarsh Farms area surface water (diamonds), groundwater (circles), shallow well, and seep sources (triangles). The regional groundwater trend line was derived from samples from relatively shallow, regional USGS wells (blue dots, shaded grey region), consistent with a relatively humid climate at the site.



975

Figure 9: Conceptual model illustrating the mechanism for development of matrix (type 1) seepage (pink arrows) and preferential flow path (PFP) or interior (type 2) seepage (blue arrows), shown as dashed pink and blue arrows and corresponding to locations in winter TIR images. Thick black lines represent the peat-sand interface groundwater flow direction, and the yellow-green box indicates the location region of high basin curvature, and outlines a typical basin shape and is based on GPR line 7.1; (as shown in Figure 2C). The conceptual PFP and matrix indications and PFP seepage locations are based on the temperature data recorded proximal to GPR line 7.1, and the winter-TIR images shown are from this same transect. Solid colored lines show contours of equal hydraulic potential. PFP seeps found in the thicker peat often are associated with locations of high basin curvature where strong vertical gradients drive focused, higher-flux seepage through pre-existing weaknesses in the peat matrix.

980

985