

## Responses to editor and reviewers

Dear editor and reviewers,

We greatly appreciate editor for providing opportunity again to revise our manuscript. We also thank two reviewers very much for pointing out some errors in writing. All comments are helpful for improving the quality of the manuscript. All authors have read and approved the revised manuscript. Please see our point-by-point responses below. A kindly note: reviewers' comments are in blue color and our responses are in black color; page and line numbers cited in our responses refer to the revised manuscript with track changes for easy evaluation. A track-changed version of the revised manuscript can be found after the response to reviewers.

### **Reviewer #1:**

The authors have addressed the problems raised in my previous review. I would suggest an acceptance for publication after some minor revision. Below are some advices for consideration in their revision.

“Meteorological Institute of Shaanxi Province, Xi’an, China” Shanxi or Shaanxi?

**Response:** Shaanxi is correct. There are two provinces with same pronounce in China (Shǎnxi and Shānxi). To make the difference clear without tonal marks, the spelling “Shaanxi” was used to represent the Shǎnxi, while “Shanxi” is used for the province of Shānxi.

“Land use planning in China is considered crucial strategy for the sustainable management of a river basin systems and has..” change ‘a river basin systems’ to ‘river basin systems’

**Response:** Done (*Please see P2 L13*).

“A geographic information system (GIS) interface,..” change it to “A Geographic Information Systems (GIS)”?

**Response:** Done (*Please see P6 L5*).

Pp11-12: the font sizes are different on these two pages.

**Response:** It has been corrected.

“Qiao et al. (2017) reported that the reduced runoff in areas with woody plant relative to grassland areas is associated with shift in runoff generation mechanisms; thus, the shift from saturation excess overland flow to infiltration excess overland flow might also have contributed to the reduced runoff in woodland areas observed in the present study.” Change it to “Qiao et al. (2017) reported that the reduced runoff in areas with woody plant relative to grassland areas is associated with a shift in runoff generation mechanisms from saturation excess overland flow to infiltration excess overland flow. Such type of shift might also have contributed to the reduced runoff in woodland areas observed in the present study.”

**Response:** It has been corrected accordingly (*Please see P12 L23-25*).

“Furthermore, afforestation on sloping land had greater hydrological effects than did planting grass” change this sentence to “... afforestation had greater hydrological effects than grass planting on sloping land”?

**Response:** It has been corrected accordingly (*Please see P15 L1*).

“Table 5 Slope characteristics of each land use type in 2010 and under different slope land conversion scenarios (unit: km<sup>2</sup>)” Since they are scenarios, how can they be in the certain year? More revision to the caption?

**Response:** Following the reviewer’s suggestion, the caption was revised, and new version is “Slope characteristics of each land use type at baseline and under different slope land conversion scenarios” (unit: km<sup>2</sup>) (*Please see P26 L1*).

**Reviewer #2:**

I think the revised manuscript has adequately addressed all my comments and suggestions. However, minor revisions are needed before acceptance for publications

P 2, Line 4: “soil moisture” or “soil water”? Please keep consistent throughout the MS.

**Response:** We have replaced “soil moisture” by “soil water” to keep consistent (*please see P2 L5; P13 L25; P14 L9*).

P 2, Line 7-8: What is the difference between “land use type” and “LULC”. I don’t find the difference between the “variation in land use type” and “spatial heterogeneity of LULC”. Please clarify.

**Response:** Thanks for pointing out the confused usage. In the manuscript, the “land use type” and “LULC” actually express the same meaning, thus the sentence “the characteristics of basin hydrology vary among land use patterns due not only to the type of LULC but also to the spatial heterogeneity of LULC” was corrected to “the characteristics of basin hydrology vary among land use patterns due not only to the type of LULC but also to the spatiotemporal heterogeneity of LULC” (*Please see P2 L8-9*).

P 4, Line 6-7: Delete this sentence.

**Response:** Done (*Please see P4 L9*).

P 4, Line 15: is characterized by

**Response:** Done (*Please see P4 L18*).

P 4, Line 18: Change “from 1952–2015” to “during 1952–2015”

**Response:** Done (*Please see P4 L21*).

P 4, Line 22: “from 1952 through 2008”?

**Response:** Yes, the hydrological data was available from 1952 to 2008, and we replaced “through” by “to” (*Please see P5 L1*).

P 6, Line 18: Change “In order to” to “to”

**Response:** Done (*Please see P6 L22*).

P 8, Line 2: Change “increased slowly” to “slowly increased”

**Response:** Done (*Please see P8 L6*).

P 8, Line 24: Change “highest” to “largest”.

**Response:** Done (*Please see P9 L5*).

P 9, Line 6: Change “shows” to “showed”.

**Response:** Done (*Please see P9 L12*).

P 9, Line 9: Delete “highest”.

**Response:** Done (*Please see P9 L14*).

P 9, Line 16: Change “presents” to “presented”.

**Response:** Done (*Please see P9 L21*).

P 9, Line 22: “1990-2000” or “1990–2000”? Please check the dash line.

**Response:** Thanks, we checked the usage of hyphen “-” and dash “–” carefully, and all errors were corrected in the manuscript (*Please see P10 L3; P8 L9-11; P13 L16*).

P 9, Line 23: Change “are” to “were”

**Response:** Done (*Please see P10 L5*).

P 11, Line 5-7: Change “illustrates” to “illustrated”; “decreases” to “decreased”; “are” to “were”

**Response:** Done (*Please see P11 L11*).

P 12, Line 11-12: Change “attributed to the topography of cropland” to “attributed to its topography”

**Response:** Done (*Please see P12 L12*).

Reference: The format should keep consistent with HESS.

**Response:** The format of reference was controlled by EndNote software, and we downloaded the output style from HESS to keep all bibliography consistent with journal requirement.

Table 2 and 3: Please explain the “Pct”. Alternatively, you can write the full name of “percentage”.

**Response:** we added the note below the table 2 to explain the meaning of the “Pct.”(*Please see P23 Table 2*).

Fig. 1: Add the unit of the legend of the DEM

**Response:** The unit was added in the Fig.1 (*Please see P28 Fig. 1*).

# Spatiotemporal response of the water cycle to land use conversions in a typical hilly-gully basin on the Loess Plateau, China

Linjing Qiu<sup>1</sup>, Yiping Wu<sup>1</sup>, Lijing Wang<sup>1</sup>, Xiaohui Lei<sup>2</sup>, Weihong Liao<sup>2</sup>, Ying Hui<sup>3</sup>, Xianyong Meng<sup>4</sup>

<sup>1</sup>Department of Earth and Environmental Science, School of Human Settlements and Civil Engineering, Xi'an Jiaotong University, Xi'an, Shaanxi 710049, China

<sup>2</sup>State Key Laboratory of Simulation and Regulation of Water Cycle in River Basin, [China Institute of Water Resources and Hydropower Research, Beijing, China](#)

<sup>3</sup>Meteorological Institute of Shaanxi Province, Xi'an, China

<sup>4</sup>~~Institute of Water Resources and Hydropower Research, Beijing, 100038, China~~

10 *Correspondence to:* Yiping Wu (yipingwu@xjtu.edu.cn)

**Abstract.** The hydrological effects of the 'Grain for Green' project (GFGP) on the Loess Plateau have been extensively debated due to the complexity of the water system and its multiple driving factors. The aim of this study was to investigate the response of the hydrological cycle to the GFGP measures based in a case study of the Yanhe basin, a typical hilly-gully area on the Loess Plateau of China. First, we analyzed the land use and land cover (LULC) changes from 1990 to 2010. Then, we evaluated the effects of LULC changes and sloping land conversion on the main hydrological components in the basin using the Soil and Water Assessment Tool (SWAT). The results indicated that cropland exhibited a decreasing trend declining from 40.2% of the basin area in 1990 to 17.6% in 2010, and that the woodland and grassland areas correspondingly increased. With the land use changes from 1990 to 2010, the water yield showed a decreasing trend which was mainly due to decrease in surface runoff. In contrast, evapotranspiration (ET) showed an increasing trend over the same period, resulting in a persistent decrease in soil water. The conversion of sloping cropland to grassland or woodland exerted negative effects on water yield and soil water. Compared with the land use condition in 2010, the negative effects were most evident where cropland with a slope  $\geq 15^\circ$  was converted to woodland, with decrease in surface runoff and soil water of 17.1% and 6.4%, respectively. These results suggest that the expansive reforestation on sloping land in the loess hilly-gully region decreased water yield and increased ET, resulting in reduced soil water. The results of this study can be used to support sustainable land use planning and water resource

management on the Loess Plateau in China.

## 1 Introduction

Land surface change is one of the most important drivers of eco-hydrological changes (Li et al., 2009; Bloeschl et al., 2007). The impacts of land use and land cover (LULC) changes on water resources and hydrological processes in a river basin are mainly reflected in the overland surface runoff, streamflow, evapotranspiration (ET), and ~~soil moisture~~soil water (Bari and Smettem, 2004; Chawla and Mujumdar, 2015; Liu et al., 2008b; Zucco et al., 2014). Many studies have investigated the relationships between land use patterns and basin hydrology and have found that the characteristics of basin hydrology vary among land use patterns due not only to ~~the variation in type of land use type~~LULC (Wang et al., 2012; Jian et al., 2015; Duan et al., 2016) but also to ~~the the spatial~~spatiotemporal heterogeneity ~~of LULC of LULC~~ (Chu et al., 2010; Liu et al., 2013). However, debate exists among ecohydrologists regarding the effects of past and ongoing land use changes because of the spatial and temporal complexity of hydrological processes (Lørup et al., 1998; Lopez-Moreno et al., 2011; Alkama et al., 2013; Liu et al., 2016).

Land use planning in China is considered crucial strategy for the sustainable management of ~~a~~ river basin systems and has been widely adopted for ecological restoration and water resource protection, especially in the Loess Plateau region, which is well known for its fragile ecology (Liu et al., 2008a; Zhang et al., 2009; Zhen et al., 2014). The river basins on the Loess Plateau are important because of the dense population, intensive cultivation, and the high demand for water in the area. Unfortunately, this region is characterized by insufficient water resources and severe soil erosion, and it has historically experienced vegetation degradation and desertification (Zhao et al., 2013; Guo et al., 2002). Thus, land use change and basin hydrology have attracted considerable attention, and since the 1970s, soil and water conservation practices have been implemented in the area to mitigate the increasing environmental problems. In 1999, the ‘Grain for Green’ project (GFGP) was launched by the Chinese government in the Loess Plateau region with the primary goal of retiring and converting steep cropland (slope  $\geq 15^\circ$ ) to green lands (Zhou et al., 2012; Liu et al., 2008a). It was reported that the vegetation coverage on the Loess Plateau increased from 6.5% in the 1970s to 51% in 2010 (Wang et al., 2012), and approximately 16,000 km<sup>2</sup> of rain-fed cropland was converted to planted vegetation during the past decade (Feng et al., 2016). Consequently, the hydrological

processes on the sloping land and in the river systems have changed, but the extent of these changes and their relationships to LULC change remain unclear.

In the past decades, the hydrological effects of land use change have been widely explored across different spatiotemporal scales on the Loess Plateau. Huang et al. (2003) investigated the runoff response to afforestation using a paired watershed analysis and revealed that forest revegetation reduced annual runoff, with the reduction amount increasing with tree age. 5 McVicar et al. (2007, 2010) developed a decision support tool for China's revegetation program and simulated annual streamflow based on revegetation planning. Wei et al. (2015) found a strong inverse relationship between runoff and conversion to forests, shrubs, and grasses during the period 2005–2010 in a typical watershed on the Loess Plateau. Feng et al. (2016) reported that revegetation increased ET and resulted in a significant ( $P < 0.001$ ) decrease in the ratio of streamflow to 10 precipitation on the Chinese Loess Plateau. Zuo et al. (2016) combined statistical tests and hydrological modeling to assess the effects of land use on runoff and found that the water resources in the upstream region decreased more than did those in the downstream region. Liang et al. (2015) used an elasticity and decomposition model based on the Budyko framework to simulate and forecast the hydrological effects of ecological restoration and demonstrated that ecological restoration played a dominant role in the reduction of streamflow in 14 main subbasins on the Chinese Loess Plateau. Another study showed that 15 the GFGP can potentially increase soil water content and water yield and decrease runoff and ET (Tian et al., 2016). Moreover, some researchers have reported that woody species consume more water by ET than do other vegetation types (Wang et al., 2012; Yang et al., 2014), and some studies have documented that large-scale reforestation has greatly decreased the water yield and exacerbated water scarcity (Sun et al., 2006), gradually leading to soil desiccation (Chen et al., 2008; Chen et al., 2007; Wang et al., 2008). In general, these studies indicated that the GFGP on the Loess Plateau has had an evident influence on 20 basin hydrology; however, because these studies were performed from different perspectives or concentrated on single hydrological elements, the effects of ecosystem restoration on water balance have not been clarified. In addition, most previous studies have been based on statistical methods and short time scales. Although numerical models are useful tools for quantitatively assessing the hydrological responses to environmental changes, the previous modeling studies mainly focused on water discharge in river channel, with few studies focused on the spatial features of hydrological responses. Spatially 25 studying such responses could improve watershed management and the development of strategies for water resource

optimization. Therefore, a comprehensive understanding of how LULC change and spatial heterogeneity in LULC affect the water balance is essential for long-term land use planning and water resource management.

In this study, the Soil and Water Assessment Tool (SWAT) was applied to investigate the hydrological impacts of land use changes, including those resulting from sloping land conversion (SLC) program, on the Loess Plateau. The Yanhe basin, a main tributary of the middle reach of the Yellow River that has undergone large-scale revegetation and SLC, was selected for analyzing the hydrological responses via modeling. The specific objectives were as follows: 1) investigate the spatiotemporal variations in key water balance components as a result of LULC change, 2) evaluate the potential effects of land conversion on water availability under the SLC program, and 3) examine the changes in soil water storage under different land use condition. ~~The results provide a useful reference for sustainable land use planning and water resource management on the Loess Plateau in China.~~

## 2 Materials and methods

### 2.1 Study area

The Yanhe basin, which is located in northern Shaanxi Province, China ( $36^{\circ}21' \text{---} 37^{\circ}19' \text{ N}$  and  $108^{\circ}38' \text{---} 110^{\circ}29' \text{ E}$ ), is a typical hilly loess area on the Loess Plateau. The drainage area of the basin is  $7591 \text{ km}^2$ , and its elevation ranges from 560 m to 1760 m (Fig. 1). The slope of the basin varies from  $0^{\circ}$  to  $85.3^{\circ}$ , with a mean value of  $17.7^{\circ}$ . The main channel of the Yanhe River is 284.3 km long and originates in Jingbian County. It flows from northwest to southeast through Zhidan County, Ansai County, Yan'an City, and Yanchang County before entering the Yellow River. The soil in the basin developed from loess deposits, and the dominant soil type is loessial soil which is classified as Calcaric Cambisols (FAO 2014). The Yanhe basin is characterized by a semi-arid continental climate with warm and concentrated precipitation in summer and cold, dry winters with occasional snowfall. According to the collected meteorological data from the Meteorological Institute of Shaanxi Province, China, the precipitation ~~from during~~ 1952—2015 ranged from 300 mm to 803 mm, with a mean annual value of 495 mm. ~~Additionally~~ Additionally, the mean annual maximum and minimum air temperatures over this period were  $17.4^{\circ}\text{C}$  and  $4.2^{\circ}\text{C}$ , respectively. Grassland, cropland, and woodland (mainly artificial woods) are the dominant land use types in this region. Most crops are cultivated on sloping lands, and woodlands are generally located on the steeper parts of the landform. The mean

annual streamflow at the most downstream station of Ganguyi was  $205 \times 10^6 \text{ m}^3$  from 1952 ~~through to~~ 2008, and the streamflow from June to September accounted for 64.1% of the total annual discharge at this station. The GFGP was implemented in the basin in 1999, and the observed streamflow showed a decreasing trend during the 2010s (Fig. 2).

## 2.2 Data

5 The SWAT model setup requires data inputs including topography, soil, land use, climate and streamflow discharge. A digital elevation model (DEM) of the basin with a 30-m resolution was obtained from the National Geomatics Center of China (<http://www.ngcc.cn/>). A soil survey map with 20-m resolution was obtained from the Institute of Soil and Water Conservation (ISWC), Chinese Academy of Sciences (CAS), and we developed a user's soil database required for the model that linked to the digital soil map using ArcGIS (version 10.2). LULC data from 1990, 2000 and 2010 with 30-m resolution were supplied  
10 by the Institute of Remote Sensing and Digital Earth, CAS, and the land use was classified into six types according to the ecosystem classification system of China: grassland, woodland, cropland, water, residential land and barren land. Required meteorological data for the SWAT model comprise daily precipitation, maximum and minimum temperature, relative humidity, wind speed and solar radiation, which were available from 1980 to 2015 from five county level meteorological stations: Jingbian, Zhidan, Aansai, Yan'an and Yanchang. These data were provided by the Meteorological Institute of Shaanxi Province,  
15 China. Observed monthly streamflow data at the Ganguyi hydrological station were obtained from the Yellow River Conservancy Commission (YRCC) from 1980—2010. The data were used for model calibration and validation, although some data gaps (missing values) were present. Ganguyi station is the most downstream station on the Yanhe River and controls an area of 5891 km<sup>2</sup>.

## 2.3 Model description

20 The SWAT model (version 2012), which was developed by the U.S. Department of Agriculture (USDA)——Agricultural Research Services (ARS), is a physically based, temporally continuous, and distributed watershed-scale hydrological model (Neitsch et al., 2011; Douglas-Mankin et al., 2010). The SWAT-modeled hydrological cycle is based on the water balance, as documented by Arnold et al. (1998). SWAT has been widely tested and successfully used to explore the effects of climate and land use/management changes on watershed hydrology and water quality (Nyeko, 2015; Panagopoulos et al., 2011; Douglas-



Mankin et al., 2010; Zhang et al., 2013; Bosch et al., 2010; Wu and Chen, 2013; Xu et al., 2012; Zhang et al., 2011; Zhang et al., 2008; Qiu et al., 2012; Gassman et al., 2014). Detailed descriptions of the mechanisms and structure of the SWAT model can be found elsewhere (Neitsch et al., 2011; Arnold et al., 2012).

#### 2.4 Model setup and calibration/validation

5 A ~~geographic~~ Geographic information system (GIS) interface, ArcSWAT (Version 2012.10.2.18), was used to set up the model. The DEM was used to delineate the watershed with a threshold sub-basin area of 50 km<sup>2</sup>, resulting in 88 sub-basins. Then, the land use map of 1990 and the soil map were imported and overlaid to create the hydrological response units (HRUs). HRUs are portions of a sub-basin that represents unique combinations of land use, soil and slope. To accurately reflect the spatial variability in the basin, multiple HRUs were selected using a minimum threshold value of 5% for  
10 each land use, soil and slope categories, resulting in 1136 HRUs. To meet the needs of the model, the SWAT codes for the main land use types in the study area were defined as cropland (AGRR), woodland (FRST), grassland (RNGE), residential land (URBN), and barren land (BARR) in the attribute data. The SWAT model was calibrated using monthly streamflow data from Ganguyi hydrological station, and we adopted the SWAT-CUP (SUF2) program to perform a sensitivity analysis of model parameters. Calibration was conducted using the first ten-year (1983–1992) record of streamflow, and the model was then  
15 validated using data from the subsequent eight years (1993–2000). Additionally, a three-year warm-up period (1980–1982) was used to minimize the effects of uncertain initial conditions (e.g., soil water storage) in the model simulation. To evaluate the model performance numerically, we used three statistical measures: percent bias (PBIAS), Nash-Sutcliffe efficiency (NSE) (Nash and Sutcliffe 1970), and the coefficient of determination (squared correlation coefficient,  $r^2$ ). Typically, a model simulation is considered satisfactory with  $NSE > 0.5$ ,  $-25\% \leq PBIAS \leq 25\%$ , and  $r^2 > 0.5$  (Neupane and Kumar, 2015; Wu and  
20 Chen, 2013).

#### 2.5 Historical land use change and hydrological simulation

~~In order to~~ To understand the historical land use change of the Yanhe basin, we conducted the spatiotemporal analysis of land use change using three land use conditions (land use maps from 1990, 2000 and 2010, corresponding to LU1990, LU2000 and LU2010, respectively), and the amount of specific land use types that changes from the initial time to the subsequent time was

identified by overlaying the land use maps for different years. Then, the different land use data was taken as input of the calibrated SWAT model to isolate the effect of land use change under the historical climate from 1986–2015. Finally, the main hydrological components of water cycle (surface runoff, subsurface flow, ET, water yield and soil water) under different land use condition was assessed quantitatively at the HRU level.

## 5 2.6 Hypothetical SLC scenarios

SWAT was applied for assessing the long-term effects of SLC on the hydrological cycle in the Yanhe basin. The land use condition of 2010 was set as the baseline scenario (BS), and four hypothetical land conversion scenarios depicting the potential land use pattern were reestablished based on the land use of 2010 and the SLC policy of the GFGP. Scenario S1 and scenario S2 involve the conversion of cropland on slopes steeper than 25° to grassland and woodland, respectively, and scenario S3 and scenario S4 involve the conversion of cropland on slopes greater than or equal to 15° to grassland and woodland, respectively. To isolate the hydrological effects only caused by different land management, SWAT model with BS and four hypothetical scenarios were set up and run for 30 years using the historical climate forcing data from 1986–2015.

## 3 Results

### 3.1 Model performance evaluation

15 We performed a global sensitivity analysis to examine 18 parameters that are potentially related to streamflow and identified the most sensitive 8 parameters for subsequent model calibration (Table 1). The selected 8 parameters represent key hydrological components such as surface runoff, soil water capacity and conductivity, ET, and groundwater recharge in this region. Although the calibrated model slightly underestimated streamflow, the model performance was satisfactory in the calibration period (1983–1992), with NSE,  $r^2$  and PBIAS values of 0.51, 0.71 and 15.7%, respectively (Fig. 3a). In the 8-year  
20 (1993–2000) validation period, the streamflow characteristics were well captured by the calibrated model, with an NSE value of 0.82, although PBIAS indicated a 16.9% underestimation (Fig. 3b). In both the calibration and validation periods, the underestimation mainly occurred in the spring and winter, during which time little discharge occurs in the watershed. Thus, the model performed poorly during the dry period. Nonetheless, both visual comparison and numerical evaluation indicated

that the overall model performance was acceptable for simulating the hydrological processes in the Yanhe basin.

### 3.2 Land use changes in Yanhe basin from 1990 to 2010

Cropland, woodland and grassland were the primary land use types in the Yanhe basin, and rapid land use change occurred from 1990 to 2010 (Table 2). A downward trend was observed in cropland, which declined from 40.2% of the basin area in 1990 to 17.6% in 2010, whereas upward trends were observed in both grassland and woodland, although these upward trends differed from each other. Grassland slowly increased ~~slowly~~ from 44.7% to 45.3% between 1990 and 2000, followed by a rapid increase from 45.3% to 55.1% between 2000 and 2010. Woodland exhibited an increase of 73.9% from 1990 to 2000 followed by a smaller increase of 7.8% from 2000 to 2010. To identify the details of the land use conversion patterns, we explored the mutual conversion among three major land use types—cropland, grassland, and woodland (Table 3). The conversion of cropland to other land use types was observed in the periods of 1990–2000 and 2000–2010, whereas the conversions of grassland or woodland to other land use types were only evident from 1990–2000. The cropland area decreased dramatically from 1990 to 2010 primarily due to conversion to woodland or grassland, with conversion percentages of 16.7% and 39.5%, respectively, from 1990 to 2000 and of 6.4% and 33.2%, respectively, from 2000 to 2010. As shown in Fig. 4, the conversions mostly occurred in the central and northwestern parts of the basin from 1990–2000 and were scattered from 2000 to 2010. We also examined the land use conversions over the 20-year periods (1990 to 2010) and found that 19.6% and 54.5% of cropland was transformed to woodland and grassland, respectively, indicating evident LULC change due to the implementation of the GFDP policy in the basin (Table 3). Although the percentages of grassland and woodland increased, 20.1% of grassland and 19.5% of woodland were converted into cropland from 1990 to 2000. Additionally, mutual conversions were observed between grassland and other land use types, but the total area of grassland changed only slightly from 1990 to 2000. For example, 1204.6 km<sup>2</sup> of cropland and 281.5 km<sup>2</sup> woodland were converted into grassland, whereas 762.3 km<sup>2</sup> and 683.2 km<sup>2</sup> of grassland were transformed to woodlands and cropland, respectively, in the same period, resulting in a small net change (Table 3). Additionally, despite the increase in woodland from 1990 to 2010, 12.6% and 31.1% of the woodland from 1990 was converted into cropland and grassland, respectively, with much of this conversion occurring in the southern part of the basin.

### 3.3 Water balance components under different land use types

To further analyze the quantitative impacts of LULC changes on the hydrological cycle, the main hydrological components of individual land use types were assessed via model simulation. The analysis results indicated that the water balance varied among different land use types in the basin (Fig. 5). The overland surface runoff per unit area from residential land was the ~~highest~~largest, with an average value of 58.9 mm, followed by that from cropland and grassland, at 19.2 mm and 9.3 mm, respectively. Woodland had the lowest surface runoff of 3.7 mm, which was approximately 80.7% lower than that of cropland and 62.2% lower than that of grassland (Fig. 5a). The water yield from individual land use types had trends similar to those of surface runoff. These results implied that the conversions of cropland and grassland to woodland reduced runoff and streamflow at the regional scale. In contrast, the ET of woodland areas was the highest, followed by that of grassland, cropland, and residential land. The soil water of all land use types except residential land exhibited a trend opposite that of ET (cropland > grassland > woodland); woodland areas used more soil water for ET and generated less runoff and streamflow. Fig. 5b ~~shows~~ showed the total water volumes for the different land use types in the basin. The highest volumes of surface runoff and water yield were associated with cropland because of its large water volume per unit area and large total area in the basin. Grassland had the largest soil water storage and ~~highest~~ ET in the basin. The surface runoff, water yield, soil water, and ET of woodland were the lowest among different land use types, except for residential land, due to the small total area of woodland in 1990.

### 3.4 Hydrological impacts of historical land use changes

The impacts of land use changes were simulated by applying the model to three land use scenarios (LU1990, LU2000, and LU2010) with the same climate forcing data (from 1986 to 2015). The simulated streamflow at the outlet of the Yanhe basin exhibited a downward trend with land use change from 1990 to 2010, and the magnitude of the reduction under LU2010 was larger than that under LU2000 (Fig. 6a). Further analysis showed that relatively large responses mainly occurred from May to September (Fig. 6b). Table 4 ~~presents~~ presented the simulated average annual components of the water balance in the Yanhe basin. A decreasing trend was observed in surface runoff at the basin scale as land use changes occurred from 1990 to 2010, with decrease of 16.6% under LU2000 and 29% under LU2010. Land use changes had minor effects on subsurface flow, with slight increase of 1.8% under LU2000 and of 2.7% under LU2010 relative to flow under LU1990. Similar to subsurface flow,

ET displayed a weak increasing trend in the basin due to land use changes. The water yield in the basin under LU2000 and LU2010 changed in a similar manner as surface runoff, with decreases of 5.6% and 9.9%, respectively, relative to water yield of LU1990. The soil water decreased by 11% from 1990 to 2010, with a rapid decrease from 1990—2000 and a slow decrease thereafter.

5 The spatial distributions of the main hydrological components at the HRU scale ~~are~~ were shown in Fig. 7. The central part of the basin produced high surface runoff, whereas the most western portion and the southern edge of the basin had little runoff (Fig. 7a and 7e). Additionally, the decrease in surface runoff from 1990 to 2010 was concentrated in the middle part of the basin. To further understand the hydrological changes associated with land use change, we analyzed the long-term (30-year) average total water volumes of the main hydrological components (Fig. 8). The results showed that decreases in total surface  
10 runoff mainly occurred in cropland areas because of its decreased area. The associated decreased percentages were 26.8% under LU2000 and 57.3% under LU2010 relative to the surface runoff of LU1990 (Fig. 8a). Although the total surface runoff generated in grassland and woodland areas increased from LU1990 to LU2010, the total magnitude of these increases could not compensate for the decrease associated with cropland. Thus, the total surface runoff of the basin decreased. The water yield displayed a trend similar to that of surface runoff from LU1990 to LU2010 (Fig. 7b and f)—the total water yield decreased by  
15 60.9% in cropland areas and increased by 18.8% and 136.4% in grassland and woodland, respectively. These changes were due to the dramatic conversion of cropland to grassland and woodland between LU1990 and LU2010 (Fig. 8b). Similar to the spatiotemporal trends in water yield, ET increased under LU2010 relative to LU1990 (Fig. 7c and g), whereas it decreased by 58.7% in cropland and increased by 21.4% and 124.0% in grassland and woodland, respectively, from LU1990 to LU2010 (Fig. 8c). In terms of the spatial distribution of soil water, an evident decrease occurred under LU2010, with the highest  
20 decrease occurring in the northcentral part of the region (Fig. 7d and h). Although the total soil water increased in woodland with land use change, the total soil water was lowest in woodland under all three land use scenarios (Fig. 8d).

### 3.5 Potential impacts of hypothetical SLC

The potential hydrological effects of SLC were projected by inputting four land conversion scenarios that were reconstructed based on the LU2010 baseline (Table 5). The changes in land use in S1 led to the conversion of 131.6 km<sup>2</sup> cropland with

slope  $>25^\circ$  to grassland, which resulted in slight decreases in surface runoff, water yield and soil water, whereas minor increase were found in subsurface flow and ET. With the same acreage of cropland to woodland conversion in S2, the induced hydrological effects were similar to those in S1, whereas the differences between S2 and the baseline were larger in magnitude than those between S1 and the baseline. When the land conversion was extended to cropland with slope  $\geq 15^\circ$ , the trends of hydrological change were strengthened. For example, in S3, grassland increased by 23.9% and 15.3% on land surfaces with slopes of  $15^\circ$ - $25^\circ$  and  $>25^\circ$ , respectively, resulting in 12.4% and 2.7% decreases in surface runoff and water yield, respectively, relative to the baseline. Conversely, subsurface flow and ET increased slightly by 2.2% and 0.2%, respectively. Although soil water consistently exhibited a negative response, the decreases were small. When the same area of cropland with slope  $\geq 15^\circ$  was converted to woodland in S4, the surface runoff and water yield decreased by 17.1% and 6.4% relative to the baseline while subsurface flow and ET increased by 3.9% and 0.3%, respectively. Soil water notably changed in S4, decreasing by 6.4% relative to the baseline soil water. Fig. 9 ~~illustrates-illustrated~~ the spatial response of soil water to land use conversion scenarios relative to the baseline of 2010. Soil water ~~decreases-decreased~~ in S4 mainly occurred along the southern edge of the basin and the northcentral part of the basin, which ~~are-were~~ areas of high elevation and high slope gradient (Fig. 9d).

#### 4 Discussion

In this study, the performance of the SWAT model was evaluated using monthly streamflow data from the Ganguyi hydrological station. Although the calibrated model slightly underestimated streamflow in the dry period in both the calibration and validation periods, the three statistical indexes (NSE, PBIAS,  $r^2$ ) indicated that the modelling accuracy was acceptable. The potential reasons for the underestimation can be categorized as “measurement quality” and “model behavior” reasons. “Measurement quality” refers to missing precipitation data or streamflow measuring error. The study area lies in the hilly-gullied loess region, and the complex and rugged terrain results in highly variable precipitation and difficulties in spatially estimating the precipitation (Cao et al., 2006). Additionally, this region has a limited number of meteorological and hydrological stations. In this study, five meteorological stations were involved; however, only three stations are located inside the basin, with the remaining two occurring outside the basin (Fig. 1). It has been reported that the accuracy of streamflow prediction mainly depends upon the precipitation gage numbers and their locations (Cao et al., 2006; Mul et al., 2009). Thus,

the insufficient precipitation records and the distances among the meteorological stations resulted in poor streamflow simulation. “Model behavior” refers to model limitations such as the inadequate representation of the physical mechanism of hydrological processes. For example, SWAT uses total daily precipitation and does not consider rainfall intensity within a day; thus, it can underestimate streamflow for some precipitation events (Qiu et al., 2012). Another example is the use of runoff curve number to simulate the surface runoff behavior. This approach does not account for saturation excess runoff or contributions from variable source areas (Garen and Moore, 2005; Easton et al., 2008). Although the simulation results in our research met the calibration criteria, the model performance can be improved if precipitation data from additional gages become available in the basin.

Cropland, grassland and woodland were the primary land use types in the Yanhe basin, and the sum of their area accounted for more than 95% of the total area during the period under study. To investigate the effects of land use change and management practices on the water balance, three land use scenarios were assessed using the SWAT model. The contributions of individual land use types to basin hydrology differed. Cropland had the highest soil water which can be partly attributed to ~~the-its~~ topography ~~of cropland~~. The cropland area was mainly distributed in the bottom region of the valley and on land with gentle slope. The valley bottom generally receives more water flow from the hillslope and has lower temperatures than higher regions, resulting in more soil water (Wang et al., 2012). Furthermore, land with gentle slope has higher soil water retention ability than does land with steep slope (Panagopoulos et al., 2011). In addition, cropland had lower ET per unit area than did the other land use types. In contrast, grassland had lower soil water, which can be attributed to its higher soil water loss through ET. Wang et al. (2012) reported that grass cover types cannot protect the soil surface from solar radiation, leading to greater water loss via direct evaporation. Woodland and, to a lesser extent, grassland areas were generally associated with lower surface runoff and water yield in the basin. This result is consistent with those of previous studies demonstrating that woodland areas capture more rainfall and uptake more water than do other land use types (e.g., cropland and grassland) (Jian et al., 2015; Wang et al., 2012), resulting in a lower runoff and water discharge (Wang et al., 2013; Duan et al., 2016). Qiao et al. (2017) reported that the reduced runoff in areas with woody plant relative to grassland areas is associated with a shift in runoff generation mechanisms ~~from saturation excess ; thus, the shift from saturation excess~~ overland flow to infiltration excess overland flow. Such type of shift might also have contributed to the reduced runoff in woodland areas observed in the present study.

Additionally, compared with other vegetation types, woodland areas might lose more water through ET. This pattern was evident from the change in soil water, with less soil water in woodland than in other areas under the same precipitation amount. Less soil water was observed in woodland because forests in the Yanhe basin generally grow on landform with high slopes; our analysis indicated that more than 62% of woodland was located on slopes  $\geq 15^\circ$  (Table 5). Steeper slopes generally retain less soil water due to low infiltration and rapid surface drainage (Famiglietti et al., 1998). Thus, a large amount of precipitation was associated with forest growth and ET rather than discharge out of the basin as surface runoff and streamflow. Such water patterns prevent water loss but at the expense of reduced soil water in the region.

After the implementation of the GFGP, the area of cropland decreased continuously because it was transformed into grassland and woodland from 1990 to 2010, and conversions among land use types were the main forms of land use change in the Yanhe basin. These results are consistent with previous findings regarding trends in land use change on the Loess Plateau (Li et al., 2016). We compared monthly and annual average streamflow under three land use scenarios, and the results showed that the decreased average monthly streamflow in the rainy season is the primary mechanism for the decrease in annual average streamflow in the basin. In addition, we found that the decrease in surface runoff was the main reason for the streamflow decrease in the basin, and our quantitative evaluation suggested that surface runoff decreased by 29.1% from 1990 to 2010 due to land use change. A similar conclusion was drawn by Farley et al. (2005), who studied 26 watersheds globally to assess the hydrological effect of afforestation and found that annual runoff was reduced by 31–44% on average. Notably, the average annual volume of soil water presented an evident decrease under the 2010 land use scenario. This trend might be due to two interrelated reasons. First, the area of cropland decreased dramatically in 2010, and cropland was characterized by the highest soil water volume per unit area relative to other land use types (Fig. 5a), leading to the large decrease in soil water. Second, a certain proportion of cropland was converted to grassland and woodland, which had the lowest soil water per unit area; thus, the soil water decreased due to the cropland area reduction, and this decrease could not be offset by increases in total soil water in grassland and woodland areas (Fig. 8). Although the area of woodland peaked in 2010, the total soil water in woodland areas increased only slightly. The main reason for this phenomenon might be that more water was consumed by woodland than cropland and grassland. Additionally, cropland areas with high slopes were converted to woodland after the GFGP was implemented (Zhou et al., 2012), and areas with steep slopes have lower ~~soil moisture~~soil water retention potentials than do



areas with gentle slopes (Pachepsky et al., 2001). Thus, topographical factors also played important roles in the spatial heterogeneity of the water balance (Qiu et al., 2001; Bi et al., 2008).

Four future SLC scenarios were proposed to demonstrate the hydrological effects of land use changes. Increases in grassland or woodland cover due to the land conversion of cropland with slopes  $\geq 15^\circ$  or  $>25^\circ$  had negative effects on surface runoff, water yield and soil water and positive effects on subsurface flow and ET. We found that the magnitudes of the hydrological effects of the conversion of sloping cropland to woodland were greater than those associated with the conversion of sloping cropland to grassland. This result suggests that the expansion of woodland could reduce runoff generation and drainage because of overland flow retention and intensification of ET in this region. However, the revegetated sloping land was prone to reduced ~~soil moisture~~soil water due to its steep slope. Some studies have reported that revegetation can cause soil water shortages in both the near-surface soil and deep soil layers (Farley et al., 2005; Jian et al., 2015), likely resulting in soil desiccation (Wang et al., 2011; Fu et al., 2012). Therefore, watershed management should consider all water balance components (Duan et al., 2016), and vegetative structure and management measures should be optimized to improve ecohydrological functions and promote watershed sustainability.

## 5 Conclusions

In this study, we found that cropland, grassland and woodland were the dominant land use types in the Yanhe basin, and land use conversion among these types occurred since 1990 due to the implementation of the GFGP. The decrease in cropland led to increase in grassland and woodland. The impacts of LULC changes on the water balance components were assessed quantitatively using the SWAT model, three periods of land use maps and four hypothetical SLC scenarios based on the GFGP policy on the Loess Plateau. Our analysis showed that cropland was associated with the highest surface runoff and water discharge per unit area, followed by grassland and woodland. These differences can partly explain the relationships between hydrological characteristics and land use change at the basin scale. Surface runoff and water yield decreased due to land use changes from 1990 to 2010 while subsurface flow and ET increased. Consequently, soil water decreased between 2000 and 2010. By adopting four cropland land conversion scenarios, we found that the function of reducing surface runoff was more effective when cropland with slopes  $\geq 15^\circ$  were converted into grassland or woodland than when areas with slopes  $>25^\circ$  were

converted. Furthermore, ~~afforestation had greater hydrological effects than grass planting on sloping land~~~~afforestation on sloping land had greater hydrological effects than did planting grass~~. Notably, surface runoff and soil water decreased and ET increased. Overall, this study provides useful information for land use planning and soil and water conservation on the Loess Plateau. Further studies are required to investigate the optimization of the vegetative structure and the avoidance of undesired hydrological effects.

## Acknowledgment

This work was supported by the Thousand Youth Talent Program of China (122990901606), the National Natural Science Foundation of China (41301223), the China Postdoctoral Science Foundation Grant (2016M592777), and State Key Research and Development Project (2016YFC0402208, 2016YFC0401903). We appreciate two anonymous reviewers for their constructive comments. We also thank —HPCC Platform in Xi'an Jiaotong University, for computing equipment and computer maintenance.

## References

- Alkama, R., Marchand, L., Ribes, A., and Decharme, B.: Detection of global runoff changes: results from observations and CMIP5 experiments, *Hydrology and Earth System Sciences*, 17, 2967-2979, doi: 10.5194/hess-17-2967-2013, 2013.
- Arnold, J. G., Srinivasan, R., Muttiah, R. S., and Williams, J. R.: Large area hydrologic modeling and assessment - Part 1: Model development, *Journal of the American Water Resources Association*, 34, 73-89, doi: 10.1111/j.1752-1688.1998.tb05961.x, 1998.
- Arnold, J. G., Moriasi, D. N., Gassman, P. W., Abbaspour, K. C., White, M. J., Srinivasan, R., Santhi, C., Harmel, R. D., van Griensven, A., Van Liew, M. W., Kannan, N., and Jha, M. K.: SWAT: Model use, calibration, and validation, *Transactions of the ASABE*, 55, 1491-1508, doi: 10.13031/2013.42256, 2012.
- Bari, M., and Smettem, K. R. J.: Modelling monthly runoff generation processes following land use changes: groundwater-surface runoff interactions, *Hydrology and Earth System Sciences*, 8, 903-922, <https://hal.archives-ouvertes.fr/hal->

00304971, 2004.

- Bi, H., Zhang, J., Zhu, J., Lin, L., Guo, C., Ren, Y., Yun, L., and Ma, N.: Spatial dynamics of soil moisture in a complex terrain in the semi-arid Loess Plateau region, China, *Journal of the American Water Resources Association*, 44, 1121-1131, doi: 10.1111/j.1752-1688.2008.00236.x, 2008.
- 5 Bloeschl, G., Ardoin-Bardin, S., Bonell, M., Dorninger, M., Goodrich, D., Gutknecht, D., Matamoros, D., Merz, B., Shand, P., and Szolgay, J.: At what scales do climate variability and land cover change impact on flooding and low flows?, *Hydrological Processes*, 21, 1241-1247, doi: 10.1002/hyp.6669, 2007.
- Bosch, D. D., Arnold, J. G., Volk, M., and Allen, P. M.: Simulation of a low-gradient coastal plain watershed using the SWAT landscape model, *Transactions of the ASABE*, 53, 1445-1456, doi: 10.13031/2013.34899, 2010.
- 10 Cao, W. Z., Bowden, W. B., Davie, T., and Fenemor, A.: Multi-variable and multi-site calibration and validation of SWAT in a large mountainous catchment with high spatial variability, *Hydrological Processes*, 20, 1057-1073, doi: 10.1002/hyp.5933, 2006.
- Chawla, I., and Mujumdar, P. P.: Isolating the impacts of land use and climate change on streamflow, *Hydrology and Earth System Sciences*, 19, 3633-3651, doi: 10.5194/hess-19-3633-2015, 2015.
- 15 Chen, H., Shao, M., and Li, Y.: Soil desiccation in the Loess Plateau of China, *Geoderma*, 143, 91-100, doi: 10.1016/j.geoderma.2007.10.013, 2008.
- Chen, L., Huang, Z., Gong, J., Fu, B., and Huang, Y.: The effect of land cover/vegetation on soil water dynamic in the hilly area of the loess plateau, China, *Catena*, 70, 200-208, doi: 10.1016/j.catena.2006.08.007, 2007.
- Chu, H. J., Lin, Y. P., Huang, C. W., Hsu, C. Y., and Chen, H. Y.: Modelling the hydrologic effects of dynamic land-use change using a distributed hydrologic model and a spatial land-use allocation model, *Hydrological Processes*, 24, 2538-2554, doi: 10.1002/hyp.7667, 2010.
- 20 Douglas-Mankin, K. R., Srinivasan, R., and Arnold, J. G.: Soil and water assessment tool (SWAT) model: current developments and applications, *Transactions of the ASABE*, 53, 1423-1431, doi: 10.13031/2013.34915, 2010.
- Duan, L. X., Huang, M. B., and Zhang, L. D.: Differences in hydrological responses for different vegetation types on a steep slope on the Loess Plateau, China, *Journal of Hydrology*, 537, 356-366, doi: 10.1016/j.jhydrol.2016.03.057, 2016.
- 25

- Easton, Z. M., Fuka, D. R., Walter, M. T., Cowan, D. M., Schneiderman, E. M., and Steenhuis, T. S.: Re-conceptualizing the soil and water assessment tool (SWAT) model to predict runoff from variable source areas, *Journal of Hydrology*, 348, 279-291, doi: 10.1016/j.jhydrol.2007.10.008, 2008.
- 5 Famiglietti, J. S., Rudnicki, J. W., and Rodell, M.: Variability in surface moisture content along a hillslope transect: Rattlesnake Hill, Texas, *Journal of Hydrology*, 210, 259-281, doi: 10.1016/S0022-1694(98)00187-5, 1998.
- Farley, K. A., Jobbagy, E. G., and Jackson, R. B.: Effects of afforestation on water yield: a global synthesis with implications for policy, *Glob. Change Biol.*, 11, 1565-1576, doi: 10.1111/j.1365-2486.2005.01011.x, 2005.
- Feng, X., Fu, B., Piao, S., Wang, S., Ciais, P., Zeng, Z., Lu, Y., Zeng, Y., Li, Y., Jiang, X., and Wu, B.: Revegetation in China's Loess Plateau is approaching sustainable water resource limits, *Nature Climate Change*, 6, 1019-1022, doi: 10.1038/nclimate3092, 2016.
- 10 Fu, W., Huang, M., Gallichand, J., and Shao, M.: Optimization of plant coverage in relation to water balance in the Loess Plateau of China, *Geoderma*, 173-174, 134-144, doi: 10.1016/j.geoderma.2011.12.016, 2012.
- Garen, D. C., and Moore, D. S.: Curve number hydrology in water quality modeling: Uses, abuses, and future directions, *Journal of the American Water Resources Association*, 41, 377-388, doi: 10.1111/j.1752-1688.2005.tb03742.x, 2005.
- 15 Gassman, P. W., Sadeghi, A. M., and Srinivasan, R.: Applications of the SWAT model special section: overview and insights, *Journal of Environmental Quality*, 43, 1-8, doi: 10.2134/jeq2013.11.0466, 2014.
- Guo, Z. T., Ruddiman, W. F., Hao, Q. Z., Wu, H. B., Qiao, Y. S., Zhu, R. X., Peng, S. Z., Wei, J. J., Yuan, B. Y., and Liu, T. S.: Onset of Asian desertification by 22 Myr ago inferred from loess deposits in China, *Nature*, 416, 159-163, doi: 10.1038/416159a, 2002.
- 20 Huang, M. B., Zhang, L., and Gallichand, J.: Runoff responses to afforestation in a watershed of the Loess Plateau, China, *Hydrological Processes*, 17, 2599-2609, doi: 10.1002/hyp.1281, 2003.
- Jian, S. Q., Zhao, C. Y., Fang, S. M., and Yu, K.: Effects of different vegetation restoration on soil water storage and water balance in the Chinese Loess Plateau, *Agricultural and Forest Meteorology*, 206, 85-96, doi: 10.1016/j.agrformet.2015.03.009, 2015.
- 25 Li, J. J., Li, Z., and Lu, Z. M.: Analysis of spatiotemporal variations in land use on the Loess Plateau of China during 1986-

- 2010, *Environmental Earth Sciences*, 75, doi: 10.1007/s12665-016-5807-y, 2016.
- Li, Z., Liu, W., Zhang, X., and Zheng, F.: Impacts of land use change and climate variability on hydrology in an agricultural catchment on the Loess Plateau of China, *Journal of Hydrology*, 377, 35-42, doi: 10.1016/j.jhydrol.2009.08.007, 2009.
- Liang, W., Bai, D., Wang, F. Y., Fu, B. J., Yan, J. P., Wang, S., Yang, Y. T., Long, D., and Feng, M. Q.: Quantifying the impacts of climate change and ecological restoration on streamflow changes based on a Budyko hydrological model in China's Loess Plateau, *Water Resources Research*, 51, 6500-6519, doi: 10.1002/2014wr016589, 2015.
- Liu, J., Li, S., Ouyang, Z., Tam, C., and Chen, X.: Ecological and socioeconomic effects of China's policies for ecosystem services, *Proceedings of the National Academy of Sciences of the United States of America*, 105, 9477-9482, doi: 10.1073/pnas.0706436105, 2008a.
- 10 Liu, M., Tian, H., Chen, G., Ren, W., Zhang, C., and Liu, J.: Effects of land-use and land-cover change on evapotranspiration and water yield in China during 1900-2000, *Journal of the American Water Resources Association*, 44, 1193-1207, doi: 10.1111/j.1752-1688.2008.00243.x, 2008b.
- Liu, M., Tian, H., Yang, Q., Yang, J., Song, X., Lohrenz, S. E., and Cai, W.-J.: Long-term trends in evapotranspiration and runoff over the drainage basins of the Gulf of Mexico during 1901-2008, *Water Resources Research*, 49, 1988-2012, doi: 15 10.1002/wrcr.20180, 2013.
- Liu, Y., Xiao, J., Ju, W., Xu, K., Zhou, Y., and Zhao, Y.: Recent trends in vegetation greenness in China significantly altered annual evapotranspiration and water yield, *Environmental Research Letters*, 11, doi: 10.1088/1748-9326/11/9/094010, 2016.
- Lopez-Moreno, J. I., Vicente-Serrano, S. M., Moran-Tejeda, E., Zabalza, J., Lorenzo-Lacruz, J., and Garcia-Ruiz, J. M.: Impact of climate evolution and land use changes on water yield in the Ebro basin, *Hydrology and Earth System Sciences*, 15, 20 311-322, doi: 10.5194/hess-15-311-2011, 2011.
- Lørup, J. K., Refsgaard, J. C., and Mazvimavi, D.: Assessing the effect of land use change on catchment runoff by combined use of statistical tests and hydrological modelling: Case studies from Zimbabwe, *Journal of Hydrology*, 205, 147-163, doi: 10.1016/S0168-1176(97)00311-9, 1998.
- 25 McVicar, T. R., Li, L., Van Niel, T. G., Zhang, L., Li, R., Yang, Q., Zhang, X., Mu, X., Wen, Z., Liu, W., Zhao, Y. A., Liu, Z.,

- and Gao, P.: Developing a decision support tool for China's re-vegetation program: Simulating regional impacts of afforestation on average annual streamflow in the Loess Plateau, *Forest Ecology and Management*, 251, 65-81, doi: 10.1016/j.foreco.2007.06.025, 2007.
- 5 McVicar, T. R., Van Niel, T. G., Li, L., Wen, Z., Yang, Q., Li, R., and Jiao, F.: Parsimoniously modelling perennial vegetation suitability and identifying priority areas to support China's re-vegetation program in the Loess Plateau: Matching model complexity to data availability, *Forest Ecology and Management*, 259, 1277-1290, doi: 10.1016/j.foreco.2009.05.002, 2010.
- Mul, M. L., Savenije, H. H. G., and Uhlenbrook, S.: Spatial rainfall variability and runoff response during an extreme event in a semi-arid catchment in the South Pare Mountains, Tanzania, *Hydrology and Earth System Sciences*, 13, 1659-1670, 10  
doi: 10.5194/hess-13-1659-2009, 2009.
- Neitsch, S. L., Arnold, J. G., Kiniry, J. R., and Williams, J. R.: Soil and water assessment tool theoretical documentation version 2009, 2011.
- Nyeko, M.: Hydrologic modelling of data scarce basin with SWAT model: capabilities and limitations, *Water Resources Management*, 29, 81-94, doi: 10.1007/s11269-014-0828-3, 2015.
- 15 Pachepsky, Y. A., Timlin, D. J., and Rawls, W. J.: Soil water retention as related to topographic variables, *Soil Science Society of America Journal*, 65, 1787-1795, doi: 10.2136/sssaj2001.1787, 2001.
- Panagopoulos, Y., Makropoulos, C., Baltas, E., and Mimikou, M.: SWAT parameterization for the identification of critical diffuse pollution source areas under data limitations, *Ecological Modelling*, 222, 3500-3512, doi: 10.1016/j.ecolmodel.2011.08.008, 2011.
- 20 Qiao, L., Zou, C. B., Stebler, E., and Will, R. E.: Woody plant encroachment reduces annual runoff and shifts runoff mechanisms in the tallgrass prairie, USA, *Water Resources Research*, 53, 4838-4849, doi: 10.1002/2016WR019951, 2017.
- Qiu, L. J., Zheng, F. L., and Yin, R. S.: SWAT-based runoff and sediment simulation in a small watershed, the loessial hilly-gullied region of China: capabilities and challenges, *International Journal of Sediment Research*, 27, 226-234, doi: 25 10.1016/S1001-6279(12)60030-4, 2012.

- Qiu, Y., Fu, B. J., Wang, J., and Chen, L. D.: Soil moisture variation in relation to topography and land use in a hillslope catchment of the Loess Plateau, China, *Journal of Hydrology*, 240, 243-263, doi: 10.1016/s0022-1694(00)00362-0, 2001.
- Sun, G., Zhou, G., Zhang, Z., Wei, X., McNulty, S. G., and Vose, J. M.: Potential water yield reduction due to forestation across China, *Journal of Hydrology*, 328, 548-558, doi: 10.1016/j.jhydrol.2005.12.013, 2006.
- Tian, F., Lu, Y., Fu, B., Yang, Y., Qiu, G., Zang, C., and Zhang, L.: Effects of ecological engineering on water balance under two different vegetation scenarios in the Qilian Mountain, northwestern China, *Journal of Hydrology: Regional Studies*, 5, 324-335, doi: 10.1016/j.ejrh.2015.11.015, 2016.
- Wang, L., Wang, Q., Wei, S., Shao, M. a., and Li, Y.: Soil desiccation for Loess soils on natural and regrown areas, *Forest Ecology and Management*, 255, 2467-2477, doi: 10.1016/j.foreco.2008.01.006, 2008.
- Wang, S., Fu, B. J., Gao, G. Y., Yao, X. L., and Zhou, J.: Soil moisture and evapotranspiration of different land cover types in the Loess Plateau, China, *Hydrology and Earth System Sciences*, 16, 2883-2892, doi: 10.5194/hess-16-2883-2012, 2012.
- Wang, S., Fu, B., Gao, G., Liu, Y., and Zhou, J.: Responses of soil moisture in different land cover types to rainfall events in a re-vegetation catchment area of the Loess Plateau, China, *Catena*, 101, 122-128, doi: 10.1016/j.catena.2012.10.006, 2013.
- Wang, Y., Shao, M. a., Zhu, Y., and Liu, Z.: Impacts of land use and plant characteristics on dried soil layers in different climatic regions on the Loess Plateau of China, *Agricultural and Forest Meteorology*, 151, 437-448, doi: 10.1016/j.agrformet.2010.11.016, 2011.
- Wei, W., Chen, L. D., Zhang, H. D., and Chen, J.: Effect of rainfall variation and landscape change on runoff and sediment yield from a loess hilly catchment in China, *Environmental Earth Sciences*, 73, 1005-1016, doi: 10.1007/s12665-014-3451-y, 2015.
- Wu, Y., and Chen, J.: Analyzing the water budget and hydrological characteristics and responses to land use in a monsoonal climate river basin in south China, *Environmental Management*, 51, 1174-1186, doi: 10.1007/s00267-013-0045-5, 2013.
- Xu, Y. D., Fu, B. J., He, C. S., and Gao, G. Y.: Watershed discretization based on multiple factors and its application in the Chinese Loess Plateau, *Hydrology and Earth System Sciences*, 16, 59-68, doi: 10.5194/hess-16-59-2012, 2012.

- Yang, L., Wei, W., Chen, L., Chen, W., and Wang, J.: Response of temporal variation of soil moisture to vegetation restoration in semi-arid Loess Plateau, China, *Catena*, 115, 123-133, doi: 10.1016/j.catena.2013.12.005, 2014.
- Zhang, G., Tang, M., and Zhang, X.: Temporal variation in soil detachment under different land uses in the Loess Plateau of China, *Earth Surface Processes and Landforms*, 34, 1302-1309, doi: 10.1002/esp.1827, 2009.
- 5 Zhang, X., Srinivasan, R., Debele, B., and Hao, F.: Runoff simulation of the headwaters of the Yellow River using the SWAT model with three snowmelt algorithms, *Journal of the American Water Resources Association*, 44, 48-61, doi: 10.1111/j.1752-1688.2007.00137.x, 2008.
- Zhang, X., Srinivasan, R., Arnold, J., Izaurrealde, R. C., and Bosch, D.: Simultaneous calibration of surface flow and baseflow simulations: a revisit of the SWAT model calibration framework, *Hydrological Processes*, 25, 2313-2320, doi: 10.1002/hyp.8058, 2011.
- 10 Zhang, X., Izaurrealde, R. C., Arnold, J. G., Williams, J. R., and Srinivasan, R.: Modifying the Soil and Water Assessment Tool to simulate cropland carbon flux: Model development and initial evaluation, *Science of the Total Environment*, 463-464, 810-822, doi: 10.1016/j.scitotenv.2013.06.056, 2013.
- Zhao, G., Mu, X., Wen, Z., Wang, F., and Gao, P.: Soil erosion, conservation, and eco-environment changes in the Loess Plateau of China, *Land Degradation & Development*, 24, 499-510, doi: 10.1002/ldr.2246, 2013.
- 15 Zhen, N., Fu, B., Lü, Y., and Zheng, Z.: Changes of livelihood due to land use shifts: A case study of Yanchang County in the Loess Plateau of China, *Land Use Policy*, 40, 28-35, doi: 10.1016/j.landusepol.2013.05.004, 2014.
- Zhou, D., Zhao, S., and Zhu, C.: The Grain for Green Project induced land cover change in the Loess Plateau: A case study with Ansai County, Shanxi Province, China, *Ecological Indicators*, 23, 88-94, doi: 10.1016/j.ecolind.2012.03.021, 2012.
- 20 Zucco, G., Brocca, L., Moramarco, T., and Morbidelli, R.: Influence of land use on soil moisture spatial-temporal variability and monitoring, *Journal of Hydrology*, 516, 193-199, doi: 10.1016/j.jhydrol.2014.01.043, 2014.
- Zuo, D., Xu, Z., Yao, W., Jin, S., Xiao, P., and Ran, D.: Assessing the effects of changes in land use and climate on runoff and sediment yields from a watershed in the Loess Plateau of China, *Science of the Total Environment*, 544, 238-250, doi: 10.1016/j.scitotenv.2015.11.060, 2016.



**Table 1 Sensitive parameters for streamflow simulation and calibrated values**

Parameters	Description	Range	Optimized value/ percent change
CN2	Soil conservation service (SCS) runoff curve number	-20%~20%	-4.03% <sup>r</sup>
SOL_AWC	Soil available water capacity	-20%~20%	10.71% <sup>r</sup>
SOL_K	Soil saturated hydraulic conductivity (mm/h)	-20%~20%	7.36% <sup>r</sup>
ESCO	Soil evaporation compensation factor	0~1	0.51 <sup>v</sup>
EPCO	Plant uptake compensation factor	0~1	0.65 <sup>v</sup>
ALPHA_BF	Baseflow alpha factor (day)	0~0.5	0.36 <sup>v</sup>
GWQMN	Threshold depth of water in the shallow aquifer required for return flow to occur (mm)	100~1200	906.20 <sup>v</sup>
SURLAG	Surface runoff lag coefficient	0.05~6	2.93 <sup>v</sup>
REVAPMN	Threshold depth of water in the shallow aquifer for "revap" to occur (mm)	100~1200	499.40 <sup>v</sup>

Note: the superscripts “r” and “v” in the column of optimized value indicate the percent changes based on initial values and replaced parameter values, respectively.

**Table 2 Land use changes in the Yanhe basin from 1990 to 2010**

	Cropland		Grassland		Woodland		Residential land		Water		Barren land	
	Area (km <sup>2</sup> )	Pct. (%)	Area (km <sup>2</sup> )	Pct. (%)	Area (km <sup>2</sup> )	Pct. (%)	Area (km <sup>2</sup> )	Pct. (%)	Area (km <sup>2</sup> )	Pct. (%)	Area (km <sup>2</sup> )	Pct. (%)
1990	3051.2	40.2	3390.4	44.7	1059.6	13.9	21.4	0.28	65.4	0.86	3.1	0.040
2000	2246.4	29.6	3436.3	45.3	1842.4	24.3	43.9	0.58	17.2	0.23	0.7	0.009
2010	1338.3	17.6	4178.7	55.1	1986.3	26.2	66.4	0.87	16.6	0.22	0.5	0.006

Note: "Pct." stands for the "Percentage"; similarly hereinafter.

**Table 3 Primary patterns of land use change in the Yanhe basin from 1990 to 2010**

	1990-2000		2000-2010		1990-2010	
	Area (km <sup>2</sup> )	Pct. (%)	Area (km <sup>2</sup> )	Pct. (%)	Area (km <sup>2</sup> )	Pct. (%)
Cropland to woodland	509.2	16.7	143.6	6.4	598.5	19.6
Cropland to grassland	1204.6	39.5	745.4	33.2	1661.8	54.5
Cropland to residential land	15.9	0.5	20.7	0.9	28.5	0.9
Cropland to barren land	0.3	0.0	0.0	0.0	0.1	0.0
Grassland to woodland	762.3	22.5	0.6	0.0	796.7	23.5
Grassland to cropland	683.1	20.1	1.5	0.0	410.4	12.1
Grassland to residential land	7.1	0.2	0.6	0.0	10.4	0.3
Grassland to barren land	0.4	0.0	0.0	0.0	0.3	0.0
Woodland to cropland	206.5	19.5	0.0	0.0	133.8	12.6
Woodland to grassland	281.5	26.6	0.0	0.0	330.1	31.1
Woodland to residential land	5.2	0.5	0.5	0.0	9.4	0.9
Woodland to barren land	0.0	0.0	0.0	0.0	0.0	0.0
Barren land to woodland	0.2	7.4	0.0	0.0	0.2	7.4
Barren land to grassland	0.8	25.9	0.0	0	1.0	31.7
Barren land to cropland	2.0	65.1	0.0	0.0	1.7	54.6
Barren land to residential land	0.0	0.0	0.0	0.0	0.2	6.4

**Table 4 Simulated average annual values of hydrological components in the Yanhe basin under different land use conditions**

	Surface runoff (mm)	Subsurface flow (mm)	ET (mm)	Water yield (mm)	Soil water (mm)
LU1990	15.1	22.2	461.8	37.3	123.0
LU2000	12.6	22.6	464.5	35.2	113.1
LU2010	10.7	22.8	466.5	33.6	109.5

**Table 5 Slope characteristics of each land use type ~~in~~ at 2010 baseline and under different slope land conversion scenarios (unit: km<sup>2</sup>)**

		Cropland	Woodland	Grassland	Residential land	Barren land
<del>LU2010BS</del>	<15°	814.3	761.2	1677.7	52.5	0.3
	15°~25°	392.7	808.4	1640.8	10.8	0.1
	>25°	131.6	417.3	860.9	3.2	0.0
S1	<15°	—	—	—	—	—
	15°~25°	—	—	—	—	—
	>25°	0	417.3	992.5	3.2	0.0
S2	<15°	—	—	—	—	—
	15°~25°	—	—	—	—	—
	>25°	0	548.9	860.9	3.2	0.0
S3	<15°	—	—	—	—	—
	15°~25°	0	808.4	2033.5	10.8	0.1
	>25°	0	417.3	992.5	3.2	0.0
S4	<15°	—	—	—	—	—
	15°~25°	0	1201.0	1640.8	10.8	0.1
	>25°	0	548.9	860.9	3.2	0.0

Note: ‘—’ indicates the same value as that of ~~LU2010BS~~ (LU2010).

**Table 6 Simulated average annual values of hydrological components under different scenarios of slope land conversion**

	Surface runoff (mm)	Subsurface flow (mm)	ET (mm)	Water yield (mm)	Soil water (mm)
S1	10.4	22.9	466.8	33.3	109.0
S2	10.3	23.0	466.9	33.2	107.7
S3	9.37	23.3	467.6	32.7	107.5
S4	8.87	23.7	467.8	32.6	102.5






Fig. 1 Map of the Yanhe basin showing the elevation and the locations of the meteorological and hydrological stations



**Fig. 2** Precipitation and streamflow changes in different decades in the Yanhe basin





**Fig. 3 Model performance for the (a) 10-year (1983–1992) calibration period and the (b) 8-year (1993–2000) validation period**




Fig. 4 Land use changes from 1990 to 2010 in the Yanhe basin






Fig. 5 Calculated (a) unit area and (b) total annual hydrological components for the 18-year simulation period (1983–2000) for different land use types in the Yanhe basin



**Fig. 6 (a) Simulated annual streamflow and (b) simulated multiyear average monthly streamflow (the data were averaged from 1986 to 2015) at the outlet of the Yanhe basin under different land use conditions**



**Fig. 7** Simulated spatial distribution of (a) surface runoff, (b) water yield, (c) ET and (d) soil water under land use change between 1990 and 2010




Fig. 8 Calculated average annual total water volume under different land use scenarios




Fig. 9 Calculated soil water difference between the baseline scenario and (a) S1, (b) S2, (c) S3 and (d) S4