

Modeling and interpreting hydrological responses of sustainable urban drainage systems with explainable machine learning methods

Yang Yang¹, Ting Fong May Chui¹

¹Department of Civil Engineering, The University of Hong Kong, Hong Kong SAR, China

5 *Correspondence to:* Ting Fong May Chui (maychui@hku.hk)

Abstract. Sustainable urban drainage systems (SuDS) are decentralized stormwater management practices that mimic natural drainage processes. The hydrological processes of SuDS are often modeled using process-based models. However, it can require considerable effort to set up these models. This study thus proposes a machine learning (ML) method to directly learn the statistical correlations between the hydrological responses of SuDS and the forcing variables at sub-hourly time scales from observation data. The proposed methods are applied to two SuDS catchments with different sizes, SuDS practice types, and data availabilities in the U.S. for discharge prediction. The resulting models have high prediction accuracies (NSE > 0.70 for all models). ML explanation methods are then employed to derive the basis of each ML prediction and based on which the hydrological processes being modeled are inferred. The physical realism of the inferred hydrological processes is then compared to that would be expected based on the domain-specific knowledge of the system being modeled. The inferred processes of some models, however, are found to be physically implausible. For instance, negative contributions of rainfalls to runoffs have been identified in some models. This study further empirically shows that an ML model's ability to provide accurate predictions can be uncorrelated with its ability to offer plausible explanations to the physical processes being modeled. Finally, this study provides a high-level overview of the practices of inferring physical processes from the ML modeling results and shows both conceptually and empirically that large uncertainty exists in every step of the inference processes. In summary, this study shows that ML methods are a useful tool for predicting the hydrological responses of SuDS catchments and inferred hydrological processes from modeling results should be interpreted cautiously due to the existence of large uncertainty in the inference processes.

1 Introduction

Sustainable urban drainage systems (SuDS), also known as low impact development practices, green infrastructure, and sponge city, are decentralized stormwater management practices that aim to promote onsite infiltration, storage, evapotranspiration, and stormwater reuse (Fletcher et al., 2015; Jones and Macdonald, 2007). SuDS can effectively improve stormwater runoff quality, reduce runoff volume, and restore natural hydrological regimes (Selbig et al., 2019; Trinh and Chui, 2013; Zhou, 2014). Commonly used SuDS include bioretention cells, green roofs, porous pavement, and rain barrels (Charlesworth, 2010; Gimenez-Maranges et al., 2020).

30 A number of numerical modeling methods have been adopted or developed to predict the hydrological performance of SuDS and understand the involved hydrological processes (Elliott and Trowsdale, 2007; Liu et al., 2014). The simplest methods are perhaps those developed based on empirical equations for assessing the drainage impact of different land use types. For instance, the rational method and SCS runoff curve number method are modified and used in Montalto et al. (2007) and Damodaram et al. (2010) to study the effectiveness of SuDS at catchment scales. Empirical equation-based methods can
35 be useful in preliminary designs to rapidly estimate some key performance metrics of SuDS. However, these methods may poorly reflect detailed SuDS design variations (Fassman-Beck et al., 2016).

Process-based models are another approach to modeling SuDS, in which physically-based or empirical equations are used to characterize the involved hydrological processes. SuDS are typically represented in process-based models as hydrological functional units, whose properties are defined using a set of parameters. Commonly used models, including SWMM and
40 MUSIC, are reviewed in Eckart et al. (2017) and Elliott and Trowsdale (2007).

The application of process-based models, however, faces several challenges. First, it may require considerable effort to set up a process-based model for SuDS, as not all the required parameters are measurable or can be measured at a reasonable cost. For example, in the SWMM, the initial soil moisture deficit parameter of SuDS is often determined through calibration (Rosa et al., 2015). Second, some complex hydro-environmental processes of SuDS and surrounding environments are difficult to
45 model using existing models. For instance, SWMM does not account for macropore flow in the SuDS soil layer (Niazi et al., 2017), and models that assess the performance of SuDS in shallow groundwater environments (Zhang and Chui, 2019) and cold climates (Johannessen et al., 2017) are limited. Third, the assumptions used in process-based models may be invalid in some cases due to unknown issues related to construction, maintenance, or physical property changes during a SuDS' service life (Yong et al., 2013).

50 It may be useful to model directly the statistical correlations between the random variables that describe the states of SuDS catchments. The resulting statistical models may be adopted for solving various prediction tasks and used as references to assess the prediction accuracy of process-based models. These models may be derived using machine learning (ML) methods, which aim to learn the statistical correlations between random variables from observation data (Solomatine and Ostfeld, 2008). Terms that are closely related to ML include data-driven modeling, predictive modeling, and statistical learning.

55 ML methods have been widely used in various fields in hydrology (Maier and Dandy, 2000). However, they have only been used in a few SuDS-related studies. For instance, linear regression methods were used in Eric et al. (2015), Hopkins et al. (2020), and Khan et al. (2013) to predict the hydrological effectiveness of SuDS, such as runoff volume reduction, based on factors such as inflow volume, antecedent soil moisture content, and SuDS implementation levels. Li et al. (2019) used neural networks models to predict the peak flow and runoff volume of a runoff event of a SuDS site based on rainfall event
60 characteristics. The studies mentioned above focused on predicting the long-term or rainfall event-level hydrological performance of SuDS. However, there is currently insufficient literature on the application of ML methods to model the temporal evolution of the hydrological responses of SuDS at regular time steps, e.g., daily, hourly, or sub-hourly. Yang and Chui (2019) showed that ML methods, such as deep learning methods and random forest methods, are useful for predicting

the runoff response of SuDS at sub-hourly time scales, provided that the model's input variables are appropriate. However, a
65 method to derive these input variables was not described in their study.

The lack of popularity of ML methods in SuDS-related studies may be explained by several factors. First, ML methods are
not applicable when observation data of the variables of interest are unavailable. Second, modeling the hydrological responses
of SuDS at fine temporal scales requires a high-dimensional hydrometeorological time series to be used as input, which can
be challenging for ML methods that are not specifically designed for modeling sequence data (Nielsen, 2019). Additionally,
70 ML methods may also not offer clear advantages over equation-based methods when applied to study the performance of SuDS
at the rainfall event level. Third, ML models are usually trained to capture the statistical correlations between random variables
without or with little consideration of the involved physical processes, thus they may be considered less useful for
understanding the physical processes compared to process-based models.

Therefore, to promote the application of ML methods in SuDS related studies, one must show that ML methods can provide
75 accurate predictions for various tasks and that the involved hydrological processes can be interpreted. While it is
straightforward to apply specific ML methods to solve prediction tasks, there is currently insufficient research into interpreting
the hydrological processes learned by ML models.

Several studies in hydrology explained ML models using methods adopted from explainable artificial intelligence (XAI),
which is an emerging field of ML that aims to make ML modeling results more understandable to humans (Bojanowski et al.,
80 2018). Commonly used XAI methods for understanding the functioning of ML models include transparent ML models and
post-hoc explainability techniques (Barredo Arrieta et al., 2020). Transparent ML models refer to those with structures that
are directly understandable to humans, which include linear regression models, decision trees, and K-nearest neighbors. These
models have been frequently adopted in hydrology for understanding the correlations between random variables or the basis
of specific predictions (Solomatine and Dulal, 2003; Wani et al., 2017). Post-hoc explainability techniques aim to explain ML
85 models that are not transparent. For instance, in hydrology, the integrated gradients method (Sundararajan et al., 2017) has
been used in Kratzert et al. (2019) to understand the contribution of meteorological input at different time steps to streamflow
discharge prediction in neural networks, the permutation feature importance method has been used in Schmidt et al. (2020) to
assess the importance of the predictors for flood magnitude prediction in various ML models, and the SHAP method (Lundberg
and Lee, 2017) has been used in Starn et al. (2021) to identify the factors affecting groundwater residence time distribution
90 predictions in XGBoost models (Chen and Guestrin, 2016).

Most of the current hydrology literature uses post-hoc explainability techniques to test whether an ML model makes right
predictions for the right reasons, where a model is generally considered more trustworthy if it can generate predictions in a
way that is consistent with our knowledge of the system being modeled. Here, the term trustworthy is defined broadly as the
quality of a model to provide predictions that can be trusted (Morton, 1993). The current applications essentially test the
95 patterns learned by ML models against that would be expected from the domain-specific knowledge of the system being
modeled (Yang and Chui, 2021), and the test results are then used as an indicator of a model's trustworthiness. This approach,
however, may be challenged by the fact that ML models can uncover hidden patterns in data that make no intuitive sense to

humans (Ilyas et al., 2019). Thus, the quality of a model to provide accurate predictions and plausible explanations to the physical processes may be uncorrelated. Rudin (2019) further suggests that the post-hoc explainability techniques themselves are uncertain as approximated because inaccurate representations of the original model may be adopted in deriving the explanations, and similar views on the uncertainties in explanation are also reported in Chen et al. (2020) and Sundararajan and Najmi (2020).

Therefore, in hydrological studies, it is meaningful to ask whether post-hoc explainability techniques and ML models can provide physically plausible explanations to the processes of the system being modeled and whether a model's abilities to provide accurate predictions and plausible explanations are correlated. This study aims to investigate these questions by examining the ML models that are trained to predict hydrological responses of SuDS catchments at sub-hourly time scales, and through which the applicability of ML methods to modeling SuDS catchments is also assessed.

2 Methods and materials

2.1 Training and testing machine learning models

2.1.1 Modeling hydrological responses of SuDS using machine learning methods

Let random variable Y_t denote the hydrological response of a SuDS catchment at time step t and random vector \mathbf{X}_t denote the time series of the hydrometeorological conditions and other factors measured on and before time step t .


$$\mathbf{X}_t := [P_t, P_{t-1}, P_{t-2}, \dots, E_1, E_2, \dots, E_k], \quad (1)$$

where P_{t-i} is the rainfall depth recorded at time step $t - i$, and E_1 through E_k represent k measurements of the other variables. P_{t-0} is written as P_t for convenience.

It is assumed that Y_t can be written as an unknown function of \mathbf{X}_t , which can be approximated by functions learned by ML algorithms from observation data of \mathbf{X}_t and Y_t . A feature engineering process is commonly involved in the learning process, in which \mathbf{X}_t is converted to lower-dimensional representations using a function g such that the function between $g(\mathbf{X}_t)$ and Y_t be learned more easily by ML algorithms (Kuhn and Johnson, 2019). Y_t can then be estimated using \hat{Y}_t , which is computed following

$$\hat{Y}_t = f_\theta(g_\varphi(\mathbf{X}_t)), \quad (2)$$

where f is a function learned by an ML algorithm, and φ and θ are parameters of g and f . Figure 1 illustrates the processes for deriving the prediction for an input sample \mathbf{x}_t .



125

Figure 1 An example of the prediction generation process for an input sample \mathbf{x}_t .

The goal of ML is then to identify the optimal parameter values θ^* and φ^* that minimize the expected loss ℓ over the data distribution $p_d(\mathbf{X}_t, Y_t)$, as shown in

$$(\theta^*, \varphi^*) = \underset{\theta, \varphi}{\operatorname{argmin}} E_{(\mathbf{x}_t, Y_t) \sim p_d(\mathbf{X}_t, Y_t)} \ell \left(f_\theta \left(g_\varphi(\mathbf{X}_t) \right), Y_t \right) \quad (3)$$

130

As $p_d(\mathbf{X}_t, Y_t)$ are unknown, the expectation is often approximated by averaging the losses computed for a set of observed samples (\mathbf{x}_t, y_t) .

2.1.2 Feature engineering methods

135

Gauch et al. (2020) showed that the hydrometeorological time series recorded in the long-term past can be represented using a coarser temporal resolution in ML models built for rainfall-runoff modeling without deteriorating their prediction accuracy. This study adopts a similar approach to represent a rainfall time series by aggregated rainfall depths recorded during different intervals, in which rainfall time series recorded between time steps $t - a$ and $t - b$ is represented by a rainfall depth feature


$$D_{t-a, t-b},$$

$$D_{t-a, t-b} = \sum_{i=a}^b P_{t-i}, \quad (4)$$

However, an approach to optimally define the set of (a, b) pairs to create rainfall depth features is not known *a priori*.

This study proposes a simple method to systematically select cut points along the time axis, which form a series of intervals for defining (a, b) pairs. As shown in Figure 2, the selection of cut points is controlled by three hyperparameters, m , l , and n . (1) m : a cut point is placed between time steps $t - m$ and $t - m - 1$ such that the rainfall data recorded prior to $t - m$ are considered irrelevant for predicting Y_t . (2) l : the rainfall data recorded between $t - l$ and $t - 0$ are considered to be most relevant for predicting Y_t , so that cut points are placed around each time step within this interval. (3) n : $n - 1$ cut points are placed between $t - l - 1$ and $t - m$, such that the neighboring cut points correspond to n intervals whose lengths roughly form an arithmetic sequence. After (a, b) pairs having been defined, a rainfall depth feature $D_{t-a,t-b}$ is then created for every interval formed by two neighboring cut points.

$m = 11$. P_t through P_{t-11} are considered relevant for predicting Y_t . A cut point is placed before P_{t-11} .



$n = 3$. Two cut points are placed between P_{t-3} and P_{t-11} such that the lengths of the three intervals defined by the neighboring points form an arithmetic sequence.

$l = 2$. P_t through P_{t-2} are considered most relevant for predicting Y_t . Cut points are placed around each P_{t-i} .

Figure 2 Illustration of the methods to place cut points along the time axis.

Representing a rainfall time series using a set of $D_{t-a,t-b}$ can reduce the dimensionality of data at the cost of losing information regarding the temporal distribution of rainfall. In this method, fewer cut points are selected for rainfalls in the long-term past (e.g., a few days), which is based on the assumption that they are less important for predicting Y_t . This is reasonable considering the relatively fast response time of SuDS (DeBusk et al., 2011). Similarly, some of the environmental variables $[E_1, E_2, \dots, E_k]$ may be less important for predicting Y_t , which can be filtered out during the feature engineering process. In this study, whether or not to include E_i is controlled by a Boolean variable, and k such variables are used.

In this study, the optimal values of the feature engineering hyperparameters, m , l , n , and the k Boolean variables, are determined using resampling and Bayesian optimization methods as described below.

2.1.3 XGBoost algorithm

This study adopts the gradient-boosted trees algorithm (Friedman, 2001) to train ML models. In particular, the XGBoost (Chen and He, 2020) software library is used. XGBoost is selected for its improved regularization methods, high computational efficiency, and ability to achieve state-of-the-art results on various ML tasks (Chen and Guestrin, 2016; Chen and He, 2020; Nielsen, 2016). A detailed introduction to XGBoost can be found in Chen and Guestrin (2016) and Mitchell and Frank (2017).

A gradient boosted trees model G is an ensemble of decision trees, in which \hat{y}_i , the prediction for an input sample \mathbf{x}_i , is the sum of the predictions of individual trees (Chen and Guestrin, 2016), given as

$$\hat{y}_i = G(\mathbf{x}_i) = \sum_{k=1}^K f_k(\mathbf{x}_i), f_k \in \mathcal{F}, \quad (5)$$

165 where f_k is a decision tree that maps input samples to the values stored at the tree leaves, K is the number of decision trees (also known as the number of boosting iterations), and \mathcal{F} is the functional space of all possible regression trees. For a given dataset, the structure of the trees, including the splitting criteria and the values stored at the leaves, is learned automatically using XGBoost.

170 There are a number of hyperparameters used in XGBoost for controlling model structure and the learning behaviors during training, e.g., the number of boosting iterations and maximal tree depth. A complete list of the XGBoost hyperparameters can be found in the software documentation (Chen and He, 2020). In this study, the XGBoost hyperparameters are optimized together with the feature engineering hyperparameters using resampling and Bayesian optimization methods as described below.

2.1.4 Resampling methods and Bayesian optimization for training and testing machine learning models

175 In this study, the effectiveness of the feature engineering and XGBoost algorithms are evaluated on different datasets of observed (\mathbf{x}_t, y_t) samples collected at different SuDS sites. For each dataset, the evaluation is performed by randomly splitting the dataset into a series of training and test subsets. For each such split, during the hyperparameter optimization phase, the training set is further split into a series of smaller training and validation datasets. Then, multiple models with different feature engineering and XGBoost hyperparameters are trained on the smaller training datasets, and the quality of a set of
180 hyperparameters is measured by the prediction accuracy of the resulting model on the validation datasets. During the model evaluation phase, the optimal hyperparameters identified earlier are used to fit a model on the training dataset (which includes both the smaller training and validation datasets), and the resulting model is evaluated using the test dataset. Apparently, the assessment results are affected by how the dataset is split, thus the hyperparameter optimization and model evaluation processes are repeated for various splits in this study. More information on resampling methods can be found in Kuhn and
185 Johnson (2013) and Hastie et al. (2009).

During the hyperparameter optimization phase, the candidate hyperparameters to be assessed are proposed by Bayesian optimization methods, which are sample-efficient algorithms for solving black-box optimization problems (Shahriari et al., 2016). Bayesian optimization methods are commonly used in ML for hyperparameter optimization for a given ML algorithm and a set of training and validation datasets (Snoek et al., 2012). The decision variables in the optimization problems are the
190 hyperparameters, and the quantity to be minimized is the prediction accuracy on the validation datasets. An introduction to Bayesian optimization can be found in Frazier (2018).

2.2 Interpreting model structures and inferring hydrological processes learned by machine learning models

2.2.1 Interpreting the basis of each prediction

Understanding why a specific prediction is made by an ML model can be useful for understanding the correlations between various variables captured by the model. In this study, XGBoost uses decision trees as its base learner. Although each decision tree can be considered as a transparent ML model (as the rules used for making predictions can be understood easily by humans), it can be challenging to directly interpret the prediction generation process of XGBoost as many trees can be used in it. Therefore, post-hoc explainability techniques, such as the *gain*, *cover*, and *frequency* metrics, are commonly used for understanding the structure of XGBoost models.

The gain of a feature is its relative contribution to the model as measured by the total gain of the feature's splits. It can be roughly regarded as a feature's contribution to prediction accuracy improvement (Chen and He, 2020). The cover of a feature is the relative number of training samples related to the feature's splits (Chen and He, 2020). The frequency of a feature is the relative number of times that this feature has been used in tree splits (Chen and He, 2020). The three metrics are global feature importance measures, as they reflect the overall contribution of a feature to an XGBoost model for making various predictions (Ahmad et al., 2018; Guidotti et al., 2019). However, these metrics can be irrelevant for understanding the basis of a specific prediction, which is a task that requires local explanation methods.

This study adopts a local feature attribution method to quantify the contribution of each feature to the prediction made for a specific input sample (Janzing et al., 2019). The SHAP (SHapley Additive exPlanations) method proposed by Lundberg and Lee (2017) is used in this study. The SHAP value of a feature for a specific input sample can be considered as the marginal contribution of this feature to the predicted value compared to the mean predictions for all samples. SHAP values satisfied a series of desired properties. For instance, the sum of the SHAP value assigned to each feature equals the difference between the predicted value and the mean prediction for all samples, and the features that do not change the expected prediction are assigned with a SHAP value of 0 (Lundberg et al., 2020). The SHAP values can be computed using the following steps.

Let the real-valued function f of N -dimensional random variable \mathbf{X} be the ML model to be explained and $\mathbf{x} := (x_1, x_2, \dots, x_N)$ be an observed sample. ϕ_i , the SHAP value of x_i , is computed as

$$\phi_i = \frac{1}{N!} \sum_{R \in \mathcal{R}} [v(S^R \cup i) - v(S^R)], \quad (6)$$

where, R is a random permutation of the N features, \mathcal{R} is the space of all feature permutations, S^R is the set of features that are located before feature i , and $v: S \in \mathcal{P}(N) \rightarrow \mathbb{R}$ is a set function that maps every non-empty subset of N features (i.e., each member of power set $\mathcal{P}(N)$ that is not empty) to a real number, and v is known as the value function.

Therefore, ϕ_i can be interpreted as the expected marginal contribution to v of feature i (i.e., $v(S^R \cup i) - v(S^R)$) in random permutations of the features. Equation 6 is developed based on the Shapley value used in game theory, more information on which can be found in Shapley (1953) and Osborne and Rubinstein (1994).

In the SHAP method, v is the expected prediction of f when some features are missing and may be defined in various ways. Lundberg and Lee (2017) define v using the observational conditional expectation, which is the expected value of f when the feature values of \mathbf{X} in S are known, as in

$$v(S) = E[f(\mathbf{X}) | \mathbf{X}_S = \mathbf{x}_S], \quad (7)$$

Janzing et al. (2019) and Lundberg et al. (2020) defined v using the interventional conditional expectation

$$v(S) = E[f(\mathbf{X}) | do(S)], \quad (8)$$

where $do(S)$ represents an intervention that sets the feature values of \mathbf{X} in S to \mathbf{x}_S . The SHAP values derived using Equations 7 and 8 are respectively termed *observational SHAP values* and *interventional SHAP values*. The observational SHAP value of x_i generally measures the value of knowing x_i to predict the outcome, and the interventional SHAP value of x_i corresponds to the expected changes in the model prediction when the feature X_i is set to the x_i .

Chen et al. (2020) suggested that both observational and interventional SHAP values are useful. They claimed that the observational SHAP values are “true to the data” because they are effective in identifying the true correlations between the features and the modeled outcome, whereas the interventional SHAP values are “true to the model” because they do not credit the features that are unused by the model. The observational SHAP values are used in most places of this paper as they are less computationally expensive than the interventional SHAP values using the TreeSHAP method proposed in Lundberg et al. (2020).

For a given input sample \mathbf{x}_t , the SHAP value assigned to a rainfall depth feature $d_{t-a,t-b}$ can be further distributed among the rainfall recorded at each time step p_{t-k} between time steps $t - a$ and $t - b$. The SHAP value $\phi_{D_{t-a,t-b}}(\mathbf{x}_t)$ can be assigned to each relevant p_{t-k} proportional to its value. Thus, $\tau_k(\mathbf{x}_t)$, the SHAP value assigned to p_{t-k} if $d_{t-a,t-b} \neq 0$, can be computed using

$$\tau_k(\mathbf{x}_t) = \frac{p_{t-k}}{d_{t-a,t-b}} \phi_{D_{t-a,t-b}}(\mathbf{x}_t), \quad (9)$$

The processes for quantifying the contribution of each feature of an input sample \mathbf{x}_t to model prediction and distributing the contributions to the rainfall of each time step are illustrated in Figure 3a.




Figure 3 (a) Illustration of the processes for quantifying the contribution of each feature of an input sample x_t and distributing the contribution to the rainfall of each time step. (b) Examples of inferring the hydrological processes being modeled based on the basis of each prediction. (c) Examples of comparing the inferred hydrological processes to the processes expected based on the domain-specific knowledge of the system being modeled.

2.2.2 Inferring hydrological processes from machine learning modeling results

The process of inferring the hydrological processes being modeled involves mapping from the explanations on the model structure to some imaginary catchments that are likely to possess the characteristics that are consistent with the explanations. For instance, if the explanations indicate that discharge predictions are largely controlled by rainfalls in the long-term past, then they are likely to correspond to processes of catchments with long-term memory effects. However, the mapping processes are inherently subjective and incomplete, discussions of these characteristics are presented in Section 3.6. This section introduces the methods to map the explanations to imaginary catchments, and more discussions on the limitations are given when the case study results are presented.

In this study, for each \mathbf{x}_t , $\tau_k(\mathbf{x}_t)$ is computed for p_{t-k} of each time step. These $\tau_k(\mathbf{x}_t)$ values quantitatively describe the associations between rainfall and the hydrological response across various time steps, which is useful for inferring the catchment's hydrological processes. For instance, if the predictions are found to be mostly controlled by recent rainfalls, then the processes being modeled can correspond to that from a small catchment with a fast response to rainfalls. The $\tau_k(\mathbf{x}_t)$ values can be useful for hydrograph decomposition. That is, a predicted hydrograph can be decomposed to sub-hydrographs associated with rainfalls that occurred in different periods based on their contribution to the predicted discharge, which is different from the current practices that decompose a hydrograph based on the origin of the runoffs, such as baseflow and overland flow (Pelletier and Andréassian, 2020). The implications of using this method are discussed in Section 3.2.

The SHAP values of multiple samples can be analyzed collectively to obtain a global understanding of the model structure and the system being modeled (Lundberg et al., 2020). This study thus computes the expected $\tau_k(\mathbf{x}_t)$ values for multiple \mathbf{x}_t in a set S when k is fixed to understand the average association between p_{t-k} and $f(\mathbf{x}_t)$ using

$$E_{\mathbf{x}_t \in S}(\tau_k(\mathbf{x}_t)) = \frac{\sum_{\mathbf{x}_t \in S} \tau_k(\mathbf{x}_t)}{|S|}, \quad (10)$$

where $|S|$ is the number of elements of S . When S contains all the \mathbf{x}_t samples, $E_{\mathbf{x}_t \in S}(\tau_k(\mathbf{x}_t))$ describes the overall association between p_{t-k} and $f(\mathbf{x}_t)$ learned by the model.

SHAP values can be negative, which will result in negative $\tau_k(\mathbf{x}_t)$ values. To avoid canceling out positive and negative $\tau_k(\mathbf{x}_t)$ values when computing the expectations, the absolute value of $\tau_k(\mathbf{x}_t)$ may be used. The quantity of $|\tau_k(\mathbf{x}_t)|$ can be interpreted as the importance of p_{t-k} for $f(\mathbf{x}_t)$. The expected value of $|\tau_k(\mathbf{x}_t)|$ of for a set S of \mathbf{x}_t be computed using

$$E_{\mathbf{x}_t \in S}(|\tau_k(\mathbf{x}_t)|) = \frac{\sum_{\mathbf{x}_t \in S} |\tau_k(\mathbf{x}_t)|}{|S|}, \quad (11)$$

Similarly, for a given \mathbf{x}_t , the contribution of rainfalls recorded between time steps $t - a$ and $t - b$, $T_{a,b}(\mathbf{x}_t)$, can be simply computed as

$$T_{a,b}(\mathbf{x}_t) = \sum_{i=a}^b \tau_i(\mathbf{x}_t) \quad (12)$$

Figure 3b gives two examples of inferring hydrological processes from ML modeling results.

2.2.3 Assessing the physical realism of the inferred processes using knowledge

The inferred hydrological processes may be tested in terms of their physical realism. The premise of this test is that if an ML model can provide physically plausible explanations to the processes it models, then its predictions can generally be considered more trustworthy (Yang and Chui, 2021). That is, this test concerns whether the right predictions are made for the right reasons (Kirchner, 2006). The justification of this method is examined in Section 3.6.

In the proposed assessment method, the inferred hydrological processes are compared to the hydrological processes that would be expected based on the domain-specific knowledge of the system being modeled. In another word, whether the inferred hydrological processes are physically plausible are evaluated. In an assessment, the qualitative or quantitative descriptions of the inferred processes and that derived from domain-specific knowledge are used in the comparison. For

290 instance, a small urban catchment is modeled and is expected to have a fast response to rainfall. If the inferred hydrological processes correspond to a catchment with a long-term memory effect, then the associated ML model can be considered unreliable. Generally, three possible outcomes are expected in such an assessment.

1. *Consistent*. These are cases when the inferred hydrological processes are physically plausible according to the domain-specific knowledge of the system being modeled. The term “consistent” is used, rather than “correct” or “valid”, is to reflect
295 that the assessment process involves a comparison to some basis derived from our knowledge of the system being modeled, which might be subjective and incomplete. The term is used following Yang and Chui (2021).

2. *Inconsistent*. These are cases when the inferred hydrological processes are physically implausible according to the domain-specific knowledge of the system being modeled.

3. *Insufficient evidence to draw conclusions*. These are cases when the requirements for the inferred processes to be
300 considered consistent are too specific or too general such that definitive conclusions cannot be drawn. For example, assume that the inferred hydrological processes indicate that the catchment has a small surface area (i.e., a qualitative description), and the time of concentration of the catchment being modeled is known from previous studies and is used as the assessment criterion (i.e., a quantitative description). In this context, it is impossible to determine the consistency between the two descriptions unless more evidence regarding the conversion between catchment scale and time of concentration is collected.
305 The inability to draw a definitive conclusion can also be caused by the lack of knowledge of the processes being modeled. For instance, it is difficult to identify the expected hydrological behaviors for ungauged natural catchments.

Figure 3c shows a few examples of the inferred hydrological processes and the patterns of processes that are derived from hydrological knowledge.

2.3 Case studies

310 2.3.1 Study sites

Two SuDS sites with different drainage areas, SuDS practice types, and data availabilities are examined in this study. Study site 1 is located on Washington Street, Geauga County, Ohio, U.S., hereafter referred to as “WS.” Multiple types of SuDS were built in WS to treat stormwater runoff generated by a nearby commercial building and parking lot, as shown in Figure 4a (Darner et al., 2015). Runoff from approximately half of the commercial building roof (i.e., an impervious area of 316 m²)
315 drains into a rain garden with a surface area of 37 m². The 762 m² parking lot was constructed using porous pavements to allow infiltration.




Figure 4 (a) Layout of the SuDS and monitoring network on the Washington Street site (WS), Geauga County, Ohio, U.S. This figure is adapted from Darner et al. (2015). (b) Map of the Shayler Crossing Watershed (SHC). The subcatchment boundaries and drainage system shown on the map are defined by Lee et al. (2018a).

320

Study site 2 is the Shayler Crossing Watershed (SHC) in Clermont County, Ohio, U.S., as shown in Figure 4b. SHC is a sub-watershed of the East Fork Little Miami River Watershed. The drainage area of SHC is approximately 0.92 km² (Hoghooghi et al., 2018) and the land use type is primarily residential. The drainage system of SHC consists of conduits, channels, detention ponds, dry ponds, and wet ponds (Lee et al., 2018a). In SHC, stormwater runoff indirectly generated by connected impervious areas (e.g., sidewalks) is treated by the nearby pervious areas, which are termed buffering pervious areas and have similar functions to grass filter strips (Lee et al., 2018b). SHC represents a typical residential area in the U.S. and is thus selected to test the applicability of the proposed ML methods in modeling small urban catchments.

325

In WS, a 10-min-resolution rainfall-discharge time series is available from on-site monitoring between 2009 and 2013. The outflow from WS was collected and measured by three flumes. Flumes 1, 2, and 3 respectively collect the surface runoffs from the parking lot, overflow from the surface layer of the rain garden, and underdrain flows from the parking lot. The onsite monitoring was conducted by the United States Geological Survey (USGS), and more details of the monitoring work can be found in Darner and Dumouchelle (2011) and Darner et al. (2015). In SHC, 10-min-resolution rainfall time series from 2009–2010 is available, in addition to a 10-min-resolution discharge time series measured at the outlet between July and August 2009 by the U.S. Environmental Protection Agency. The dataset used in this study is the same as in Lee et al. (2018a) and Lee et al. (2018b), in which more details on the dataset can be found.

335

It can be challenging to set up process-based models for both sites. In WS, the physical properties and exact design of the different drainage system elements are not precisely known (Darner et al., 2015). For instance, the rain garden is not isolated from the gravel storage layer of the porous pavements, however, the exact flow conditions in the storage layer are unknown. In SHC, the main challenge lies in the heavy workload and uncertainties in estimating the model parameters that characterize the complex drainage system. For example, to accurately represent the drainage processes, SHC should be divided into multiple subcatchments connected by the drainage network, and each subcatchment should be further subdivided into multiple subareas, such as directly and indirectly connected impervious subareas (Lee et al., 2018a). The task of the sub-area division, however, requires substantial effort, considering the relatively large number of subcatchments involved.

2.3.2 Numerical experiments

Rainfall-runoff models are built for both SHC and WS using ML methods. In WS, the output variable is the flow rate of the total runoff collected by the three flumes recorded at regular 10-min intervals during the warm season (i.e., April to October) (Darner et al., 2015). The input variables include the 10-min-resolution rainfall time series recorded prior to runoff, the month in which the runoff occurs (optional), and the accumulative rainfall depth recorded since the beginning of monitoring (optional). The optional features are considered to account for the possible evolving performance of the SuDS during its service life (Yong et al., 2013) and the potential seasonality of the SuDS hydrological properties (Muthanna et al., 2008). Whether the two sets of optional features should be included is controlled by the two binary feature engineering hyperparameters, in addition to m , l , and n . The ranges of the hyperparameter values are listed in Table 1, and their optimal values are determined using the Bayesian optimization methods. The rainfall-discharge data collected between 2010 and 2013 by USGS are used in this study. A total of 142 independent rainfall events are identified using a 24-h dry spell threshold (Guo and Senior, 2006). A nested cross-validation (CV) resampling procedure is implemented, in which 5-fold CV is used for both the inner and outer CV iterations. The folds are created using a rainfall event-grouped stratified sampling method (Zeng and Martinez, 2000), i.e., data associated with the same rainfall event are grouped into the same fold, and the peak discharge of the rainfall events in each fold roughly follows the same distribution. This is to prevent data leakage and ensure that the data in each fold are representative (Kuhn and Johnson, 2013). In general, each outer CV iteration can be considered as an experiment to assess the effectiveness of an ML method using a specific split of the dataset, and its associated inner CV iterations are considered as procedures to derive the model to be evaluated on the test dataset.

Table 1 Hyperparameter values considered for the two study sites.

	Study site #1 WS	Study site #2 SHC
Candidate feature engineering hyperparameter values	m is a random integer between 144 and 1440, l is a random integer between 1 and 36, and n is a random integer between 2 and 36. The inclusion or exclusion of the accumulative rainfall depth and the	m , l , and n are integers and their ranges are the same as that for study site #1.

occurring month of the runoff event is controlled by two binary variables.

Candidate XGBoost hyperparameter values	<i>eta</i> is a real number between 0.005 and 0.1, <i>max_depth</i> is an integer between 2 and 10, <i>min_child_weight</i> is an integer between 1 and 10, <i>subsample</i> is a real number between 0.20 and 1, <i>colsample_bytree</i> is a real number between 0.2 and 1, <i>gamma</i> is a real number between 0 and 10, the maximum value of <i>nround</i> is 5000, and the optimal <i>nround</i> is determined using an early stopping criterion that the training stops if there is no improvement in validation accuracy for 20 consecutive rounds.	Same as study site #1.
---	--	------------------------

In SHC, the output variable is the watershed outlet discharge measured at 10-min intervals, and the input variable is the rainfall time series proceeding the discharge measurement. Only two months of runoff data are available. The nested CV procedure is not used due to the small dataset size; instead, the dataset is split into training, validation, and test datasets that each contains at least one large runoff event. The Bayesian optimization methods are then used to identify the optimal hyperparameters (as shown in Table 1) that minimize prediction error on the validation dataset when the model is trained on the training dataset. The training and validation datasets are then combined and the ML methods with the optimal hyperparameters are applied. The resulting models are then tested on the test dataset.

For each site, the resampling and hyperparameter optimization methods are also applied to train linear regression models, which are used as a baseline for evaluating XGBoost models. The only difference in the training processes between the two model types is that only the feature engineering hyperparameters are used when fitting linear regression models to the data. For SHC, the process-based model developed by Lee et al. (2018a) is also compared with the ML models built in this study. Their model is built using SWMM software, in which SHC is divided into 191 subcatchments and the drainage processes in each subcatchment are characterized using various parameters. The prediction accuracies of different types of models are then compared for each site.

The proposed method is then applied to explain the basis of each prediction for the two sites, i.e., for each discharge prediction, the contribution of rainfall of each time step (i.e., $\tau_k(\mathbf{x}_t)$) is computed. Both the observational and interventional SHAP values are used in the derivation, which results in two versions of the $\tau_k(\mathbf{x}_t)$ values. The following experiments on inferring the involved hydrological processes are conducted based on the $\tau_k(\mathbf{x}_t)$ values.

1. The predicted hydrographs are decomposed into multiple hydrographs associated with the rainfalls recorded between the past 0–1 h, 1–2 h, and so on using Equation 12. Whether the hydrograph decomposition method can generate physically plausible results is examined by a few simple hydrological principles, which include (a) rainfalls have


- 385 positive contributions to runoffs and (b) runoffs in small catchments are mostly contributed by rainfalls that occurred
in the recent past.
2. The overall importance of rainfall of each time step to discharge prediction (Equation 11) is computed for each site
using all the samples. These importance scores are then used to infer the hydrological processes of the system being
modeled. The physical realism of the inferred processes is evaluated using principles derived from hydrological
390 knowledge of the system being modeled, which includes (a) smaller catchments commonly have faster responses to
rainfalls compared to larger catchments and (b) the importance scores of rainfalls change smoothly across time steps.
Principle (b) is derived from hydrological knowledge that rainfalls of similar magnitudes in adjacent time steps are
expected to have similar impacts on the runoff generation processes.
3. This experiment aims to investigate whether different ML explanation methods lead to similar inferred hydrological
395 processes. The gain, cover, and frequency metrics are computed for each XGBoost model of WS. These scores are then
distributed among rainfall of each time step proportionally to its associated rainfall depth of all the samples, and the
resulting quantities are compared to importance scores derived in experiment #2, in which the SHAP methods are used
during the computation. The SHAP-related importance scores are normalized such that the resulting scores associated
with all predictors sum to 1.
- 400 4. This experiment aims to investigate whether more accurate models are likely to provide more physically plausible
explanations to the physical processes being modeled. The XGBoost models trained using 10%, 20%, 40%, and 60%
of the observed samples of WS are evaluated in terms of prediction accuracy and their ability to provide consistent
explanations to the modeled processes. The models' optimal hyperparameters are estimated using a resampling method
(i.e., a further training-validation split) and Bayesian optimization methods. The test dataset used in prediction accuracy
405 estimation is the remaining 40% of the samples that are not used in training. For each sample size, 10 versions of the
training sets are created; and for each version of the dataset, 10 models are trained by repeatedly applying the resampling
and Bayesian methods (which are both stochastic). That is, 100 models are created for each sample size. The importance
of rainfall of each time step is then derived following the methods in experiment #2, which is then used to infer the
hydrological processes being modeled. The consistency of the inferred processes is then evaluated based on whether
410 the importance scores of rainfalls change smoothly across time steps using the test dataset.

3 Results and discussion

3.1 Prediction accuracy of machine learning models

The prediction accuracies of the various WS and SHC models are compared in Figure 5. The root-mean-square error (RMSE),
coefficient of determination (R^2), and Nash-Sutcliffe coefficient of efficiency (NSE; Nash and Sutcliffe, 1970) of the
415 predictions on the test datasets are compared, except for the SWMM model developed by Lee et al. (2018a), which was tested
on a part of its training dataset due to insufficient data. The prediction accuracies of the XGBoost models, i.e., $NSE > 0.7$ and

$R^2 > 0.7$, can be considered satisfactory, considering that they were relatively easy to set up and that it was impossible or very difficult to build process-based models for either site. The XGBoost models for both sites consistently outperform the linear regression (LM) models, suggesting that more sophisticated ML algorithms such as XGBoost are able to better capture complex rainfall-runoff correlations than simple LM methods. The SHC XGBoost models have comparable prediction accuracies to SWMM, although the former were built with considerably less efforts. Thus, in future SuDS studies, it can be useful to quickly train some ML models based on available data and used them as a reference to evaluate the prediction accuracies of process-based models. The proposed ML model training methods can be potentially extended to study other small scale urban catchments that have similar configurations to SHC.



425


Figure 5 Prediction accuracies of the various models built for the Washington Street SuDS site (WS) and Shayler Crossing Watershed (SHC). The prediction accuracies are evaluated in terms of the root-mean-square error (RMSE), coefficient of determination (R^2), and Nash-Sutcliffe coefficient of efficiency (NSE). The RMSE units are L/s for WS and m^3/s for SHC. Each data point in the figure shows the prediction accuracy evaluated using a specific split of the dataset. The prediction accuracies derived using the same test dataset are connected by lines. The SWMM model for SHC was built by Lee et al. (2018a).

430

Each data point in Figure 5 shows the results obtained for a specific split of a dataset (i.e., the division of data into training, validation, and test datasets), and the points that correspond to the same split are connected by lines. The prediction accuracies of XGBoost and LM models varied considerably for different splits of a dataset. The variations indicate that the sample distributions in the different versions of training and test datasets appreciably differ, even though a stratified sampling method is used to balance the sample distribution in the different folds. The imbalanced sample distribution is associated with the limited number of samples used for the model training and evaluation, which implies that the four years of rainfall-runoff data still contained an insufficient number of samples for the ML methods examined in this study. For instance, only a few high-flow events were observed each year in WS, which may be insufficient for the training ML models to provide accurate high-flow predictions. Even fewer samples were available for training and testing the SHC models; thus, the uncertainties of the prediction accuracies may be even larger.

3.2 Physical realism of the decomposed hydrographs

The results obtained for numerical experiment #1 are presented in this section. As an example, Figure 6 shows the predicted decomposed hydrographs of WS associated with rainfall of each hour for a large, medium, and small runoff event. As shown in Figure 6, runoff is mostly contributed by the rainfall that occurred within the past 1 h regardless of the runoff event magnitude, especially for the peak discharge. These patterns are generally expected from small catchments, where runoffs are mostly contributed by recent rainfalls. As WS is a small-scale catchment, the inferred fast runoff responses are consistent with our hydrological knowledge.



450 **Figure 6 (a) Rainfall time series and (b) decomposed hydrographs of a large, medium, and small runoff event from the Washington Street SuDS site (WS). The model used to derive the hydrographs was obtained in the outer cross-validation iteration 1. Observational SHAP values were used in the computation.**

Although it is not exactly clear how to quantitatively assess the physical realism of the contribution values assigned to rainfall of each hour, they express some patterns that are obviously inconsistent with our hydrological knowledge. First, Figure 6 shows that rainfalls can have negative contributions to runoffs, which are physically impossible. Second, there is a constant bias term in the decomposed hydrographs that are independent of the rainfalls. This term is the average prediction for all samples and accounts for the differences between the predicted values and the contributions assigned to all variables in the SHAP method. However, this constant term does not clearly correspond to any processes in hydrology. Additionally, a model might use features that are not derived from rainfall (e.g., the age of the SuDS practice) as a predictor, which will also be assigned with contributions to runoffs when the SHAP method is used to examine the basis of predictions. However, it is unclear how to use these contributions in hydrograph decomposition.

460

The results of this experiment show that the inferred hydrological processes can be only partially consistent with the knowledge of the system being modeled. Some ML explanation methods, such as SHAP, can generate explanations that are inherently inconsistent with hydrological principles, such as the rainfalls' negative contributions to runoffs and the constant

contributions to runoffs that are not associated with any variable. Nevertheless, it would be meaningful to compare the decomposed hydrographs to those derived using approaches in process-based modeling and tracer and isotope hydrology to further evaluate the validity of the explanations derived using ML methods.

3.3 Physical realism of the importance of rainfalls of different time steps to discharge prediction

The results of numerical experiment #2 are shown in Figure 7. In both WS and SHC, rainfalls recorded prior to 100 time steps in the past (i.e., 16.7 h) have almost no impact on discharge prediction, which is reasonable considering their small catchment sizes. The rainfalls that occurred in 1 and 5 time steps (i.e., 10 and 50 min) in the past are found to have the highest impact on discharge prediction for WS and SHC. This pattern is expected as SHC is considerably (which is around 800 times) larger than WS, and thereby the time required for stormwater to travel through the catchment is also longer in SHC. Although the exact response time of both catchments is unknown, it is possible to use the knowledge regarding the relations between the response time of the two catchments to conduct an assessment. Utilizing relational patterns in assessing the consistency of multiple entities has been demonstrated in Yang and Chui (2021).




Figure 7 Average importance of the rainfalls at different time steps in the past for discharge predictions in the XGBoost models of the Washington Street SuDS site (WS) and the Shayler Crossing Watershed (SHC). Each line corresponds to an XGBoost model trained on a specific training dataset. Each time step is 10 min. The x-axis is on a pseudo-logarithmic scale. Observational SHAP values were used in the computation.


It is also worth noting that the importance scores assigned to rainfalls fluctuate across time steps for SHC, which indicates that the models find rainfalls in some specific time steps are more important for discharge prediction when compared to the others, which is inconsistent with our hydrological knowledge. In WS, these inconsistent patterns are not observed, where the importance scores of rainfalls change monotonically from the past 1 time step to the current time step and the time steps in the

485 more distant past. The inconsistent patterns might be caused by the insufficient data used in the model training, which is discussed further in Section 3.5.

In WS, the rainfall of a specific time step can be assigned with notably different importance scores when the models trained using different training datasets are used, which is an indication of considerably different model structures. The structural differences in ML models are also reported in Schmidt et al. (2020), where the existence of multiple possible model structures is referred to as equifinality (Beven and Freer, 2001). The different importance scores will naturally result in different explanations of the processes being modeled, and apparently, these explanations cannot be simultaneously close to reality (Bouaziz et al., 2021). However, in this case, it is not possible to quantitatively assess the explanations provided by different models due to the lack of knowledge. Experiment #4 investigate whether models with higher prediction accuracies can generate more trustworthy explanations to the process being modeled, and the results are presented in Section 3.5.

495 **3.4 Comparison of multiple machine learning explanation methods**

The results of experiment #3 are shown in Figure 9, where various feature importance scores of rainfalls of different time steps are compared. All importance scores derived using different methods suggest that the rainfalls of more recent time steps have a higher impact on discharge prediction. However, different methods can derive considerably different importance scores for the rainfall of a specific time step, and the relations between the importance scores assigned to the rainfalls of different time steps also vary among different methods. Some methods, such as interventional SHAP and frequency, are more sensitive to model structural differences than the others. The differences in various importance scores indicate that the selection of the explanation method is another source of uncertainty in inferring the processes being modeled.



505 **Figure 8** The importance of rainfall from each time step for making discharge predictions assessed by different feature importance measures in the Washington Street SuDS site (WS) models. Each line shows the results of model trained during an outer cross-validation (CV) iteration. The x -axis is on a pseudo-logarithmic scale. For interventional SHAP, all the training samples are used as background dataset.

The importance scores derived from the observational and interventional SHAP values varied significantly due to different computation methods for computing the expected prediction, i.e., Equations 7 to 8. It is, however, currently unclear how to
 510 evaluate an explanation method's effectiveness in inferring the processes being modeled. Nevertheless, it is recommended that future study to always report the configurations of the explanation methods being used and evaluate the uncertainties associated with explanation method selection.

3.5 Correlation between the physical realism of inferred processes and model prediction accuracy

The results of experiment #4 are discussed in this section. As shown in Figure 9, the models' prediction accuracy, as measured
 515 by NSE, generally increases as more samples are used to train the model, despite its large uncertainties associated with the random sampling of the dataset. However, the number of models that correspond to consistent explanations (i.e., the single-peaked patterns of rainfall importance scores), also shown by the numbers in Figure 9, did not increase as more samples are used in training. In fact, consistent results are rarely observed for all training sample sizes. These results suggest that more accurate models do not necessarily offer more physically realistic explanations to the processes being modeled and using more
 520 data samples in model training does not guarantee more physically realistic explanations. For the models trained with the same amount of data, selecting a more accurate model does not guarantee the inferences made based on the selected model are more consistent with our knowledge. However, it is also possible that our knowledge used in the assessment is biased, as the test

dataset may not represent the true data distribution that would be observed on an infinite time scale. Nevertheless, the lack of correlation between a model's ability to provide accurate predictions and exhibit physically plausible behavioral patterns when model input changes has also been reported in Yang and Chui (2021).



530 **Figure 9** Boxplot of the prediction accuracy of the Washington Street SuDS site (WS) models when different sizes of samples are used in model training. For each sample size, the models that offer consistent and inconsistent explanations are grouped together, and the numbers of consistent and inconsistent models (the n values) are shown. Observational SHAP values were used in the computation. The points show the NSE of each model and their horizontal positions are randomly set to avoid overlapping.

Ilyas et al. (2019) argued that ML models can make predictions based on features that humans cannot comprehend. The implication of this argument is that ML models can make right predictions for the “wrong” reasons (Ross et al., 2017) or reasons that are inconsistent with our knowledge, and therefore the prediction accuracy of a model is not a trustworthy measurement of the physical realism of the explanations it provides. Regularizing ML models using physical principles, as suggested in Nearing et al. (2021), can potentially increase the physical realism of the explanations and the inferred physical processes.

3.6 Inferring hydrological processes using machine learning methods and analyzing ingredients of cake samples

This section uses a metaphor to explain the processes of inferring hydrological processes using ML methods, as shown in Figure 10. An ML model is similar to a cake (baked by others) in that they both are consumed by humans, and the exact mechanisms that generate the outcomes (i.e., the predictions or the tastes) are often unknown due to complexity. Here, the mechanisms refer to the numerical operations that generate the predictions or the ingredients and procedures that give the flavor. Normally, the predictions or the tastes are of main interest. However, it can be useful to inspect the mechanisms that lead to the outcomes such that more confidence regarding future outcomes can be gained, where future outcomes refer to the

predictions under new conditions or more cakes acquired through similar means. ML explanation methods and chemical
 545 composition analysis methods can provide information regarding the elements that contribute to the prediction or flavor.
 However, in many cases, such information can only be treated as circumstantial evidence of certain physical principles being
 learned by a model or the presence of certain ingredients. This is because ML models usually do not have structures that
 directly resemble the physical processes and the chemical composition analysis usually does not directly test the presence of
 a food ingredient. The raw information is then further processed by referring to domain-specific knowledge, such as
 550 hydrological knowledge or nutritional facts of foods. For instance, a high degree of association between the predicted discharge
 and recent rainfall is an indication of a catchment's fast runoff response, which is commonly seen in small urban catchments,
 and a high carotene content may indicate that carrots are used in the cake. The inferred physical processes or ingredients and
 procedures are then evaluated against that would be expected based on domain-specific knowledge of the system being
 modeled or baking a specific type of cakes. Finally, whether the ML model learns the expected physical processes or whether
 555 the cake is baked following the expected recipe is evaluated.

(a) Testing whether a cake is made following the recipe



(b) Testing whether a model learns the physical processes




Figure 10 Illustration of the processes of (a) testing whether a cake is made following the desired recipe and (b) testing whether a model captures the physical processes of the system being modeled.

It is important to note that uncertainties are presented in every step of the assessment. First, different ML explanation
 560 methods or chemical composition analysis methods can lead to significantly different outcomes, which are used as the basis
 for inference. An example is provided in Section 3.4. Second, the inference process can be biased and subjective due to our
 incomplete knowledge. For example, a chemical component could correspond to an ingredient that we do not know, and a
 rainfall's negative contribution to runoff could be caused by an unknown stormwater harvesting activity in the catchment. Bias

and subjectivity, however, cannot be avoided in an open system, as there may be infinitely many physically plausible explanations to the same outcome (Oreskes et al., 1994). Third, the knowledge applied in the final assessment processes to define assessment criteria can be incomplete.

Are the practices of inferring the physical processes using ML methods of any good? This study considers the consistency evaluation results of the inferences as circumstantial evidence to support a model's trustworthiness. Although an ML model does not have to learn the physical principles to make good predictions, we might prefer the desired principles are captured by the models. This is similar to suggest that we prefer delicious cakes are made with ingredients we considered safe. Models that are associated with inferences that are consistent with our knowledge may be proven more reliable under new circumstances, such as extreme event prediction and prediction under data distribution drifts (Lu et al., 2019). More research on testing ML models' reliability is recommended.

It is also important to note that the inferred processes should be interpreted cautiously due to the large uncertainties involved in every step of the assessment. The detailed configurations of the entire inference process should be reported when presenting the inferred processes. In particular, large uncertainty resides in the process of making inferences according to the raw explanations derived from ML explanation methods, as many plausible physical processes can give rise to the same raw explanations. It is therefore important to consider a larger search space for drawing inferences, which may be considered as an attempt to mitigate the streetlight effect, i.e., limiting the search space to be only under a streetlight in the dark or a specific set of plausible explanations (Demirdjian et al., 2005).

4 Conclusions

The following conclusions can be drawn.

1. This study shows that ML methods can be useful for modeling the hydrological responses of SuDS catchments at sub-hourly time scales. In this study, models with high prediction accuracies ($NSE > 0.7$) are obtained for two SuDS catchments of different sizes, SuDS practice types, and data availabilities. ML models can be set up relatively easily provided that observation data of the variables of interest are available and thus are recommended to be used as a reference to evaluate process-based models.
2. The physical process being modeled can be inferred based on the results of ML explanation methods. However, the inferred processes might be inconsistent with the patterns that would be expected based on domain-specific knowledge of the system being modeled. An ML model's ability to provide accurate predictions can be uncorrelated with its ability to offer plausible explanations to the physical processes being modeled.
3. This study provides a high-level overview of the processes of inferring the physical processes being modeled using ML explanation methods. It shows that large uncertainties are presented in the processes of explaining model structures using ML explanation methods, making inferences according to the raw explanations, and assessing the physical realism of the inferred physical processes. The inferred hydrological processes normally should only be

considered as circumstantial evidence to support a model's trustworthiness due to their indirect connection to the raw explanations. Due to the existence of the large uncertainties in the inference processes, the inferred physical processes should be interpreted cautiously, and more physically plausible explanations that correspond to the same raw explanations can be potentially investigated.

600 **Code availability**

The source code used in this study, the optimal hyperparameters, and the optimal hyperparameters are available at https://github.com/stsfk/ExplainableML_SuDS. The following R packages are used for modeling and analysis in this research: xgboost (Chen and He, 2020), tidymodels (Kuhn and Wickham, 2020), lubridate (Grolemund and Wickham, 2011), RcppRoll (Ushey, 2018), zeallot (Teetor, 2018), mlrMBO (Bischl et al., 2017), and hydroGOF (Zambrano-Bigiarini, 2020). The
605 following Python packages are used: shap (Lundberg and Lee, 2017), NumPy (Harris et al., 2020), and xgboost (Chen and Guestrin, 2016). All the R and Python packages used in this research are freely available online.

Data availability

The data of the two study sites examined in this study is obtained from the United States Geological Survey (USGS), Clermont County, Ohio, U.S., and the United States Environmental Protection Agency (US EPA). The identification numbers of the
610 USGS monitoring sites for the Washington Street SuDS site (WS) are 412533081221500, 412535081221400, and 412535081221402. The data of the Shayler Crossing Watershed can be downloaded at <https://doi.org/10.23719/1378947>. The SWMM model used in this research is developed in Lee et al. (2018a).

Author contribution

YY designed the study, acquired the data, wrote the code, conducted the numerical experiment, analyzed the results, and
615 prepared the manuscript. TFMC contributed to the design of numerical experiments, supervised the study, validated the results, and revised the manuscript.

Competing interests

The authors declare that they have no conflict of interest.

Acknowledgments

620 The work described in this paper was partly supported by a grant from the Research Grants Council of the Hong Kong Special Administrative Region, China (Project No. HKU17255516), and partly supported by the RGC Theme-based Research Scheme (Grant No: T21-711/16-R) funded by the Research Grants Council of the Hong Kong Special Administrative Region, China. We thank Robert Darner from USGS, Christ Nietch from USEPA, Joong Gwang Lee from Center for Urban Green Infrastructure Engineering, and Bill Mellman from Clermont County Water Resources for providing data for this research. We
625 thank the comments from Omar Wani and Hoshin Gupta on evaluating the physical realism of machine learning models in hydrological studies. We also would like to thank Georgia Papacharalampous and the other two anonymous reviewers for providing insightful feedback that greatly improved the quality of this paper. Finally, we wish to thank the editor Roberto Greco for handling and assessing our paper during the review processes.

References

- 630 Ahmad, M. A., Teredesai, A. and Eckert, C.: Interpretable machine learning in healthcare, in Proceedings - 2018 IEEE International Conference on Healthcare Informatics, ICHI 2018, p. 447., 2018.
- Barredo Arrieta, A., Díaz-Rodríguez, N., Del Ser, J., Bennetot, A., Tabik, S., Barbado, A., Garcia, S., Gil-Lopez, S., Molina, D., Benjamins, R., Chatila, R. and Herrera, F.: Explainable Artificial Intelligence (XAI): Concepts, taxonomies, opportunities and challenges toward responsible AI, *Inf. Fusion*, 58, 82–115, doi:10.1016/J.INFFUS.2019.12.012, 2020.
- 635 Beven, K. and Freer, J.: Equifinality, data assimilation, and uncertainty estimation in mechanistic modelling of complex environmental systems using the GLUE methodology, *J. Hydrol.*, 249(1–4), 11–29, doi:10.1016/S0022-1694(01)00421-8, 2001.
- Bischl, B., Richter, J., Bossek, J., Horn, D., Thomas, J. and Lang, M.: mlrMBO: A Modular Framework for Model-Based Optimization of Expensive Black-Box Functions, [online] Available from: <https://arxiv.org/abs/1703.03373v3> (Accessed 4
640 September 2021), 2017.
- Bojanowski, P., Joulin, A., Paz, D. L. and Szlam, A.: Optimizing the latent space of generative networks, in 35th International Conference on Machine Learning, ICML 2018, vol. 2, pp. 960–972., 2018.
- Bouaziz, L. J. E., Fencica, F., Thirel, G., De Boer-Euser, T., Buitink, J., Brauer, C. C., De Niel, J., Dewals, B. J., Drogue, G., Grelier, B., Melsen, L. A., Moustakas, S., Nossent, J., Pereira, F., Sprokkereef, E., Stam, J., Weerts, A. H., Willems, P.,
645 Savenije, H. H. G. and Hrachowitz, M.: Behind the scenes of streamflow model performance, *Hydrol. Earth Syst. Sci.*, 25(2), 1069–1095, doi:10.5194/hess-25-1069-2021, 2021.
- Charlesworth, S. M.: A review of the adaptation and mitigation of global climate change using sustainable drainage in cities, *J. Water Clim. Chang.*, 1(3), 165–180, doi:10.2166/wcc.2010.035, 2010.
- Chen, H., Janizek, J. D., Lundberg, S. and Lee, S. I.: True to the model or true to the data?, arXiv [online] Available from:
650 <http://arxiv.org/abs/1805.11783>, 2020.

- Chen, T. and Guestrin, C.: XGBoost: A scalable tree boosting system, in Proceedings of the ACM SIGKDD International Conference on Knowledge Discovery and Data Mining, vol. 13-17-Augu, pp. 785–794., 2016.
- Chen, T. and He, T.: xgboost: eXtreme Gradient Boosting, [online] Available from: <https://cran.r-project.org/web/packages/xgboost/vignettes/xgboost.pdf> (Accessed 29 June 2020), 2020.
- 655 Damodaram, C., Giacomoni, M. H., Prakash Khedun, C., Holmes, H., Ryan, A., Saour, W. and Zechman, E. M.: Simulation of combined best management practices and low impact development for sustainable stormwater management, *J. Am. Water Resour. Assoc.*, 46(5), 907–918, doi:10.1111/j.1752-1688.2010.00462.x, 2010.
- Darner, R. A. and Dumouchelle, D. H.: Hydraulic Characteristics of Low-Impact Development Practices in Northeastern Ohio, 2008-2010: U.S. Geological Survey Scientific Investigations Report 2011–5165. [online] Available from: <https://pubs.usgs.gov/sir/2011/5165/> (Accessed 7 July 2020), 2011.
- 660 Darner, R. A., Shuster, W. D. and Dumouchelle, D. H.: Hydrologic Characteristics of Low-Impact Stormwater Control Measures at Two Sites in Northeastern Ohio , 2008 – 13: U.S. Geological Survey Scientific Investigations Report 2015-5030., 2015.
- DeBusk, K. M., Hunt, W. F. and Line, D. E.: Bioretention Outflow: Does It Mimic Nonurban Watershed Shallow Interflow?, *J. Hydrol. Eng.*, 16(3), 274–279, doi:10.1061/(ASCE)HE.1943-5584.0000315, 2011.
- 665 Demirdjian, D., Taycher, L., Shakhnarovich, G., Grauman, K. and Darrell, T.: Avoiding the “streetlight effect”: Tracking by exploring likelihood modes, in Proceedings of the IEEE International Conference on Computer Vision, vol. I, pp. 357–364., 2005.
- Eckart, K., McPhee, Z. and Bolisetti, T.: Performance and implementation of low impact development – A review, *Sci. Total Environ.*, 607–608, 413–432, doi:10.1016/j.scitotenv.2017.06.254, 2017.
- 670 Elliott, A. H. and Trowsdale, S. A.: A review of models for low impact urban stormwater drainage, *Environ. Model. Softw.*, 22(3), 394–405, doi:10.1016/j.envsoft.2005.12.005, 2007.
- Eric, M., Li, J. and Joksimovic, D.: Performance Evaluation of Low Impact Development Practices Using Linear Regression, *Br. J. Environ. Clim. Chang.*, 5(2), 78–90, doi:10.9734/bjecc/2015/11578, 2015.
- 675 Fassman-Beck, E., Hunt, W., Berghage, R., Carpenter, D., Kurtz, T., Stovin, V. and Wadzuk, B.: Curve number and runoff coefficients for extensive living roofs, *J. Hydrol. Eng.*, 21(3), 04015073, doi:10.1061/(ASCE)HE.1943-5584.0001318, 2016.
- Fletcher, T. D., Shuster, W., Hunt, W. F., Ashley, R., Butler, D., Arthur, S., Trowsdale, S., Barraud, S., Semadeni-Davies, A., Bertrand-Krajewski, J. L., Mikkelsen, P. S., Rivard, G., Uhl, M., Dagenais, D. and Viklander, M.: SUDS, LID, BMPs, WSUD and more – The evolution and application of terminology surrounding urban drainage, *Urban Water J.*, 12(7), 525–542, doi:10.1080/1573062X.2014.916314, 2015.
- 680 Frazier, P. I.: A tutorial on bayesian optimization, arXiv [online] Available from: <http://arxiv.org/abs/1807.02811> (Accessed 6 October 2020), 2018.
- Friedman, J. H.: Greedy function approximation: A gradient boosting machine, *Ann. Stat.*, 29(5), 1189–1232, doi:10.1214/aos/1013203451, 2001.

- 685 Gimenez-Maranges, M., Breuste, J. and Hof, A.: Sustainable Drainage Systems for transitioning to sustainable urban flood management in the European Union: A review, *J. Clean. Prod.*, 255, 120191, doi:10.1016/j.jclepro.2020.120191, 2020.
- Grolemund, G. and Wickham, H.: Dates and Times Made Easy with lubridate. *Journal of Statistical Software*, 40(3), 1-25, <https://www.jstatsoft.org/v40/i03/>, 2011.
- Guidotti, R., Monreale, A., Ruggieri, S., Turini, F., Giannotti, F. and Pedreschi, D.: A Survey of Methods for Explaining Black
690 Box Models, *ACM Comput. Surv.*, 51(5), 1–42, doi:10.1145/3236009, 2019.
- Guo, Y. and Senior, M. J.: Climate model simulation of point rainfall frequency characteristics, *J. Hydrol. Eng.*, 11(6), 547–554, doi:10.1061/(ASCE)1084-0699(2006)11:6(547), 2006.
- Harris, C. R., Millman, K. J., van der Walt, S. J., Gommers, R., Virtanen, P., Cournapeau, D., Wieser, E., Taylor, J., Berg, S., Smith, N. J., Kern, R., Picus, M., Hoyer, S., van Kerkwijk, M. H., Brett, M., Haldane, A., del Río, J. F., Wiebe, M., Peterson,
695 P., Gérard-Marchant, P., Sheppard, K., Reddy, T., Weckesser, W., Abbasi, H., Gohlke, C. and Oliphant, T. E.: Array programming with NumPy, *Nature*, 585(7825), 357–362, doi:10.1038/s41586-020-2649-2, 2020.
- Hastie, T., Tibshirani, R. and Friedman, J.: *The Elements of Statistical Learning*, Springer New York, New York, NY., 2009.
- Hoghooghi, N., Golden, H. E., Bledsoe, B. P., Barnhart, B. L., Brookes, A. F., Djang, K. S., Halama, J. J., McKane, R. B., Nietch, C. T. and Pettus, P. P.: Cumulative effects of Low Impact Development on watershed hydrology in a mixed land-cover
700 system, *Water (Switzerland)*, 10(8), 991, doi:10.3390/w10080991, 2018.
- Hopkins, K. G., Bhaskar, A. S., Woznicki, S. A. and Fanelli, R. M.: Changes in event-based streamflow magnitude and timing after suburban development with infiltration-based stormwater management, *Hydrol. Process.*, 34(2), 387–403, doi:10.1002/hyp.13593, 2020.
- Ilyas, A., Santurkar, S., Tsipras, D., Engstrom, L., Tran, B. and Madry, A.: Adversarial examples are not bugs, they are features,
705 in *Advances in Neural Information Processing Systems*, vol. 32. [online] Available from: <http://git.io/adv-datasets>. (Accessed 28 June 2021), 2019.
- Janzing, D., Minorics, L. and Blöbaum, P.: Feature relevance quantification in explainable ai: A causal problem, *arXiv*, 2019.
- Johannessen, B. G., Hanslin, H. M. and Muthanna, T. M.: Green roof performance potential in cold and wet regions, *Ecol. Eng.*, 106, 436–447, doi:10.1016/j.ecoleng.2017.06.011, 2017.
- 710 Jones, P. and Macdonald, N.: Making space for unruly water: Sustainable drainage systems and the disciplining of surface runoff, *Geoforum*, 38(3), 534–544, doi:10.1016/j.geoforum.2006.10.005, 2007.
- Khan, U. T., Valeo, C., Chu, A. and He, J.: A data driven approach to bioretention cell performance: Prediction and design, *Water (Switzerland)*, 5(1), 13–28, doi:10.3390/w5010013, 2013.
- Kirchner, J. W.: Getting the right answers for the right reasons: Linking measurements, analyses, and models to advance the
715 science of hydrology, *Water Resour. Res.*, 42(3), doi:10.1029/2005WR004362, 2006.
- Kratzert, F., Herrnegger, M., Klotz, D., Hochreiter, S. and Klambauer, G.: NeuralHydrology – Interpreting LSTMs in Hydrology, in *Lecture Notes in Computer Science (including subseries Lecture Notes in Artificial Intelligence and Lecture Notes in Bioinformatics)*, vol. 11700 LNCS, pp. 347–362., 2019.

- Kuhn, M. and Johnson, K.: Applied predictive modeling., 2013.
- 720 Kuhn, M. and Johnson, K.: Feature Engineering and Selection : a Practical Approach for Predictive Models., Chapman and Hall/CRC. [online] Available from: <https://www.routledge.com/Feature-Engineering-and-Selection-A-Practical-Approach-for-Predictive-Models/Kuhn-Johnson/p/book/9781138079229> (Accessed 24 July 2020), 2019.
- Kuhn, M. and Wickham, H.: Tidymodels: a collection of packages for modeling and machine learning using tidyverse principles, <https://www.tidymodels.org>, 2020.
- 725 Lee, J. G., Nietch, C. T. and Panguluri, S.: Drainage area characterization for evaluating green infrastructure using the Storm Water Management Model, *Hydrol. Earth Syst. Sci.*, 22(5), 2615–2635, doi:10.5194/hess-22-2615-2018, 2018a.
- Lee, J. G., Nietch, C. T. and Panguluri, S.: SWMM Modeling Methods for Simulating Green Infrastructure at a Suburban Headwatershed: User’s Guide, U.S. Environ. Prot. Agency, (October), 157 [online] Available from: <https://nepis.epa.gov/Exe/ZyPDF.cgi/P100TJ39.PDF?Dockey=P100TJ39.PDF%0A> (Accessed 11 July 2020b), 2018.
- 730 Li, S., Kazemi, H. and Rockaway, T. D.: Performance assessment of stormwater GI practices using artificial neural networks, *Sci. Total Environ.*, 651, 2811–2819, doi:10.1016/j.scitotenv.2018.10.155, 2019.
- Liu, J., Sample, D., Bell, C. and Guan, Y.: Review and Research Needs of Bioretention Used for the Treatment of Urban Stormwater, *Water*, 6(4), 1069–1099, doi:10.3390/w6041069, 2014.
- Lu, J., Liu, A., Dong, F., Gu, F., Gama, J. and Zhang, G.: Learning under Concept Drift: A Review, *IEEE Trans. Knowl. Data Eng.*, 31(12), 2346–2363, doi:10.1109/TKDE.2018.2876857, 2019.
- 735 Lundberg, S. M. and Lee, S. I.: A unified approach to interpreting model predictions, in *Advances in Neural Information Processing Systems*, vol. 2017-Decem, pp. 4766–4775. [online] Available from: <https://github.com/slundberg/shap> (Accessed 30 June 2020), 2017.
- Lundberg, S. M., Erion, G., Chen, H., DeGrave, A., Prutkin, J. M., Nair, B., Katz, R., Himmelfarb, J., Bansal, N. and Lee, S.-
740 I.: From local explanations to global understanding with explainable AI for trees, *Nat. Mach. Intell.*, 2(1), 56–67, doi:10.1038/s42256-019-0138-9, 2020.
- Maier, H. R. and Dandy, G. C.: Neural networks for the prediction and forecasting of water resources variables: a review of modelling issues and applications, *Environ. Model. Softw.*, 15(1), 101–124, doi:10.1016/S1364-8152(99)00007-9, 2000.
- Mitchell, R. and Frank, E.: Accelerating the XGBoost algorithm using GPU computing, *PeerJ Comput. Sci.*, 2017(7), e127,
745 doi:10.7717/peerj-cs.127, 2017.
- Montalto, F., Behr, C., Alfredo, K., Wolf, M., Arye, M. and Walsh, M.: Rapid assessment of the cost-effectiveness of low impact development for CSO control, *Landsc. Urban Plan.*, 82(3), 117–131, doi:10.1016/j.landurbplan.2007.02.004, 2007.
- Morton, A.: Mathematical models: Questions of trustworthiness, *Br. J. Philos. Sci.*, 44(4), 659–674, doi:10.1093/bjps/44.4.659, 1993.
- 750 Muthanna, T. M., Viklander, M. and Thorolfsson, S. T.: Seasonal climatic effects on the hydrology of a rain garden, *Hydrol. Process.*, 22(11), 1640–1649, doi:10.1002/hyp.6732, 2008.
- Muthoo, A., Osborne, M. J. and Rubinstein, A.: A Course in Game Theory., *Economica*, 63(249), 164, doi:10.2307/2554642,

- 1996.
- Nash, J. E. and Sutcliffe, J. V.: River flow forecasting through conceptual models part I - A discussion of principles, *J. Hydrol.*, 755 10(3), 282–290, doi:10.1016/0022-1694(70)90255-6, 1970.
- Nearing, G. S., Kratzert, F., Sampson, A. K., Pelissier, C. S., Klotz, D., Frame, J. M., Prieto, C. and Gupta, H. V: What Role Does Hydrological Science Play in the Age of Machine Learning?, *Water Resour. Res.*, 57(3), doi:10.1029/2020WR028091, 2021.
- Niazi, M., Nietch, C., Maghrebi, M., Jackson, N., Bennett, B. R., Tryby, M. and Massoudieh, A.: Storm Water Management 760 Model: Performance Review and Gap Analysis, *J. Sustain. Water Built Environ.*, 3(2), 04017002, doi:10.1061/JSWBAY.0000817, 2017.
- Nielsen, A.: Practical Time Series Analysis, O'Reilly Media, Inc. [online] Available from: <https://www.oreilly.com/library/view/practical-time-series/9781492041641/> (Accessed 30 June 2020), 2019.
- Nielsen, D.: Tree Boosting With XGBoost: Why does XGBoost win every machine learning competition?, Master's Thesis, 765 Norwegian Univ. Sci. Technol., (December), 2016, doi:10.1111/j.1758-5899.2011.00096.x, 2016.
- Oreskes, N., Shrader-Frechette, K. and Belitz, K.: Verification, validation, and confirmation of numerical models in the earth sciences, *Science* (80-.), 263(5147), 641–646, doi:10.1126/science.263.5147.641, 1994.
- Pelletier, A. and Andréassian, V.: Hydrograph separation: An impartial parametrisation for an imperfect method, *Hydrol. Earth Syst. Sci.*, 24(3), 1171–1187, doi:10.5194/hess-24-1171-2020, 2020.
- 770 Rosa, D. J., Clausen, J. C. and Dietz, M. E.: Calibration and Verification of SWMM for Low Impact Development, *J. Am. Water Resour. Assoc.*, 1–12, doi:10.1111/jawr, 2015.
- Ross, A., Hughes, M. C. and Doshi-Velez, F.: Right for the Right Reasons: Training Differentiable Models by Constraining their Explanations, [online] Available from: <https://github.com/dtak/rrr>. (Accessed 2 September 2021), 2017.
- Rudin, C.: Stop explaining black box machine learning models for high stakes decisions and use interpretable models instead, 775 *Nat. Mach. Intell.*, 1(5), 206–215, doi:10.1038/s42256-019-0048-x, 2019.
- Schmidt, L., Heße, F., Attinger, S. and Kumar, R.: Challenges in Applying Machine Learning Models for Hydrological Inference: A Case Study for Flooding Events Across Germany, *Water Resour. Res.*, 56(5), doi:10.1029/2019WR025924, 2020.
- Selbig, W. R., Buer, N. and Danz, M. E.: Stormwater-quality performance of lined permeable pavement systems, *J. Environ. Manage.*, 251, doi:10.1016/j.jenvman.2019.109510, 2019.
- 780 Shahriari, B., Swersky, K., Wang, Z., Adams, R. P. and De Freitas, N.: Taking the human out of the loop: A review of Bayesian optimization, *Proc. IEEE*, 104(1), 148–175, doi:10.1109/JPROC.2015.2494218, 2016.
- Snoek, J., Larochelle, H. and Adams, R. P.: Practical Bayesian optimization of machine learning algorithms, in *Advances in Neural Information Processing Systems*, vol. 4, pp. 2951–2959. [online] Available from: <https://arxiv.org/abs/1206.2944v2> (Accessed 5 October 2020), 2012.
- 785 Shapley, L. S. A value of n-person games. *Contributions to the Theory of Games*, pp. 307–317, 1953.
- Solomatine, D. P. and Dulal, K. N.: Model trees as an alternative to neural networks in rainfall-runoff modelling, *Hydrol. Sci.*

- J., 48(3), 399–411, doi:10.1623/hysj.48.3.399.45291, 2003.
- Solomatine, D. P. and Ostfeld, A.: Data-driven modelling: Some past experiences and new approaches, in *Journal of Hydroinformatics*, vol. 10, pp. 3–22, IWA Publishing., 2008.
- 790 Starn, J. J., Kauffman, L. J., Carlson, C. S., Reddy, J. E. and Fienen, M. N.: Three-Dimensional Distribution of Groundwater Residence Time Metrics in the Glaciated United States Using Metamodels Trained on General Numerical Simulation Models, *Water Resour. Res.*, 57(2), e2020WR027335, doi:10.1029/2020WR027335, 2021.
- Sundararajan, M. and Najmi, A.: The many shapley values for model explanation, in *37th International Conference on Machine Learning, ICML 2020*, vol. PartF16814, pp. 9210–9220., 2020.
- 795 Sundararajan, M., Taly, A. and Yan, Q.: Axiomatic attribution for deep networks, in *34th International Conference on Machine Learning, ICML 2017*, vol. 7, pp. 5109–5118., 2017.
- Teetor, N.: zeallot: Multiple, Unpacking, and Destructuring Assignment. R package version 0.1.0. <https://CRAN.R-project.org/package=zeallot>, 2018.
- Trinh, D. H. and Chui, T. F. M.: Assessing the hydrologic restoration of an urbanized area via an integrated distributed hydrological model, *Hydrol. Earth Syst. Sci.*, 17(12), 4789–4801, doi:10.5194/hess-17-4789-2013, 2013.
- 800 Ushey, K.: RcppRoll: Efficient Rolling / Windowed Operations. R package version 0.3.0. <https://CRAN.R-project.org/package=RcppRoll>, 2018.
- Wani, O., Beckers, J. V. L., Weerts, A. H. and Solomatine, D. P.: Residual uncertainty estimation using instance-based learning with applications to hydrologic forecasting, *Hydrol. Earth Syst. Sci.*, 21(8), 4021–4036, doi:10.5194/hess-21-4021-2017, 2017.
- 805 Yang, Y. and Chui, T. F. M.: Hydrologic Performance Simulation of Green Infrastructures: Why Data-Driven Modelling Can Be Useful?, in *New Trends in Urban Drainage Modelling*, pp. 480–484, Springer International Publishing., 2019.
- Yang, Y. and Chui, T. F. M.: Reliability Assessment of Machine Learning Models in Hydrological Predictions through Metamorphic Testing, *Water Resour. Res.*, 1–27, doi:10.1029/2020wr029471, 2021.
- Yong, C. F., McCarthy, D. T. and Deletic, A.: Predicting physical clogging of porous and permeable pavements, *J. Hydrol.*, 810 481, 48–55, doi:10.1016/j.jhydrol.2012.12.009, 2013.
- Zambrano-Bigiarini, M.: hydroGOF: Goodness-of-fit functions for comparison of simulated and observed hydrological time series R package version 0.4-0., <https://github.com/hzambran/hydroGOF>, <http://doi.org/10.5281/zenodo.840087>, 2020.
- Zeng, X. and Martinez, T. R.: Distribution-balanced stratified cross-validation for accuracy estimation, *J. Exp. Theor. Artif. Intell.*, 12(1), 1–12, doi:10.1080/095281300146272, 2000.
- 815 Zhang, K. and Chui, T. F. M.: A review on implementing infiltration-based green infrastructure in shallow groundwater environments: Challenges, approaches, and progress, *J. Hydrol.*, 579, 124089, doi:10.1016/j.jhydrol.2019.124089, 2019.
- Zhou, Q.: A Review of Sustainable Urban Drainage Systems Considering the Climate Change and Urbanization Impacts, *Water*, 6(4), 976–992, doi:10.3390/w6040976, 2014.