

**Comments on “Inclusion of flood diversion canal operation in the H08 hydrological model with a case study from the Chao Phraya River Basin – Part 1: Model development and validation”**

**Reply to RC2**

Integrating anthropogenic factors in GHMs is an important but tough job due to vast varied implementations of water conservation engineering and lack of data. In this study, Gopalan et al., developed a novel diversion module in a GHM H08 and tested its performances as well as other anthropogenic processes in a data-rich river catchment in Thailand. This module enhanced the robustness of GHMs in reproducing hydrological processes under human perturbations. Additionally, it provides the fundamental to evaluate the potential of flood control, which is a crucial topic regarding sustainable development under climate change. Although there are several issues needed to clarify before considering for publication, they do not affect the significance of this study and the interests of broad readership.

Thank you very much for your valuable comments regarding the scientific contribution of our work. We highly appreciate your review comments that provided valuable insights for further modifications of our current version.

The detailed point-by-point replies to all the major as well as the minor comments are given below. Once again thank you for enlightening us with your valuable comments and suggestions.

**Major comments**

1. Although the introduction underlines the importance of integrating water diversion in GHMs regarding floods control, the structure can be tighter. For instance, Paragraph 2 and 3 (Line 38 — 57) can be combined to introduce the demand of water diversion for flood control and its potential impacts on the water cycle. Paragraph 4 (Line 59 — 72) can be modified by reviewing relevant studies regarding flood control (water quality is trivial) and pointing out the limitation of hydrodynamic models in investigations of earth systems and the lack of water diversion in GHMs.

Thank you very much for your comment. According to the comment, the authors have tightened the structure of the Introduction section further to remove redundancies and improve the understanding. Once again thank you very much for the nice idea. **Line 27**

2. According to the Eq. 2, there may be a jump of  $D_{wet}$  (from  $Q_{min}$  to  $Q - Q_{env}$ ) when the  $Q$  is reaching the  $Q_{rivcap}$ . Is it what you expected?

Thank you very much for your valuable comment. It is true that there will be a jump in the daily  $D_{wet}$  values from  $Q_{cancap}$  to  $Q_{min}$  when the river discharge falls below the  $Q_{rivcap}$ . There will be another jump in  $D_{wet}$  values from  $Q_{min}$  to  $Q - Q_{env}$  when river discharge is approaching the environmental flow. However, this pattern of sudden changes in canal flow was also seen in the observed canal diversion flow values (please see the below figure for reference). We tried to replicate this observed pattern using the proposed canal operations.




Figure 1. Observed canal discharge for different canal systems during the wet season of 2016.

Additional, a minor issue is that the case  $Q < Q_{env}$  is not listed in Eq. 1 or 2.

Thank you very much for notifying the error that we made in Eq. 1 and 2. According to the comment, we have added the case of canal flow diversion when  $Q < Q_{env}$  in Eq. 1 and 2. **Line 147; Line 167**

3. The introduction of the diversion operation (Line 144 — 179) can be clarified more briefly. Instead of explaining each cases listed in Eq. 1 and 2, it is better to describe the logic of operation. The dry season for example, the operation strategy tries to meet the minimum flow diversion ( $Q_{min}$ ) on the premise of guaranteeing the environmental flow ( $Q_{env}$ ).

Thank you very much for your valuable comment. According to the comment, the logic of operation during the dry/wet season has been explained briefly rather than explaining each case listed in Eq. 1 and 2. Thank you for providing this nice idea. The modified sections are as follows:

*“The dry season is characterized by low rainfall that causes consequent water shortage for an extended period. To alleviate the water scarcity issues, water supply should be provided from the river channel to the neighbouring areas through diversion canals by preserving the environmental flow in the river channel. Based on this aspect, the operation of diversion canal systems during the dry season leads to the emergence of three cases concerning the environmental flow ( $Q_{env}$ ) required to be maintained in the river channel, which are expressed as follows:*

$$D_{dry} = \begin{cases} Q_{min} & ; \text{if } Q > Q_{env} \text{ and } (Q - Q_{min}) > Q_{env} \\ Q - Q_{env} & ; \text{if } Q > Q_{env} \text{ and } (Q - Q_{min}) < Q_{env} \\ 0 & ; \text{if } Q < Q_{env} \end{cases} \quad (1)$$

where  $D_{dry}$  is the daily water diversion during the dry season;  $Q_{min}$  is minimum flow diversion;  $Q_{env}$  is the environmental flow requirement; and  $Q$  is the daily river discharge at the origin of diversion. The first two cases in Eq. 1 represent two low flow scenarios (Supplementary Fig. S1a and b) and can be explained as follows: (i) the operation strategy tries to meet minimum flow diversion ( $Q_{min}$ ) on the premise of guaranteeing the environmental flow ( $Q_{env}$ ) in the river channel even after water diversion due to enough water availability, and (ii) the diversion criterion attempts to divert water ( $Q - Q_{env}$ ) that is smaller in quantity when compared to the  $Q_{min}$  to ensure the required the environmental flow requirement in the river channel due to the relatively low water availability. Using these diversion criteria, environmental flow is maintained in both cases. No flow is diverted to the canal if river discharge is lower than environmental flow, depicted as the third case in Eq. 1.” **Line 142**

*“The wet season is the period during which most of the annual rainfall is received. This high rainfall will eventually cause flooding in the neighbouring areas whenever river discharge exceeds the river channel carrying capacity. The diversion canals can divert this floodwater from the river channel and restore the river water level below the carrying capacity. From this perspective, five relevant cases can be identified for the operation of diversion canals during the wet season, as shown below:*

$$D_{wet} \left\{ \begin{array}{ll} Q_{cancap} & ; \text{if } Q > Q_{rivcap} \text{ and } (Q - Q_{cancap}) > Q_{env} \\ Q - Q_{env} & ; \text{if } Q > Q_{rivcap} \text{ and } (Q - Q_{cancap}) < Q_{env} \\ Q_{min} & ; \text{if } Q < Q_{rivcap} \text{ and } (Q - Q_{min}) > Q_{env} \\ Q - Q_{env} & ; \text{if } Q < Q_{rivcap} \text{ and } (Q - Q_{min}) < Q_{env} \\ 0 & ; \text{if } Q < Q_{env} \end{array} \right\} \quad (2)$$

where  $D_{wet}$  is the daily water diversion during the wet season;  $Q_{cancap}$  is the maximum canal carrying capacity; and  $Q_{rivcap}$  is the river channel carrying capacity. The first four cases in Eq. 2 are based on whether river discharge ( $Q$ ) is greater or smaller than the river channel carrying capacity ( $Q_{rivcap}$ ). The first two out of the four cases correspond to the flood flow scenario, where  $Q > Q_{rivcap}$  (Supplementary Fig. S1c and d). In the flood flow scenario, the operation strategy tries to divert the maximum possible amount of floodwater that is equivalent to the  $Q_{cancap}$  (Case I of Eq. 2) to keep the river flow below the  $Q_{rivcap}$ . However, at some point, the river flow in the main channel falls below the  $Q_{env}$  after the diversion of  $Q_{cancap}$ . In such instances, the remaining river discharge after meeting the environmental flow requirement ( $Q - Q_{env}$ ) is diverted into the canal instead of diverting the  $Q_{cancap}$  (Case II of Eq. 2). The last two out of the four cases represent non-flood flow scenario, where  $Q < Q_{rivcap}$  (Supplementary Fig. S1e and f). Although the river discharge lies below the  $Q_{rivcap}$  in the non-flood scenario, a minimum flow ( $Q_{min}$ ) is diverted from the main channel to reduce flooding at downstream locations (Case III of Eq. 2). If the diversion of  $Q_{min}$  to the canal reduces the river discharge below the  $Q_{env}$ , then a decreased quantity of water ( $Q - Q_{env}$ ) is diverted from the main channel rather than the  $Q_{min}$  to maintain the environmental flow in the river (Case IV of Eq. 2). Canal diversion remains zero during periods of environmental flow (Case V of Eq. 2).” **Line 162**

#### 4. Two issues are needed to clarify in the calibration.

- a) The model is calibrated by naturalized and regulated discharges. And irrigated discharge is mentioned as well. How was the discharge naturalized?

Thank you very much for your valuable comment. First of all, the authors would like to apologize for the confusion made by us. To avoid further confusion, we have used acronyms in the revised manuscript to represent all the five simulations carried out in this study. The conducted simulations are naturalized (NAT; no human influences), regulated (DAM; dam operation is enabled), irrigated (IRG; dam + water withdrawal for irrigation is

enabled), regionalized (REG; dam + water withdrawal for irrigation + regionalized canal scheme is enabled), and generalized (GEN; dam + water withdrawal for irrigation + generalized canal scheme is enabled) as shown in Table 3. The regulated simulation was renamed as “dam simulation” to provide more clarity in the revised manuscript. **Line 392; Line 834**

Regarding the model calibration, the H08 model was calibrated for pristine flow at Nakhon Sawan and further validated at various stations in the CPRB. To do so, initially, the “NAT” discharge was simulated by enabling the land surface hydrology and river routing modules of the H08 model, which do not include the effect of water infrastructures and thereby simulate the pristine flow. Further, this “NAT” simulation was compared with the ‘naturalized observed discharge’ at Nakhon Sawan (C.2 station). The ‘naturalized observed discharge’ at Nakhon Sawan was reconstructed by following Mateo et al. (2014). This was performed by adding the water stored in the two major dam reservoirs (Bhumibol and Sirikit) with the ‘observed discharge’ at Nakhon Sawan. These explanations were added to the manuscript (section 4) and supplementary material (section S4.1) to have more clarity. **Line 409 (manuscript); Line 76; Line 102 (supplementary material)**

Mateo, C. M., Hanasaki, N., Komori, D., Tanaka, K., Kiguchi, M., Champathong, A., Sukhapunnaphan, T., Yamazaki, D. and Oki, T.: Assessing the impacts of reservoir operation to floodplain inundation by combining hydrological, reservoir management, and hydrodynamic models, *Water Resour. Res.*, 50(9), 7245–7266, <https://doi.org/10.1002/2013WR014845>, 2014.

Is the regulated discharge equivalent to the irrigated discharge. What is the difference between the two and the observed discharge? Please provide more information.

In addition to the pristine flow prediction, the ability of the calibrated parameters in reproducing the observed discharge at the Nakhon Sawan was assessed. For this purpose, initially, the “DAM” discharge was simulated by enabling the reservoir operation module of the H08 model in addition to the land surface hydrology and river routing modules. Then, the “DAM” discharge and observed discharge were compared at Nakhon Sawan under the assumption that the “DAM” simulation could act as a proxy for the observed discharge although precisely not the case because the “DAM” discharge simulation does not include water abstraction for irrigation. Still, this comparison was made to evaluate the performance of the included reservoir operations in the model. Lastly, all six modules of

the H08 model were enabled to simulate the “IRG” discharge. In fact, this “IRG” simulation should correspond to the observed discharge because it includes most of the human interactions such as the reservoir operation and irrigation water abstraction. Therefore, the “IRG” simulation was compared with the observed discharge for final hydrograph reproducibility. Both the “DAM” and “IRG” discharge simulations were compared with the same observed discharge to examine the performance of different human interactions (reservoir operation and irrigation water abstraction) with the water cycle in terms of hydrograph reproducibility. The authors sincerely apologize for the confusion made by us and this comment really helped us to improve the clarity and understanding of the explanations regarding the naturalized (NAT), dam (DAM), and irrigated (IRG) discharge simulations in the manuscript. According to the comment, these explanations were added to the supplementary material (sections S4.2 and S4.3.2) to provide a better understanding.

**Line 102; Line 192**

b) The crop module is calibrated the crop module to meet the census irrigated discharge.

How is the contribution of diversion canal to irrigation withdrawal in CPRB?

Thank you very much for your comment. The actual contribution of diversion canal to irrigation withdrawal in CPRB is unknown because water taken from rivers and canals is seldom reported separately. Reported irrigation water withdrawal for Thailand is approximately 51.8 km<sup>3</sup>/year (FAO 2013; Kiguchi et al., 2021), of which nearly 75% (38.9 km<sup>3</sup>/year) is utilized in the CPRB based on the Water Resources Master Plan produced by the Office of the National Water Resources. This includes the contribution from both river and canal systems, whose individual share is unknown.

FAO (Food and Agriculture Organization): AQUASTAT Core Database. Food and Agriculture Organization of the United Nations. <http://www.fao.org/aquastat/en/>, Database accessed on 2021/04/19, 2013.

Kiguchi, M., Takata, K., Hanasaki, N., Archevarahuprok, B., Champathong, A., Ikoma, E., Jaikaeo, C., Kaewrueng, S., Kanae, S., Kazama, S., Kuraji, K., Matsumoto, K., Nakamura, S., Nguyen-Le, D., Noda, K., Piamsa-Nga, N., Raksapatcharawong, M., Rangsiwanichpong, P., Ritphring, S., Shirakawa, H., Somphong, C., Srisutham, M., Suanburi, D., Suanpaga, W., Tebakari, T., Trisurat, Y., Udo, K., Wongsa, S., Yamada, T., Yoshida, K., Kiatiwat, T. and Oki, T.: A review of climate-change impact and adaptation

studies for the water sector in Thailand, *Environ. Res. Lett.*, 16(2), 023004, <https://doi.org/10.1088/1748-9326/abce80>, 2021.

If it was significant, the calibrated irrigated discharge (no irrigation due to diversion) must be higher than the observations, correct?

In the H08 model, the crop growth module mainly simulates the crop calendar and crop yields. The irrigation water demand is estimated by the coupled module of the H08 model only when there is a soil moisture deficit. The soil moisture should maintain at 75% of field capacity for non-paddy crops and 100% of field capacity for paddy crops in irrigated fields. There will be a soil moisture deficit below this threshold and water is withdrawn from the river to meet this deficit. The simulated irrigation water withdrawal by the coupled model for the CPRB was nearly 26 km<sup>3</sup>/year (nearly 50% of water withdrawal for Thailand) in comparison with the observed withdrawal of 39 km<sup>3</sup>/year (Supplementary material S4.3.2). While simulating the irrigated (IRG) discharge, the canal operations were not enabled, and the agricultural water demand has met mainly by the water withdrawal from the river.

Once the canal operations were enabled, that simulation was referred to as the regionalized discharge (REG) in this study because it includes region-specific canal operation. During this canal operation, a huge amount of water is diverted from the river channel ( $\approx 13$  km<sup>3</sup>/year; Fig. 6) in which only 1.6 km<sup>3</sup>/year is utilized for irrigation due to the absence of irrigation supply data from canals. This amount is not significant compared with the simulated water withdrawal of 26 km<sup>3</sup>/year. Most of the remaining diverted water is returned to the river channel (9.6 km<sup>3</sup>/year) and the remainder is taken out of the basin or stored in retention areas (2 km<sup>3</sup>/year). This returned water to the river channel is further available for irrigation water abstraction because the order of water withdrawal to meet the agricultural water demand assumes that the priority should be given to the canal water supply. If the canal water supply is not meeting the water demand fully, the water is withdrawn from the river system to meet the demand gap. Due to this water withdrawal from rivers, the calibrated irrigated discharge will not be higher than the observations.

## 5. Several questions regarding the physical processes

- a) Do the canal network and the retention area affect the land surface processes? For example, does the retention area (1-m deep) maintain water during precipitation? Will surface runoff go to canals instead of going to the natural river channel?

Thank you very much for your comment. The retention areas will affect the land surface processes, but not the canal network. The retention areas are modeled in such a way that they receive runoff generated from precipitation in each grid based on their areal fraction during both dry and wet seasons. This runoff constitutes a part of retention pond storage and only the remaining storage capacity is available for the storage of diverted floodwater during the wet season. In the case of canal networks, it was assumed that the surface runoff will not go to the canals, and they only receive diverted water from the river network. These explanations on how the retention areas can affect the land surface processes were added to the manuscript to avoid confusion. **Line 204**

b) Is the assumption of retention storage cleaning (Line 178 — 179) reasonable? I guess that a part of the water might be loss through deep drainage.

Thank you very much for your comment. Of course, the evaporation of retention storage at the end of every normal year is an assumption for simplicity at this stage. In CPRB, the rainfed paddy croplands (retention areas in this study) situate in the low-lying area which is lower than the water level of the rivers and canals (Jamrussri et al., 2018; JICA, 2013). Therefore, pumping stations were constructed to drain the floodwater stored in the paddy fields to the canals immediately after the floods and further operated to drain water from canals to main rivers (JICA, 2013). This will prepare the paddy fields for cultivation and further storage of water if floods occur within the same year. However, this pumping process was not modelled in this study due to the challenges involved. We are further developing the operation scheme to include the pumping process for the quick withdrawal of the water stored in the retention areas to represent the real processes. In addition, as the reviewer stated, a part of the retention storage might be lost through percolation. However, due to limitations in the availability of such data, we assumed that the percolation loss will be negligible in the highly saturated paddy fields at the time of floods. A similar assumption was also made for the canal operations that the water will transfer without any loss and delay. To make these physical processes clearer to the readers, these explanations were added to the discussion (section 5) as the uncertainties and limitations involved in the study. Thank you very much for reminding us about this. **Line 555**

Jamrussri, S., Toda, Y. and Tsubaki, R.: Integrated flood countermeasures in the upper and middle Chao Phraya River Basin, *J. Appl. Water Eng. Res.*, 7(2), 143–155, <https://doi.org/10.1080/23249676.2018.1497559>, 2018.



JICA (Japan International Cooperation Agency): Project for the comprehensive flood management plan for the Chao Phraya River basin, Final report, Volume 1: Summary Report, CTI Engineering International Co., Ltd., Oriental Consultants Co., Ltd., Nippon Koei Co., Ltd., CTI Engineering Co., Ltd., available at: <https://openjicareport.jica.go.jp/pdf/12127205.pdf> (last access: 20 April 2021), September 2013.

Moreover, it is more proper to re-set the retention storage at the end of a hydrological year rather than a normal year?

If we reset the retention storage at the end of a hydrological year (March), the water will be kept in these retention areas until then and the paddy fields become not available for the cultivation of the second crop during the dry season (supplementary Fig. S4). Also, we believe that the retention pond or shallow and ill-managed storage cannot keep water until the end of the hydrological year (March). Therefore, due to the above-mentioned reasons as well as the immediate withdrawal of retention storage using pumps, we reset the retention storage at the end of a normal year rather than a hydrological year.

c) Canal water only can be withdrawn by neighbouring grid cells for irrigation. Does it imply that the spatial resolution of simulation will affect the results?

Thank you very much for your comment. Yes, the spatial resolution of the simulation will affect the results. In this study, for simplicity, 10% of diverted water is supplied to each of the nearby grid cells because our primary concern was flood control. Therefore, of course, we should change this fraction of ‘supply to near grids’ if we are performing the simulation on a finer/coarser resolution. One alternative way to overcome this issue is that we can finalize the ‘supply to near grids’ based on the water demand in each of the grid cells through which the canal passes as well the in the neighbouring grid cells. In such instances, it can be confirmed that the supplied water will be completely utilized. To make these physical processes clearer to the readers, these explanations were added to the discussion section as the uncertainties and limitations involved in the study. **Line 570**

d) Seems that the rain-fed cropland is assumed to be used as retention pond. Is it a universal assumption in the future global simulations? If so, will it affect the crop yield?

Thank you very much for your comment. In this study, we assumed that the rainfed cropland can be used as retention areas because, in Thailand, the rainfed cropland comprises low-lying paddy fields that are natural floodplains and cannot be cultivated during the rainy season because of flooding (Jamrussri et al., 2018). This assumption will affect the crop yield because the cropland is not available for cultivation until the beginning of the subsequent year due to the storage of floodwater. This is one of the limitations this study currently poses and that will be addressed in our future studies by considering the actual pumping process (please refer to the response of major comment 5b) in the canal operation scheme for the CPRB. However, this is not a universal assumption for future global applications. Being the rainfed cropland is not the required condition for retention areas. The most important land use for potential retention areas is the low-lying areas along rivers (floodplains) and canals. In addition, although the lakes/ponds could be partially filled with water during the wet season, they can also be used as retention areas based on available free space. For modelling, the geographic locations of possible retention areas (e.g., low-lying areas, lakes, ponds, wetlands, etc.) along with their depth and areal extents available for storage of floodwater specific to each area should be estimated. This information can be extracted from remotely sensed data such as general DEMs (e.g., MERIT DEM), satellite imageries (MODIS/LANDSAT), radar altimetry, as well as from literature although it is strenuous. In this study, the authors tried to propose a way to set parameters from simulations for the future global application (generalized canal scheme) rather than to claim that the model applies universally. These explanations were added to the discussion section to have more clarity. **Line 578**

Jamrussri, S., Toda, Y. and Tsubaki, R.: Integrated flood countermeasures in the upper and middle Chao Phraya River Basin, *J. Appl. Water Eng. Res.*, 7(2), 143–155, <https://doi.org/10.1080/23249676.2018.1497559>, 2018.

6. In Figure 7, the annual average discharge is employed to demonstrate the effect of flood control. I think it is more suitable to present the intra-annual fluctuations of discharge rather than the annual mean, isn't it?

Thank you very much for your valuable comment. We highly agree with your comment that it is better to present the intra-annual fluctuations of discharge to have a clear idea about the effect of canal operations on flood control. Therefore, according to the comment, we have depicted

the annual and seasonal variations of river discharge under various simulations in Fig. 7. Explanations were also added to support the modified Fig. 7 as follows:

*“Initially, the impact of canal systems and retention areas on reducing the annual average, wet season, and dry season discharges of the CPRB was analyzed. Fig. 7 shows the annual, wet season, and dry season discharges in the CPRB for various simulations averaged from 1980 to 2004. The maximum annual average discharge under the NAT simulation was approximately 850 m<sup>3</sup>/s in the basin (Fig. 7a1), which may lead to devastating impacts in the lower basin, including Bangkok City. The effect of reservoir operation on annual average discharge was negligible (Fig. 7b1). A marked reduction in discharge, with values ranging between 500 m<sup>3</sup>/s and 583 m<sup>3</sup>/s, occurred after enabling irrigation water abstraction (Fig. 7c1). The impact of water diversion on annual average discharge shows that diversion has a great potential for flood control in the lower CPRB (Fig. 7d1 and e1). In the REG simulation, the annual average discharge of the CPRB was approximately 523 m<sup>3</sup>/s, a reduction of 10% from the IRG simulation. In contrast, the GEN simulation portrayed a reduction of 28% in basin annual average discharge, compared with the IRG simulation.*

*The discharge reduction under various simulations during the wet season was very similar to the annual average flow reduction pattern except for the DAM simulation. Under the DAM simulation, remarkable discharge reduction was observed in the Ping, Nan, and Chao Phraya rivers (Fig. 7b2) due to the operation of upstream dam reservoirs of Bhumibol and Sirikit with an outlet discharge deduction of nearly 15%. The subsequent discharge simulations of IRG, REG, and GEN ones illustrated nearly 34%, 10%, and 26% reduction in the outlet discharge of the CPRB (Fig. 7c2-e2), which further revealed the dominance of wet season irrigation water abstraction and canal operations in the annual pattern. During the dry season, the outlet discharge was nearly 202 m<sup>3</sup>/s under the NAT simulation (Fig. 7a3), which was enhanced to 551 m<sup>3</sup>/s after enabling the reservoir operation (Fig. 7b3). Likewise the wet season, further reductions in discharge was noted in the river channel due to the irrigation water abstraction and canal operations (Fig. 7c3-e3). Overall, the canal operations significantly reduced the main channel discharge both annually and intra-annually.” **Line 472; Line 820***

7. The presentation skill can be further improved. I listed several suggestions below in ‘minor comments’, but not limited to them.

Thank you very much for your comment. According to the comment, the authors have thoroughly read the manuscript and it has been modified to improve the presentation wherever

necessary. In addition, the authors have addressed all the minor comments raised by the reviewer whose detailed responses can be seen in the below section. The authors are thankful to the reviewer for your thoughtful comments.

### **Minor comments**

1. Line 76: “have been generated by” —> “due to”

Response to comment No. 1: Thank you very much for your comment. According to the comment, “have been generated by” has been changed to “are due to”. **Line 79**

2. Line 110: Do  $0.5^\circ$  and one-day represent the finest resolution that the H08 can reach? If not, please remove it.

Response to comment No. 2: Thank you very much for your comment. In the H08 model,  $0.5^\circ \times 0.5^\circ$  and one day are the finest resolutions for standard global applications. However, the model was designed for application to any spatial resolution as we carried out in this study (a spatial resolution of 5 arcmins). Therefore, in order to avoid confusion, the sentence was rewritten as “*Each of the modules can run separately with standard spatial and temporal resolutions of  $0.5^\circ \times 0.5^\circ$  and one day, respectively, on a global scale*”. **Line 104**

3. Line 144: Please briefly describe the definition of dry/wet season.

Response to comment No. 3: Thank you very much for your comment. According to the comment, we have added a brief definition of dry/wet season as follows:

*“The dry season is characterized by low rainfall that causes consequent water shortage for an extended period.”* **Line 142**

*“The wet season is the period during which most of the annual rainfall is received.”* **Line 162**

4. Line 228 — 233: Please shortly explain what 5, 50, and 90 means in Q<sub>5</sub>, Q<sub>50</sub>, and Q<sub>90</sub> (% of quantile?).

Response to comment No. 4: Thank you very much for your comment. According to the comment, we have added a brief description of the Q<sub>5</sub>, Q<sub>50</sub>, and Q<sub>90</sub> indices as follows:

*“Q<sub>5</sub> value (the 95-percentile flow, which was equalled or exceeded for 5% of the flow record – a high flow representation)”* **Line 247**

*“Q<sub>50</sub> value (the 50-percentile flow, which was equalled or exceeded for 50% of the flow record – a medium flow representation)”* **Line 250**

*“Q<sub>90</sub> value (the 10-percentile flow, which was equalled or exceeded for 90% of the flow record – a low flow representation)”* **Line 253**

5. Line 279: “these 5 canals ...” It is properer to use word rather than Arabic numeral if the number is less than ten, or less than one hundred if the number represents for the amount of objects. Please check other places as well as the supplement.

Response to comment No. 5: Thank you very much for your comment. According to the comment, all the Arabic numeral representation of the numbers in the whole manuscript and supplementary file has changed to word format whenever the number is less than ten as well as less than one hundred if the number represents the amount of objects. Thank you for notifying this. The modifications are underlined throughout the manuscript and supplementary file. **Line 305 and elsewhere in manuscript and supplementary material**

6. Line 453 “a great potential” → “a great potential of flood control”.

Response to comment No. 6: Thank you very much for your comment. According to the comment, “a great potential” has been changed to “a great potential for flood control” for clarity. **Line 478**

7. Line 489: “values”: What values?

Response to comment No. 7: Thank you very much for your comment. According to the comment, “values” has been changed to “the diverted river flow values” for clarity. **Line 524**

8. Line 490: Remove “simulated”.

Response to comment No. 8: Thank you very much for your comment. According to the comment, “simulated” has been removed. **Line 524**

9. Figure 2: Modify the second sentence to “The green area denote the river basin”.

Response to comment No. 9: Thank you very much for your comment. According to the comment, “green coloured shape denotes the basin boundary” has been changed to “green area denotes the river basin”. **Line 802**

10. Please modify the y-label of Figure 8. It looks like number of days divided by 25 years.

Response to comment No. 10: Thank you very much for your comment. According to the comment, the y-label of Figure 8 has been modified to avoid confusion. **Line 823**

11. Supplement Line 150: Please add the unit of cropping intensity.

Response to comment No. 11: Thank you very much for your comment. As the reviewer knows, the cropping intensity can be explained as the number of times the crops are grown on a given agricultural land within a year. Cropping intensity of 1.5 means that on average 150% of the total irrigated cropland is used for cultivation (i.e., 100% of the land is used for cultivation of the first crop and 50% of the land is used for cultivation of the second crop). Since the cropping intensity is unitless, these explanations were added in the text for more clarity as follows:

*“Cropping intensity of 1.5 means that on average 150% of the total irrigated cropland is used for cultivation.”* **Line 170**